


DRAINAGE REPORT

**Murphy's Farm
Dracut, MA 01826
Map 22 / Lot 53 &
Map 39 / Block 53 / Lots 1-23**



344 North Main Street | Andover • MA 01810
(978) 416-0920 | www.civildci.com



APPLICANT:

**The Homes at Murphy's Farm, LLC
18 Cassimere Street
Andover, MA 01810**

SUBMITTED TO:

**Town of Dracut
11 Spring Park Ave.
Dracut, MA 01826**

ISSUED:

April 22, 2024

REVISED:

September 1, 2025

CDCI FILE #: 23-10524

DRAINAGE REPORT

Drainage Narrative

TAB 1

Figures

TAB 2

Figure 1 – Orthophoto
Figure 2 – USGS Map
Figure 3 – FEMA Flood Map
Figure 4 – NRCS Soils Map
Figure 5 – NHESP Map

Existing Conditions

TAB 3

2-Yr Storm Event Node Listing
10-Yr Storm Event
25-Yr Storm Event Node Listing
100-Yr Storm Event Node Listing

Proposed Conditions

TAB 4

2-Yr Storm Event Node Listing
10-Yr Storm Event
25-Yr Storm Event Node Listing
100-Yr Storm Event Node Listing

Supplemental Information

TAB 5

Checklist for Stormwater Report
Stormwater Calculations
Operations and Maintenance Program
Test Pit Soil Logs
Existing Watershed Plan
Proposed Watershed Plan

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

TAB 1

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

PROJECT DESCRIPTION

The applicant proposes to develop Murphy's Farm (Map 22, Lot 53 & Map 39, Block 53, Lots 1-23) in Dracut, MA into a 40B development consisting of 28 Multi-Family Dwellings containing a total of 268 units. The project consists of constructing $\pm 3,050$ -FT of new roadway along with associated infrastructure including driveways, landscaping, snow storage, parks, drainage facilities, and utilities. The project plans illustrate the proposal in detail including zoning, easements, construction details, roadway profile and provisions for utilities. Drainage will be collected and routed through a series of best management practices sized to address the MADEP Stormwater Management Standards as well as the local stormwater regulations.

SITE DESCRIPTION

The total area of the project site is approximately 33.30-AC and is located within the Residential-1 (R-1) zoning district. The site is located on the easterly side of Dracut, between Poppy Lane and Elizabeth Drive. A portion of the property has frontage on Wheeler Street in Methuen, MA. On-site resource areas include bordering vegetated wetlands (BVW), and vernal pools, both with associated setbacks. Elevations vary, ranging from approximately 114-FT along the frontage of Wheeler Street to a high of approximately 178-FT near Elizabeth Drive, at the boundary shared with 489 Wheeler Road. The resource areas were delineated by Norse Environmental Services in August 2015, and an ORAD was issued on January 26, 2016.

According to the Natural Resource Conservation Service Soil Survey for Essex County, Massachusetts, the on-site soils beyond the limit of the wetlands consist of the following soil types:

- Wareham Loamy Fine Sand Hydrologic Soil Group (HSG) A/D
- Swansea Muck, HSG B/D
- Freetown Muck, HSG B/D
- Hinkley Loamy Sand, HSG A
- Merrimac Fine Sandy Loam, HSG A
- Windsor Loamy Sand, HSG A
- Deerfield Loamy Fine Sand, HSG A
- Canton Fine Sandy Loam, HSG B
- Pits, gravel, Unranked
- Pits, quarry, Unranked
- Udorthents, Unranked

For the purposes of drainage calculations, portions of the Swansea Muck, Freetown Muck, Pits, and Udorthents map units were considered to be an HSG-A soil due to surrounding mapped soils, wetland delineation, and test pit results. Test pits were conducted by this office in December of 2023, April of 2024, December of 2024, and August of 2025 to determine soil texture and estimated seasonal high groundwater elevations. Test pit logs are provided under Tab 5 of this report. Additionally, permeameter testing compliant with ASTM D-5126 was performed to determine field saturated hydraulic conductivity. Finally, according to the Flood Insurance Rate Map for Essex County, Massachusetts Maps 25017C0163E and 25017C0161E, no part of this site is located within the 100-year base flood elevation.

SURFACE DRAINAGE

Pre-Development Condition

The project site has been disturbed and currently consists largely of bare sandy soil, however for drainage design purposes the existing cover types are assumed to be 'Woods' to mimic historic pre-development conditions. The pre-development condition consists of eight (8) watershed areas contributing to seven (7) design points. Design Point #1 (DP-1) receives runoff from EWA-1 and consists of overland flow through the northern wetland complex and into a culvert running across Wheeler Street. Design Point #3 (DP-3) receives runoff from EWA-3 and consists of overland flow directed off-site, towards #48 Rinzee Road.

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

Design Point #4 (DP-4) receives runoff from EWA-4 and consists of overland flow directed towards Poppy Lane. Design Point #5 (DP-5) receives runoff from EWA-5A and EWA-5B and consists of overland flow directed towards the Wetland Series 'A'. Runoff from EWA-5A first ponds in Wetland Series 'J' prior to flowing through a culvert that discharges to Wetland Series 'A'. This culvert was installed after the issuance of an Order of Conditions associated with DEP#145-1050, but is considered for pre-development drainage calculations. Design Point #6 (DP-6) receives runoff from EWA-6 and consists of overland flow directed towards Wetland Series 'B' and 'C'. Design Point #7 (DP-7) receives runoff from EWA-7 and consists of overland flow directed towards a wetland complex partially located on #4 Poppy Lane as well as a portion of the 'D' and 'E' series wetland complex. Design Point #8 (DP-8) receives runoff from EWA-8 and consists of overland flow directed towards series 'D' and 'E' wetland complex. Contributing areas to the Design Points are detailed in the following Table 1.

TABLE 1: EXISTING WATERSHED DESIGN POINT DETAILS

DESIGN POINT	AREA NAME	AREA (Acres)	Tc (min.)	CN
DP-1	EWA-1	5.11	13.7	38
DP-3	EWA-3	2.74	10.2	30
DP-4	EWA-4	2.77	28.1	30
DP-5	EWA-5A	1.14	14.9	30
	EWA-5B	10.52	19.5	32
DP-6	EWA-6	2.34	16.2	30
DP-7	EWA-7	5.96	14.3	30
DP-8	EWA-8	4.76	12.7	30

Post-Development Condition

The proposed project includes the construction of 28 Multi-Family Dwellings containing a total of 268 units. Other components include construction of $\pm 3,050$ -FT of roadway along with landscaping, snow storage, parks, drainage, utilities, and associated appurtenances. Drainage will be collected and routed through a series of best management practices sized to address the MADEP Stormwater Management Standards. Impervious area will include bituminous concrete pavement and rooftop areas, and totals 9.35-AC.

The post-development condition consists of thirteen (13) watershed areas discharging to seven (7) design points. DP-1 receives overland flow from PWA-1. DP-3 receives overland flow from PWA-3. DP-4 receives overland flow from PWA-4. DP-5 receives overland flow from PWA-5A as well as discharge from two infiltration basins (PWA-5B, PWA-5C, PWA-5F) and one subsurface system (PWA-5D). Runoff from PWA-5E is first routed through wetland series 'J' before discharging to wetland series 'A' through an existing culvert. The existing culvert will be upgraded to an 18" RCP in accordance with MassDOT design guidelines, and is modeled as part of the reach associated with Wetland Series 'J', flowing at approximately 20% capacity during the 100-Year storm. DP-6 receives overland flow from PWA-6. DP-7 receives overland flow from PWA-7B as well as flow from one infiltration basin (PWA-7A). DP-8 receives overland flow from PWA-8.

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

The design points are summarized in Table 2 below.

TABLE 2: PROPOSED WATERSHED DESIGN POINT DETAILS

DESIGN POINT	AREA NAME	AREA (Acres)	Tc (min.)	CN
DP-1	PWA-1	4.42	13.7	37
DP-3	PWA-3	0.20	6.6	30
DP-4	PWA-4	0.25	6.0	30
DP-5	PWA-5A	0.54	6.0	34
	PWA-5B	5.02	8.7	47
	PWA-5C	5.04	11.2	69
	PWA-5D	0.42	6.0	71
	PWA-5E	3.70	6.0	68
	PWA-5F	1.97	19.0	35
DP-6	PWA-6	1.88	9.6	30
DP-7	PWA-7A	8.81	6.0	66
	PWA-7B	1.49	13.2	33
DP-8	PWA-8A	1.60	8.5	31

Peak Discharge Comparison

As illustrated in the following tables, the impact of the proposed improvements has been mitigated through the use of best management practices including infiltration basins, subsurface infiltration and subsurface detention systems for up to and including the 100-year, 24-hour storm event.

Design Point #1 Peak Flows (CFS)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.00	0.06	0.45	3.53
Post-Development	0.00	0.05	0.39	3.05

Design Point #3 Peak Flows (CFS)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.00	0.00	0.02	0.51
Post-Development	0.00	0.00	0.00	0.04

Design Point #4 Peak Flows (CFS)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.00	0.00	0.02	0.40
Post-Development	0.00	0.00	0.00	0.05

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

Design Point #5 Peak Flows (CFS)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.00	0.03	0.23	3.31
Post-Development	0.00	0.02	0.11	3.03

Design Point #6 Peak Flows (CFS)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.00	0.00	0.02	0.40
Post-Development	0.00	0.00	0.02	0.36

Design Point #7 Peak Flows (CFS)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.00	0.00	0.05	1.05
Post-Development	0.00	0.00	0.03	0.56

Design Point #8 Peak Flows (CFS)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.00	0.00	0.04	0.71
Post-Development	0.00	0.00	0.02	0.40

Peak Volume Comparison

As illustrated in the following tables, the impact of the proposed improvements has been mitigated through the use of best management practices including infiltration basins, subsurface infiltration and subsurface detention systems for up to and including the 100-year, 24-hour storm event, with the exception of the 2- and 10-year storm events for Design Point 5, and the 10-year storm event for Design Point 7. A waiver to the Dracut Stormwater Regulations for maintaining peak volumes pre- and post-development has been requested.

Design Point #1 Volumes (Acre-Ft)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.000	0.048	0.161	0.551
Post-Development	0.000	0.033	0.121	0.440

Design Point #3 Volumes (Acre-Ft)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.000	0.000	0.015	0.127
Post-Development	0.000	0.000	0.001	0.009

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

Design Point #4 Volumes (Acre-Ft)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.000	0.000	0.015	0.128
Post-Development	0.000	0.000	0.001	0.012

Design Point #5 Volumes (Acre-Ft)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.000	0.007	0.115	0.687
Post-Development	0.006	0.028	0.79	0.433

Design Point #6 Volumes (Acre-Ft)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.000	0.000	0.013	0.108
Post-Development	0.000	0.000	0.010	0.087

Design Point #7 Volumes (Acre-Ft)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.000	0.000	0.033	0.275
Post-Development	0.000	0.002	0.020	0.105

Design Point #8 Volumes (Acre-Ft)

	2-YR	10-YR	25-YR	100-YR
	(3.08-IN)	(4.68-IN)	(5.94-IN)	(8.55-IN)
Pre-Development	0.000	0.000	0.026	0.220
Post-Development	0.000	0.000	0.012	0.085


METHODOLOGY

Drainage calculations were performed using the computer program HydroCAD by HydroCAD Software Solutions, LLC based upon Technical Release 20 (TR-20), developed by the NRCS. Drainage calculations were prepared for the 2-YR, 10-YR, 25-YR, and 100-YR Type III 24-hour storm events. Rainfall data corresponds with Cornell Extreme Precipitation. Curve numbers were generated using the information provided in TR-55 and the SCS Soils Survey. Infiltration rates for BMPs were determined by field testing in accordance with ASTM D-5126, with a factor of safety of 2 applied.

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

TAB 2



344 North Main Street | Andover • MA 01810
(978) 416-0920 | www.civildci.com

PROJECT:
**THE HOMES AT MURPHY'S
FARM LLC**


**18 CASSIMERE STREET
ANDOVER, MA 01810**

PREPARED FOR:
MURPHY'S FARM

DRACUT, MA 01826

**FIGURE 1:
ORTHO**

PREPARED BY: TJS
SCALE: 1"=500'
CDCI FILE #: 23-10524
DATE: MARCH 29, 2024



344 North Main Street | Andover • MA 01810
(978) 416-0920 | www.civildci.com

PROJECT:
**THE HOMES AT MURPHY'S
FARM LLC**


**18 CASSIMERE STREET
ANDOVER, MA 01810**


PREPARED FOR:
MURPHY'S FARM


DRACUT, MA 01826

**FIGURE 2:
USGS**

PREPARED BY: TJS
SCALE: 1"=500'
CDCI FILE #: 23-10524
DATE: MARCH 29, 2024










DRAINAGE REPORT

Murphy's Farm
Dracut, MA

TAB 3



23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 2

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Yr	Type III 24-hr		Default	24.00	1	3.08	2
2	10-Yr	Type III 24-hr		Default	24.00	1	4.68	2
3	25-Yr	Type III 24-hr		Default	24.00	1	5.94	2
4	100-Yr	Type III 24-hr		Default	24.00	1	8.55	2

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Printed 8/21/2025

Page 3

Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
1.53	39	>75% Grass cover, Good, HSG A (EWA-1, EWA-5B)
0.56	61	>75% Grass cover, Good, HSG B (EWA-1, EWA-5B)
31.87	30	Woods, Good, HSG A (EWA-1, EWA-3, EWA-4, EWA-5A, EWA-5B, EWA-6, EWA-7, EWA-8)
1.38	55	Woods, Good, HSG B (EWA-1, EWA-3, EWA-5B)
35.34	32	TOTAL AREA

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 4

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
33.40	HSG A	EWA-1, EWA-3, EWA-4, EWA-5A, EWA-5B, EWA-6, EWA-7, EWA-8
1.94	HSG B	EWA-1, EWA-3, EWA-5B
0.00	HSG C	
0.00	HSG D	
0.00	Other	
35.34		TOTAL AREA

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Yr Rainfall=3.08"

Printed 8/21/2025

Page 5

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEWA-1:	Runoff Area=5.11 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=400' Tc=13.7 min CN=38 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-3:	Runoff Area=2.74 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=300' Tc=10.2 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-4:	Runoff Area=2.77 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=788' Tc=28.1 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-5A:	Runoff Area=1.14 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=323' Tc=14.9 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-5B:	Runoff Area=10.52 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=715' Tc=19.5 min CN=32 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-6:	Runoff Area=2.34 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=611' Tc=16.2 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-7:	Runoff Area=5.96 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=456' Tc=14.3 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-8:	Runoff Area=4.76 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=370' Tc=12.7 min CN=30 Runoff=0.00 cfs 0.000 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.00' Max Vel=0.00 fps Inflow=0.00 cfs 0.000 af 12.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=2.98 cfs Outflow=0.00 cfs 0.000 af
Reach DP-1: Northern Wetland System Culvert	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-4: Poppy Ln	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-5: Wetland Series 'A'	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-6: Wetland Series 'B' & 'C'	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-7: #4 Poppy Ln	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-8: Wetland Series 'D' & 'E'	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af

23-10524 - Pre - R3*Type III 24-hr 2-Yr Rainfall=3.08"*

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 6

Total Runoff Area = 35.34 ac Runoff Volume = 0.000 af Average Runoff Depth = 0.00"
100.00% Pervious = 35.34 ac 0.00% Impervious = 0.00 ac

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 7

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEWA-1:	Runoff Area=5.11 ac 0.00% Impervious Runoff Depth=0.11" Flow Length=400' Tc=13.7 min CN=38 Runoff=0.08 cfs 0.048 af
SubcatchmentEWA-3:	Runoff Area=2.74 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=300' Tc=10.2 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-4:	Runoff Area=2.77 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=788' Tc=28.1 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-5A:	Runoff Area=1.14 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=323' Tc=14.9 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-5B:	Runoff Area=10.52 ac 0.00% Impervious Runoff Depth=0.01" Flow Length=715' Tc=19.5 min CN=32 Runoff=0.02 cfs 0.007 af
SubcatchmentEWA-6:	Runoff Area=2.34 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=611' Tc=16.2 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-7:	Runoff Area=5.96 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=456' Tc=14.3 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentEWA-8:	Runoff Area=4.76 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=370' Tc=12.7 min CN=30 Runoff=0.00 cfs 0.000 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.05' Max Vel=1.03 fps Inflow=0.02 cfs 0.007 af 12.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=2.98 cfs Outflow=0.02 cfs 0.007 af
Reach DP-1: Northern Wetland System Culvert	Inflow=0.08 cfs 0.048 af Outflow=0.08 cfs 0.048 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-4: Poppy Ln	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-5: Wetland Series 'A'	Inflow=0.02 cfs 0.007 af Outflow=0.02 cfs 0.007 af
Reach DP-6: Wetland Series 'B' & 'C'	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-7: #4 Poppy Ln	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-8: Wetland Series 'D' & 'E'	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af

23-10524 - Pre - R3*Type III 24-hr 10-Yr Rainfall=4.68"*

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 8

Total Runoff Area = 35.34 ac Runoff Volume = 0.056 af Average Runoff Depth = 0.02"
100.00% Pervious = 35.34 ac 0.00% Impervious = 0.00 ac

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 1

Summary for Subcatchment EWA-1:

Runoff = 0.08 cfs @ 14.84 hrs, Volume= 0.048 af, Depth= 0.11"

Routed to Reach DP-1 : Northern Wetland System Culvert


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.41	61	>75% Grass cover, Good, HSG B
0.52	39	>75% Grass cover, Good, HSG A
3.33	30	Woods, Good, HSG A
0.85	55	Woods, Good, HSG B
5.11	38	Weighted Average
5.11		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.5	50	0.0650	0.11		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.40"
6.2	350	0.0350	0.94		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
13.7	400	Total			

Subcatchment EWA-1:

Hydrograph



23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 2

Summary for Subcatchment EWA-3:

Runoff = 0.00 cfs @ 24.06 hrs, Volume= 0.000 af, Depth= 0.00"
 Routed to Reach DP-3 : #48 Rinzee Rd


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
2.70	30	Woods, Good, HSG A
0.04	55	Woods, Good, HSG B
2.74	30	Weighted Average
2.74		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.3	50	0.1000	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
3.9	250	0.0450	1.06		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
10.2	300	Total			

Subcatchment EWA-3:

Hydrograph



23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 3

Summary for Subcatchment EWA-4:


Runoff = 0.00 cfs @ 24.25 hrs, Volume= 0.000 af, Depth= 0.00"

Routed to Reach DP-4 : Poppy Ln

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
2.77	30	Woods, Good, HSG A
2.77		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	50	0.0600	0.11		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
4.5	250	0.0350	0.94		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
10.8	276	0.0072	0.42		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
5.1	212	0.0190	0.69		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
28.1	788	Total			

Subcatchment EWA-4:**Hydrograph**

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 4

Summary for Subcatchment EWA-5A:

Runoff = 0.00 cfs @ 24.11 hrs, Volume= 0.000 af, Depth= 0.00"
 Routed to Reach DP-5 : Wetland Series 'A'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
1.14	30	Woods, Good, HSG A
1.14		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.8	50	0.0330	0.09		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
3.4	146	0.0200	0.71		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
1.7	127	0.0620	1.24		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
14.9	323	Total			

Subcatchment EWA-5A:

Hydrograph



Summary for Subcatchment EWA-5B:

Runoff = 0.02 cfs @ 23.18 hrs, Volume= 0.007 af, Depth= 0.01"
 Routed to Reach 3R : 'Wetland Series J'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
8.87	30	Woods, Good, HSG A
0.49	55	Woods, Good, HSG B
1.01	39	>75% Grass cover, Good, HSG A
0.15	61	>75% Grass cover, Good, HSG B
10.52	32	Weighted Average
10.52		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.3	50	0.1000	0.13		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
5.2	251	0.0260	0.81		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
1.1	76	0.0520	1.14		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
5.1	168	0.0120	0.55		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
1.8	170	0.1000	1.58		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.5	715	Total			

Subcatchment EWA-5B:

Hydrograph



23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 7

Summary for Subcatchment EWA-6:

Runoff = 0.00 cfs @ 24.12 hrs, Volume= 0.000 af, Depth= 0.00"
 Routed to Reach DP-6 : Wetland Series 'B' & 'C'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
2.34	30	Woods, Good, HSG A
2.34		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.9	50	0.0800	0.12		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
5.8	282	0.0260	0.81		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
2.8	204	0.0590	1.21		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.7	75	0.1300	1.80		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
16.2	611	Total			

Subcatchment EWA-6:

Hydrograph



23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 8

Summary for Subcatchment EWA-7:


Runoff = 0.00 cfs @ 24.10 hrs, Volume= 0.000 af, Depth= 0.00"

Routed to Reach DP-7 : #4 Poppy Ln

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
5.96	30	Woods, Good, HSG A
5.96		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	50	0.0600	0.11		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.40"
6.6	406	0.0420	1.02		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
14.3	456	Total			

Subcatchment EWA-7:**Hydrograph**

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 9

Summary for Subcatchment EWA-8:

Runoff = 0.00 cfs @ 24.09 hrs, Volume= 0.000 af, Depth= 0.00"
 Routed to Reach DP-8 : Wetland Series 'D' & 'E'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
4.76	30	Woods, Good, HSG A
4.76		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.9	50	0.0800	0.12		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.40"
5.8	320	0.0340	0.92		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
12.7	370	Total			

Subcatchment EWA-8:

Hydrograph



Summary for Reach 3R: 'Wetland Series J'


[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 10.52 ac, 0.00% Impervious, Inflow Depth = 0.01" for 10-Yr event
Inflow = 0.02 cfs @ 23.18 hrs, Volume= 0.007 af
Outflow = 0.02 cfs @ 23.25 hrs, Volume= 0.007 af, Atten= 0%, Lag= 4.4 min
Routed to Reach DP-5 : Wetland Series 'A'

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Max. Velocity= 1.03 fps, Min. Travel Time= 2.3 min
Avg. Velocity= 0.86 fps, Avg. Travel Time= 2.8 min


Peak Storage= 2 cf @ 23.21 hrs
Average Depth at Peak Storage= 0.05' , Surface Width= 0.45'
Bank-Full Depth= 1.00' Flow Area= 0.8 sf, Capacity= 2.98 cfs

12.0" Round Pipe
n= 0.013
Length= 143.0' Slope= 0.0070 '
Inlet Invert= 137.05', Outlet Invert= 136.05'



Reach 3R: 'Wetland Series J'

Hydrograph




Summary for Reach DP-1: Northern Wetland System Culvert

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 5.11 ac, 0.00% Impervious, Inflow Depth = 0.11" for 10-Yr event
Inflow = 0.08 cfs @ 14.84 hrs, Volume= 0.048 af
Outflow = 0.08 cfs @ 14.84 hrs, Volume= 0.048 af, Atten= 0%, Lag= 0.0 min
Routed to nonexistent node 1R

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-1: Northern Wetland System Culvert

Summary for Reach DP-3: #48 Rinzee Rd


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.74 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.06 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.06 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min
Routed to nonexistent node 1R

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-3: #48 Rinzee Rd

Hydrograph




Summary for Reach DP-4: Poppy Ln

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.77 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.25 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.25 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min
Routed to nonexistent node 1R

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-4: Poppy Ln**Hydrograph**

Summary for Reach DP-5: Wetland Series 'A'


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 11.66 ac, 0.00% Impervious, Inflow Depth = 0.01" for 10-Yr event
Inflow = 0.02 cfs @ 23.25 hrs, Volume= 0.007 af
Outflow = 0.02 cfs @ 23.25 hrs, Volume= 0.007 af, Atten= 0%, Lag= 0.0 min
Routed to nonexistent node 1R

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-5: Wetland Series 'A'

Hydrograph




Summary for Reach DP-6: Wetland Series 'B' & 'C'

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.34 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.12 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.12 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min
Routed to nonexistent node 1R

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-6: Wetland Series 'B' & 'C'

Summary for Reach DP-7: #4 Poppy Ln


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 5.96 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.10 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.10 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min
Routed to nonexistent node 1R

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-7: #4 Poppy Ln

Hydrograph



Summary for Reach DP-8: Wetland Series 'D' & 'E'


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 4.76 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.09 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.09 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min
Routed to nonexistent node 1R

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-8: Wetland Series 'D' & 'E'

Hydrograph



23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Yr Rainfall=5.94"

Printed 8/21/2025

Page 9

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEWA-1:	Runoff Area=5.11 ac 0.00% Impervious Runoff Depth=0.38" Flow Length=400' Tc=13.7 min CN=38 Runoff=0.61 cfs 0.161 af
SubcatchmentEWA-3:	Runoff Area=2.74 ac 0.00% Impervious Runoff Depth=0.07" Flow Length=300' Tc=10.2 min CN=30 Runoff=0.02 cfs 0.015 af
SubcatchmentEWA-4:	Runoff Area=2.77 ac 0.00% Impervious Runoff Depth=0.07" Flow Length=788' Tc=28.1 min CN=30 Runoff=0.02 cfs 0.015 af
SubcatchmentEWA-5A:	Runoff Area=1.14 ac 0.00% Impervious Runoff Depth=0.07" Flow Length=323' Tc=14.9 min CN=30 Runoff=0.01 cfs 0.006 af
SubcatchmentEWA-5B:	Runoff Area=10.52 ac 0.00% Impervious Runoff Depth=0.12" Flow Length=715' Tc=19.5 min CN=32 Runoff=0.17 cfs 0.109 af
SubcatchmentEWA-6:	Runoff Area=2.34 ac 0.00% Impervious Runoff Depth=0.07" Flow Length=611' Tc=16.2 min CN=30 Runoff=0.02 cfs 0.013 af
SubcatchmentEWA-7:	Runoff Area=5.96 ac 0.00% Impervious Runoff Depth=0.07" Flow Length=456' Tc=14.3 min CN=30 Runoff=0.05 cfs 0.033 af
SubcatchmentEWA-8:	Runoff Area=4.76 ac 0.00% Impervious Runoff Depth=0.07" Flow Length=370' Tc=12.7 min CN=30 Runoff=0.04 cfs 0.026 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.16' Max Vel=2.07 fps Inflow=0.17 cfs 0.109 af 12.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=2.98 cfs Outflow=0.17 cfs 0.109 af
Reach DP-1: Northern Wetland System Culvert	Inflow=0.61 cfs 0.161 af Outflow=0.61 cfs 0.161 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.02 cfs 0.015 af Outflow=0.02 cfs 0.015 af
Reach DP-4: Poppy Ln	Inflow=0.02 cfs 0.015 af Outflow=0.02 cfs 0.015 af
Reach DP-5: Wetland Series 'A'	Inflow=0.18 cfs 0.115 af Outflow=0.18 cfs 0.115 af
Reach DP-6: Wetland Series 'B' & 'C'	Inflow=0.02 cfs 0.013 af Outflow=0.02 cfs 0.013 af
Reach DP-7: #4 Poppy Ln	Inflow=0.05 cfs 0.033 af Outflow=0.05 cfs 0.033 af
Reach DP-8: Wetland Series 'D' & 'E'	Inflow=0.04 cfs 0.026 af Outflow=0.04 cfs 0.026 af

23-10524 - Pre - R3*Type III 24-hr 25-Yr Rainfall=5.94"*

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 10

Total Runoff Area = 35.34 ac Runoff Volume = 0.378 af Average Runoff Depth = 0.13"
100.00% Pervious = 35.34 ac 0.00% Impervious = 0.00 ac

23-10524 - Pre - R3

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Yr Rainfall=8.55"

Printed 8/21/2025

Page 11

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEWA-1:	Runoff Area=5.11 ac 0.00% Impervious Runoff Depth=1.29" Flow Length=400' Tc=13.7 min CN=38 Runoff=4.06 cfs 0.551 af
SubcatchmentEWA-3:	Runoff Area=2.74 ac 0.00% Impervious Runoff Depth=0.55" Flow Length=300' Tc=10.2 min CN=30 Runoff=0.51 cfs 0.127 af
SubcatchmentEWA-4:	Runoff Area=2.77 ac 0.00% Impervious Runoff Depth=0.55" Flow Length=788' Tc=28.1 min CN=30 Runoff=0.40 cfs 0.128 af
SubcatchmentEWA-5A:	Runoff Area=1.14 ac 0.00% Impervious Runoff Depth=0.55" Flow Length=323' Tc=14.9 min CN=30 Runoff=0.20 cfs 0.053 af
SubcatchmentEWA-5B:	Runoff Area=10.52 ac 0.00% Impervious Runoff Depth=0.72" Flow Length=715' Tc=19.5 min CN=32 Runoff=2.84 cfs 0.634 af
SubcatchmentEWA-6:	Runoff Area=2.34 ac 0.00% Impervious Runoff Depth=0.55" Flow Length=611' Tc=16.2 min CN=30 Runoff=0.40 cfs 0.108 af
SubcatchmentEWA-7:	Runoff Area=5.96 ac 0.00% Impervious Runoff Depth=0.55" Flow Length=456' Tc=14.3 min CN=30 Runoff=1.05 cfs 0.275 af
SubcatchmentEWA-8:	Runoff Area=4.76 ac 0.00% Impervious Runoff Depth=0.55" Flow Length=370' Tc=12.7 min CN=30 Runoff=0.86 cfs 0.220 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.78' Max Vel=4.32 fps Inflow=2.84 cfs 0.634 af 12.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=2.98 cfs Outflow=2.82 cfs 0.634 af
Reach DP-1: Northern Wetland System Culvert	Inflow=4.06 cfs 0.551 af Outflow=4.06 cfs 0.551 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.51 cfs 0.127 af Outflow=0.51 cfs 0.127 af
Reach DP-4: Poppy Ln	Inflow=0.40 cfs 0.128 af Outflow=0.40 cfs 0.128 af
Reach DP-5: Wetland Series 'A'	Inflow=3.02 cfs 0.687 af Outflow=3.02 cfs 0.687 af
Reach DP-6: Wetland Series 'B' & 'C'	Inflow=0.40 cfs 0.108 af Outflow=0.40 cfs 0.108 af
Reach DP-7: #4 Poppy Ln	Inflow=1.05 cfs 0.275 af Outflow=1.05 cfs 0.275 af
Reach DP-8: Wetland Series 'D' & 'E'	Inflow=0.86 cfs 0.220 af Outflow=0.86 cfs 0.220 af

23-10524 - Pre - R3*Type III 24-hr 100-Yr Rainfall=8.55"*

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 12

Total Runoff Area = 35.34 ac Runoff Volume = 2.095 af Average Runoff Depth = 0.71"
100.00% Pervious = 35.34 ac 0.00% Impervious = 0.00 ac

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

TAB 4

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Printed 8/21/2025

Page 2

Project Notes

Rainfall events imported from "23-10524 - Pre - R1.hcp"

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 3

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Yr	Type III 24-hr		Default	24.00	1	3.08	2
2	10-Yr	Type III 24-hr		Default	24.00	1	4.68	2
3	25-Yr	Type III 24-hr		Default	24.00	1	5.94	2
4	100-Yr	Type III 24-hr		Default	24.00	1	8.55	2

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 4

Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
10.71	39	>75% Grass cover, Good, HSG A (PWA-1, PWA-3, PWA-5A, PWA-5B, PWA-5C, PWA-5D, PWA-5E, PWA-5F, PWA-6, PWA-7A, PWA-7B, PWA-8)
0.39	61	>75% Grass cover, Good, HSG B (PWA-1, PWA-5B, PWA-5C, PWA-5F)
0.86	30	Brush, Good, HSG A (PWA-4, PWA-6, PWA-7B, PWA-8)
6.57	98	Paved parking, HSG A (PWA-5B, PWA-5C, PWA-5D, PWA-5F, PWA-7A)
0.13	98	Paved parking, HSG B (PWA-5C)
3.11	98	Roofs, HSG A (PWA-5B, PWA-5C, PWA-5F, PWA-7A)
0.05	98	Roofs, HSG B (PWA-5F)
12.15	30	Woods, Good, HSG A (PWA-1, PWA-3, PWA-4, PWA-5A, PWA-5B, PWA-5C, PWA-5E, PWA-5F, PWA-6, PWA-7A, PWA-7B, PWA-8)
1.37	55	Woods, Good, HSG B (PWA-1, PWA-5C, PWA-5E, PWA-5F)
35.34	53	TOTAL AREA

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 5

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
33.40	HSG A	PWA-1, PWA-3, PWA-4, PWA-5A, PWA-5B, PWA-5C, PWA-5D, PWA-5E, PWA-5F, PWA-6, PWA-7A, PWA-7B, PWA-8
1.94	HSG B	PWA-1, PWA-5B, PWA-5C, PWA-5E, PWA-5F
0.00	HSG C	
0.00	HSG D	
0.00	Other	
35.34		TOTAL AREA

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Yr Rainfall=3.08"

Printed 8/21/2025

Page 6

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPWA-1:	Runoff Area=4.42 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=397' Tc=13.7 min CN=37 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-3:	Runoff Area=0.20 ac 0.00% Impervious Runoff Depth=0.00" Tc=6.0 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-4:	Runoff Area=0.25 ac 0.00% Impervious Runoff Depth=0.00" Tc=6.0 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-5A:	Runoff Area=0.54 ac 0.00% Impervious Runoff Depth=0.00" Tc=6.0 min CN=34 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-5B:	Runoff Area=5.02 ac 19.72% Impervious Runoff Depth=0.06" Flow Length=705' Tc=8.7 min CN=47 Runoff=0.04 cfs 0.024 af
SubcatchmentPWA-5C:	Runoff Area=5.04 ac 50.99% Impervious Runoff Depth=0.71" Flow Length=400' Tc=11.2 min CN=69 Runoff=2.97 cfs 0.299 af
SubcatchmentPWA-5D:	Runoff Area=0.42 ac 54.76% Impervious Runoff Depth=0.81" Tc=6.0 min CN=71 Runoff=0.35 cfs 0.028 af
SubcatchmentPWA-5E:	Runoff Area=1.97 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=230' Tc=19.0 min CN=35 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-5F:	Runoff Area=3.70 ac 49.73% Impervious Runoff Depth=0.67" Tc=6.0 min CN=68 Runoff=2.40 cfs 0.206 af
SubcatchmentPWA-6:	Runoff Area=1.88 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=175' Tc=9.6 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-7A:	Runoff Area=8.81 ac 48.01% Impervious Runoff Depth=0.58" Tc=6.0 min CN=66 Runoff=4.68 cfs 0.428 af
SubcatchmentPWA-7B:	Runoff Area=1.49 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=267' Tc=13.2 min CN=33 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-8:	Runoff Area=1.60 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=100' Tc=8.5 min CN=31 Runoff=0.00 cfs 0.000 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.00' Max Vel=0.00 fps Inflow=0.00 cfs 0.000 af 18.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=8.78 cfs Outflow=0.00 cfs 0.000 af
Reach DP-1: Northern Wetlands Culvert	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 2-Yr Rainfall=3.08"

Printed 8/21/2025

Page 7

Reach DP-4: Poppy LnInflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af**Reach DP-5: Wetland Series 'A'**Inflow=0.00 cfs 0.006 af
Outflow=0.00 cfs 0.006 af**Reach DP-6: Wetland Series 'B' & 'C'**Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af**Reach DP-7: #4 Poppy Ln**Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af**Reach DP-8: Wetland Series 'D' & 'E'**Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af**Pond Forebay-1: PCB-18**Peak Elev=141.50' Storage=0 cf Inflow=0.04 cfs 0.024 af
Outflow=0.04 cfs 0.024 af**Pond IB-1:**Peak Elev=139.13' Storage=386 cf Inflow=2.97 cfs 0.323 af
Discarded=2.84 cfs 0.323 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=2.84 cfs 0.323 af**Pond IB-2:**Peak Elev=137.22' Storage=140 cf Inflow=2.40 cfs 0.206 af
Discarded=2.31 cfs 0.206 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=2.31 cfs 0.206 af**Pond IB-3:**Peak Elev=136.07' Storage=711 cf Inflow=4.68 cfs 0.428 af
Discarded=4.11 cfs 0.428 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=4.11 cfs 0.428 af**Pond SUB-1: Subsurface System-1**Peak Elev=131.82' Storage=1,065 cf Inflow=0.35 cfs 0.028 af
Outflow=0.00 cfs 0.006 af**Total Runoff Area = 35.34 ac Runoff Volume = 0.986 af Average Runoff Depth = 0.33"**
72.10% Pervious = 25.48 ac 27.90% Impervious = 9.86 ac

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 8

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPWA-1:	Runoff Area=4.42 ac 0.00% Impervious Runoff Depth=0.09" Flow Length=397' Tc=13.7 min CN=37 Runoff=0.05 cfs 0.033 af
SubcatchmentPWA-3:	Runoff Area=0.20 ac 0.00% Impervious Runoff Depth=0.00" Tc=6.0 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-4:	Runoff Area=0.25 ac 0.00% Impervious Runoff Depth=0.00" Tc=6.0 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-5A:	Runoff Area=0.54 ac 0.00% Impervious Runoff Depth=0.03" Tc=6.0 min CN=34 Runoff=0.00 cfs 0.001 af
SubcatchmentPWA-5B:	Runoff Area=5.02 ac 19.72% Impervious Runoff Depth=0.43" Flow Length=705' Tc=8.7 min CN=47 Runoff=0.97 cfs 0.180 af
SubcatchmentPWA-5C:	Runoff Area=5.04 ac 50.99% Impervious Runoff Depth=1.73" Flow Length=400' Tc=11.2 min CN=69 Runoff=8.24 cfs 0.726 af
SubcatchmentPWA-5D:	Runoff Area=0.42 ac 54.76% Impervious Runoff Depth=1.88" Tc=6.0 min CN=71 Runoff=0.89 cfs 0.066 af
SubcatchmentPWA-5E:	Runoff Area=1.97 ac 0.00% Impervious Runoff Depth=0.05" Flow Length=230' Tc=19.0 min CN=35 Runoff=0.01 cfs 0.008 af
SubcatchmentPWA-5F:	Runoff Area=3.70 ac 49.73% Impervious Runoff Depth=1.66" Tc=6.0 min CN=68 Runoff=6.80 cfs 0.510 af
SubcatchmentPWA-6:	Runoff Area=1.88 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=175' Tc=9.6 min CN=30 Runoff=0.00 cfs 0.000 af
SubcatchmentPWA-7A:	Runoff Area=8.81 ac 48.01% Impervious Runoff Depth=1.51" Tc=6.0 min CN=66 Runoff=14.57 cfs 1.111 af
SubcatchmentPWA-7B:	Runoff Area=1.49 ac 0.00% Impervious Runoff Depth=0.02" Flow Length=267' Tc=13.2 min CN=33 Runoff=0.00 cfs 0.002 af
SubcatchmentPWA-8:	Runoff Area=1.60 ac 0.00% Impervious Runoff Depth=0.00" Flow Length=100' Tc=8.5 min CN=31 Runoff=0.00 cfs 0.000 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.04' Max Vel=0.87 fps Inflow=0.01 cfs 0.008 af 18.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=8.78 cfs Outflow=0.01 cfs 0.008 af
Reach DP-1: Northern Wetlands Culvert	Inflow=0.05 cfs 0.033 af Outflow=0.05 cfs 0.033 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.00 cfs 0.000 af Outflow=0.00 cfs 0.000 af

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 9

Reach DP-4: Poppy LnInflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af**Reach DP-5: Wetland Series 'A'**Inflow=0.02 cfs 0.028 af
Outflow=0.02 cfs 0.028 af**Reach DP-6: Wetland Series 'B' & 'C'**Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af**Reach DP-7: #4 Poppy Ln**Inflow=0.00 cfs 0.002 af
Outflow=0.00 cfs 0.002 af**Reach DP-8: Wetland Series 'D' & 'E'**Inflow=0.00 cfs 0.000 af
Outflow=0.00 cfs 0.000 af**Pond Forebay-1: PCB-18**Peak Elev=141.50' Storage=1 cf Inflow=0.97 cfs 0.180 af
Outflow=0.97 cfs 0.180 af**Pond IB-1:**Peak Elev=139.50' Storage=5,289 cf Inflow=8.99 cfs 0.905 af
Discarded=3.97 cfs 0.906 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=3.97 cfs 0.906 af**Pond IB-2:**Peak Elev=137.36' Storage=1,407 cf Inflow=6.80 cfs 0.510 af
Discarded=4.09 cfs 0.510 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=4.09 cfs 0.510 af**Pond IB-3:**Peak Elev=136.77' Storage=8,023 cf Inflow=14.57 cfs 1.111 af
Discarded=5.15 cfs 1.111 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=5.15 cfs 1.111 af**Pond SUB-1: Subsurface System-1**Peak Elev=132.84' Storage=2,388 cf Inflow=0.89 cfs 0.066 af
Outflow=0.01 cfs 0.018 af**Total Runoff Area = 35.34 ac Runoff Volume = 2.637 af Average Runoff Depth = 0.90"**
72.10% Pervious = 25.48 ac 27.90% Impervious = 9.86 ac

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 1

Summary for Subcatchment PWA-1:

Runoff = 0.05 cfs @ 15.11 hrs, Volume= 0.033 af, Depth= 0.09"
 Routed to Reach DP-1 : Northern Wetlands Culvert


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.14	61	>75% Grass cover, Good, HSG B
0.18	39	>75% Grass cover, Good, HSG A
3.08	30	Woods, Good, HSG A
1.02	55	Woods, Good, HSG B
4.42	37	Weighted Average
4.42		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.5	50	0.0650	0.11		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.40"
6.2	347	0.0350	0.94		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
13.7	397	Total			

Subcatchment PWA-1:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 2

Summary for Subcatchment PWA-3:

Runoff = 0.00 cfs @ 24.02 hrs, Volume= 0.000 af, Depth= 0.00"
 Routed to Reach DP-3 : #48 Rinzee Rd


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.01	39	>75% Grass cover, Good, HSG A
0.19	30	Woods, Good, HSG A
0.20	30	Weighted Average
0.20		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PWA-3:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 3

Summary for Subcatchment PWA-4:

Runoff = 0.00 cfs @ 24.02 hrs, Volume= 0.000 af, Depth= 0.00"

Routed to Reach DP-4 : Poppy Ln


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.11	30	Brush, Good, HSG A
0.14	30	Woods, Good, HSG A
0.25	30	Weighted Average
0.25		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PWA-4:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 4

Summary for Subcatchment PWA-5A:

Runoff = 0.00 cfs @ 17.19 hrs, Volume= 0.001 af, Depth= 0.03"
Routed to Reach DP-5 : Wetland Series 'A'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.33	30	Woods, Good, HSG A
0.21	39	>75% Grass cover, Good, HSG A
0.54	34	Weighted Average
0.54		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PWA-5A:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 5

Summary for Subcatchment PWA-5B:


Runoff = 0.97 cfs @ 12.34 hrs, Volume= 0.180 af, Depth= 0.43"
 Routed to Pond Forebay-1 : PCB-18

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.15	61	>75% Grass cover, Good, HSG B
1.41	39	>75% Grass cover, Good, HSG A
2.47	30	Woods, Good, HSG A
0.14	98	Roofs, HSG A
0.85	98	Paved parking, HSG A
5.02	47	Weighted Average
4.03		80.28% Pervious Area
0.99		19.72% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.3	50	0.0360	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.40"
0.3	60	0.0400	3.00		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
1.1	265	0.0750	4.11		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
3.0	330	0.0150	1.84		Shallow Concentrated Flow, Grassed Waterway Kv= 15.0 fps
8.7	705	Total			

Subcatchment PWA-5B:



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 7

Summary for Subcatchment PWA-5C:


Runoff = 8.24 cfs @ 12.17 hrs, Volume= 0.726 af, Depth= 1.73"
 Routed to Pond IB-1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
2.22	39	>75% Grass cover, Good, HSG A
0.06	61	>75% Grass cover, Good, HSG B
0.11	30	Woods, Good, HSG A
0.08	55	Woods, Good, HSG B
0.08	98	Roofs, HSG A
2.36	98	Paved parking, HSG A
0.13	98	Paved parking, HSG B
5.04	69	Weighted Average
2.47		49.01% Pervious Area
2.57		50.99% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.9	50	0.1000	0.29		Sheet Flow, Grass: Short n= 0.150 P2= 3.40"
8.3	350	0.0100	0.70		Shallow Concentrated Flow, Short Grass Pasture Kv= 7.0 fps
11.2	400	Total			

Subcatchment PWA-5C:



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 9

Summary for Subcatchment PWA-5D:

Runoff = 0.89 cfs @ 12.10 hrs, Volume= 0.066 af, Depth= 1.88"
Routed to Pond SUB-1 : Subsurface System-1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.19	39	>75% Grass cover, Good, HSG A
0.23	98	Paved parking, HSG A
0.42	71	Weighted Average
0.19		45.24% Pervious Area
0.23		54.76% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PWA-5D:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 10

Summary for Subcatchment PWA-5E:

Runoff = 0.01 cfs @ 15.87 hrs, Volume= 0.008 af, Depth= 0.05"
 Routed to Reach 3R : 'Wetland Series J'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.42	39	>75% Grass cover, Good, HSG A
1.34	30	Woods, Good, HSG A
0.21	55	Woods, Good, HSG B
1.97	35	Weighted Average
1.97		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.8	50	0.0100	0.05		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
0.4	30	0.0600	1.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
2.6	110	0.0200	0.71		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
0.2	40	0.3700	3.04		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
19.0	230	Total			

Subcatchment PWA-5E:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 11

Summary for Subcatchment PWA-5F:

Runoff = 6.80 cfs @ 12.10 hrs, Volume= 0.510 af, Depth= 1.66"
 Routed to Pond IB-2 :


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.19	30	Woods, Good, HSG A
0.06	55	Woods, Good, HSG B
1.57	39	>75% Grass cover, Good, HSG A
0.04	61	>75% Grass cover, Good, HSG B
1.10	98	Roofs, HSG A
0.05	98	Roofs, HSG B
0.69	98	Paved parking, HSG A
3.70	68	Weighted Average
1.86		50.27% Pervious Area
1.84		49.73% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PWA-5F:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 12

Summary for Subcatchment PWA-6:

Runoff = 0.00 cfs @ 24.05 hrs, Volume= 0.000 af, Depth= 0.00"
 Routed to Reach DP-6 : Wetland Series 'B' & 'C'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.06	39	>75% Grass cover, Good, HSG A
1.56	30	Woods, Good, HSG A
0.26	30	Brush, Good, HSG A
1.88	30	Weighted Average
1.88		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	50	0.0600	0.11		Sheet Flow,
					Woods: Light underbrush n= 0.400 P2= 3.40"
1.9	125	0.0500	1.12		Shallow Concentrated Flow,
					Woodland Kv= 5.0 fps
9.6	175	Total			

Subcatchment PWA-6:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 13

Summary for Subcatchment PWA-7A:

Runoff = 14.57 cfs @ 12.10 hrs, Volume= 1.111 af, Depth= 1.51"
Routed to Pond IB-3 :


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.97	30	Woods, Good, HSG A
3.61	39	>75% Grass cover, Good, HSG A
1.79	98	Roofs, HSG A
2.44	98	Paved parking, HSG A
8.81	66	Weighted Average
4.58		51.99% Pervious Area
4.23		48.01% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

Subcatchment PWA-7A:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 14

Summary for Subcatchment PWA-7B:

Runoff = 0.00 cfs @ 21.81 hrs, Volume= 0.002 af, Depth= 0.02"

Routed to Reach DP-7 : #4 Poppy Ln


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
0.53	30	Woods, Good, HSG A
0.57	39	>75% Grass cover, Good, HSG A
0.39	30	Brush, Good, HSG A
1.49	33	Weighted Average
1.49		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.2	50	0.0300	0.08		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
3.0	217	0.0600	1.22		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
13.2	267	Total			

Subcatchment PWA-7B:

Hydrograph



23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 15

Summary for Subcatchment PWA-8:

Runoff = 0.00 cfs @ 24.00 hrs, Volume= 0.000 af, Depth= 0.00"
 Routed to Reach DP-8 : Wetland Series 'D' & 'E'


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-Yr Rainfall=4.68"

Area (ac)	CN	Description
1.24	30	Woods, Good, HSG A
0.26	39	>75% Grass cover, Good, HSG A
0.10	30	Brush, Good, HSG A
1.60	31	Weighted Average
1.60		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.0	50	0.0200	0.10		Sheet Flow, Grass: Dense n= 0.240 P2= 3.40"
0.5	50	0.1200	1.73		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
8.5	100	Total			

Subcatchment PWA-8:

Hydrograph



Summary for Reach 3R: 'Wetland Series J'


[52] Hint: Inlet/Outlet conditions not evaluated

Inflow Area = 1.97 ac, 0.00% Impervious, Inflow Depth = 0.05" for 10-Yr event
Inflow = 0.01 cfs @ 15.87 hrs, Volume= 0.008 af
Outflow = 0.01 cfs @ 15.96 hrs, Volume= 0.008 af, Atten= 0%, Lag= 4.8 min
Routed to Reach DP-5 : Wetland Series 'A'


Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
Max. Velocity= 0.87 fps, Min. Travel Time= 2.8 min
Avg. Velocity= 0.79 fps, Avg. Travel Time= 3.0 min

Peak Storage= 2 cf @ 15.91 hrs
Average Depth at Peak Storage= 0.04' , Surface Width= 0.48'
Bank-Full Depth= 1.50' Flow Area= 1.8 sf, Capacity= 8.78 cfs

18.0" Round Pipe
n= 0.013
Length= 143.0' Slope= 0.0070 '
Inlet Invert= 136.00', Outlet Invert= 135.00'



Reach 3R: 'Wetland Series J'




Summary for Reach DP-1: Northern Wetlands Culvert

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 4.42 ac, 0.00% Impervious, Inflow Depth = 0.09" for 10-Yr event
Inflow = 0.05 cfs @ 15.11 hrs, Volume= 0.033 af
Outflow = 0.05 cfs @ 15.11 hrs, Volume= 0.033 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-1: Northern Wetlands Culvert

Summary for Reach DP-3: #48 Rinzee Rd


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.20 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.02 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.02 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-3: #48 Rinzee Rd

Hydrograph



Summary for Reach DP-4: Poppy Ln


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.25 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.02 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.02 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-4: Poppy Ln

Hydrograph




Summary for Reach DP-5: Wetland Series 'A'

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 16.69 ac, 33.73% Impervious, Inflow Depth > 0.02" for 10-Yr event
Inflow = 0.02 cfs @ 17.17 hrs, Volume= 0.028 af
Outflow = 0.02 cfs @ 17.17 hrs, Volume= 0.028 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-5: Wetland Series 'A'

Summary for Reach DP-6: Wetland Series 'B' & 'C'


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 1.88 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.05 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.05 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-6: Wetland Series 'B' & 'C'

Hydrograph



Summary for Reach DP-7: #4 Poppy Ln


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 10.30 ac, 41.07% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 21.81 hrs, Volume= 0.002 af
Outflow = 0.00 cfs @ 21.81 hrs, Volume= 0.002 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-7: #4 Poppy Ln

Hydrograph



Summary for Reach DP-8: Wetland Series 'D' & 'E'


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 1.60 ac, 0.00% Impervious, Inflow Depth = 0.00" for 10-Yr event
Inflow = 0.00 cfs @ 24.00 hrs, Volume= 0.000 af
Outflow = 0.00 cfs @ 24.00 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs

Reach DP-8: Wetland Series 'D' & 'E'

Hydrograph



23-10524 - Post - R7

Type III 24-hr 10-Yr Rainfall=4.68"

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 25

Summary for Pond Forebay-1: PCB-18

[44] Hint: Outlet device #1 is below defined storage

Inflow Area = 5.02 ac, 19.72% Impervious, Inflow Depth = 0.43" for 10-Yr event
 Inflow = 0.97 cfs @ 12.34 hrs, Volume= 0.180 af
 Outflow = 0.97 cfs @ 12.34 hrs, Volume= 0.180 af, Atten= 0%, Lag= 0.0 min
 Primary = 0.97 cfs @ 12.34 hrs, Volume= 0.180 af
 Routed to Pond IB-1 :

Routing by Stor-Ind method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Peak Elev= 141.50' @ 12.34 hrs Surf.Area= 561 sf Storage= 1 cf

Plug-Flow detention time= 0.0 min calculated for 0.179 af (100% of inflow)
 Center-of-Mass det. time= 0.0 min (946.2 - 946.2)

Volume	Invert	Avail.Storage	Storage Description
#1	141.50'	896 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
141.50	560	0	0
142.00	890	363	363
142.50	1,242	533	896

Device	Routing	Invert	Outlet Devices
#1	Primary	138.22'	15.0" Round Culvert L= 42.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 138.22' / 138.00' S= 0.0052 '/' Cc= 0.900 n= 0.013, Flow Area= 1.23 sf
#2	Primary	141.50'	24.0" x 24.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads


Primary OutFlow Max=7.60 cfs @ 12.34 hrs HW=141.50' (Free Discharge)

1=Culvert (Inlet Controls 7.60 cfs @ 6.20 fps)

2=Orifice/Grate (Weir Controls 0.00 cfs @ 0.12 fps)

Pond Forebay-1: PCB-18

Hydrograph



Summary for Pond IB-1:

[79] Warning: Submerged Pond Forebay-1 Primary device # 1 INLET by 1.28'

Inflow Area = 10.06 ac, 35.39% Impervious, Inflow Depth = 1.08" for 10-Yr event
 Inflow = 8.99 cfs @ 12.17 hrs, Volume= 0.905 af
 Outflow = 3.97 cfs @ 12.53 hrs, Volume= 0.906 af, Atten= 56%, Lag= 21.4 min
 Discarded = 3.97 cfs @ 12.53 hrs, Volume= 0.906 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach DP-5 : Wetland Series 'A'
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach 3R : 'Wetland Series J'

Routing by Stor-Ind method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs / 3
 Peak Elev= 139.50' @ 12.53 hrs Surf.Area= 13,908 sf Storage= 5,289 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)
 Center-of-Mass det. time= 7.4 min (883.5 - 876.1)

Volume	Invert	Avail.Storage	Storage Description
#1	139.10'	75,588 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
139.10	12,689	0	0
140.00	15,447	12,661	12,661
141.00	18,355	16,901	29,562
142.00	23,617	20,986	50,548
143.00	26,463	25,040	75,588

Device	Routing	Invert	Outlet Devices
#1	Discarded	139.10'	12.340 in/hr Exfiltration over Surface area
#2	Primary	139.10'	12.0" Round Culvert L= 100.9' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.10' / 138.60' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 2	140.00'	2.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	140.75'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 2	141.75'	15.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Device 5	141.90'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#7	Secondary	142.00'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 28

Discarded OutFlow Max=3.97 cfs @ 12.53 hrs HW=139.50' (Free Discharge)

↑1=Exfiltration (Exfiltration Controls 3.97 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=139.10' (Free Discharge)

↑2=Culvert (Controls 0.00 cfs)

↑3=Orifice/Grate (Controls 0.00 cfs)

↑4=Orifice/Grate (Controls 0.00 cfs)


↑5=Orifice/Grate (Controls 0.00 cfs)

↑6=Orifice/Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=139.10' (Free Discharge)

↑7=Broad-Crested Rectangular Weir(Controls 0.00 cfs)

Pond IB-1:



Summary for Pond IB-2:

Inflow Area = 3.70 ac, 49.73% Impervious, Inflow Depth = 1.66" for 10-Yr event
 Inflow = 6.80 cfs @ 12.10 hrs, Volume= 0.510 af
 Outflow = 4.09 cfs @ 12.23 hrs, Volume= 0.510 af, Atten= 40%, Lag= 7.7 min
 Discarded = 4.09 cfs @ 12.23 hrs, Volume= 0.510 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach DP-5 : Wetland Series 'A'
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach DP-5 : Wetland Series 'A'

Routing by Stor-Ind method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Peak Elev= 137.36' @ 12.23 hrs Surf.Area= 8,915 sf Storage= 1,407 cf

Plug-Flow detention time= 2.0 min calculated for 0.509 af (100% of inflow)
 Center-of-Mass det. time= 2.0 min (858.7 - 856.7)

Volume	Invert	Avail.Storage	Storage Description
#1	137.20'	29,965 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
137.20	8,663	0	0
138.00	9,922	7,434	7,434
140.00	12,609	22,531	29,965

Device	Routing	Invert	Outlet Devices
#1	Discarded	137.20'	19.800 in/hr Exfiltration over Surface area
#2	Primary	137.00'	12.0" Round Culvert L= 117.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 137.00' / 136.41' S= 0.0050 ' / Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#3	Device 2	137.70'	4.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	138.50'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 3	138.80'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	139.00'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 30

Discarded OutFlow Max=4.09 cfs @ 12.23 hrs HW=137.36' (Free Discharge)

↑ **1=Exfiltration** (Exfiltration Controls 4.09 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=137.20' (Free Discharge)

↑ **2=Culvert** (Passes 0.00 cfs of 0.12 cfs potential flow)

↑ **3=Orifice/Grate** (Controls 0.00 cfs)

↑ **5=Orifice/Grate** (Controls 0.00 cfs)


↑ **4=Orifice/Grate** (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=137.20' (Free Discharge)

↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond IB-2:

Hydrograph



23-10524 - Post - R7

Type III 24-hr 10-Yr Rainfall=4.68"

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 31

Summary for Pond IB-3:

Inflow Area = 8.81 ac, 48.01% Impervious, Inflow Depth = 1.51" for 10-Yr event
 Inflow = 14.57 cfs @ 12.10 hrs, Volume= 1.111 af
 Outflow = 5.15 cfs @ 12.44 hrs, Volume= 1.111 af, Atten= 65%, Lag= 20.6 min
 Discarded = 5.15 cfs @ 12.44 hrs, Volume= 1.111 af
 Primary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach DP-7 : #4 Poppy Ln
 Secondary = 0.00 cfs @ 5.00 hrs, Volume= 0.000 af
 Routed to Reach DP-7 : #4 Poppy Ln

Routing by Stor-Ind method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs / 3
 Peak Elev= 136.77' @ 12.44 hrs Surf.Area= 11,240 sf Storage= 8,023 cf

Plug-Flow detention time= 9.4 min calculated for 1.109 af (100% of inflow)
 Center-of-Mass det. time= 9.5 min (871.8 - 862.2)

Volume	Invert	Avail.Storage	Storage Description
#1	136.00'	148,441 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
136.00	9,701	0	0
138.00	13,719	23,420	23,420
140.00	18,204	31,923	55,343
142.00	23,158	41,362	96,705
144.00	28,578	51,736	148,441

Device	Routing	Invert	Outlet Devices
#1	Discarded	136.00'	19.800 in/hr Exfiltration over Surface area
#2	Primary	135.00'	12.0" Round Culvert L= 75.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 135.00' / 134.25' S= 0.0100 ' S= 0.0100 ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#3	Device 2	138.20'	1.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 2	139.50'	12.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#5	Device 4	142.00'	48.0" x 48.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#6	Secondary	143.00'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65 2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 10-Yr Rainfall=4.68"

Printed 8/21/2025

Page 32

Discarded OutFlow Max=5.15 cfs @ 12.44 hrs HW=136.77' (Free Discharge)

↑ **1=Exfiltration** (Exfiltration Controls 5.15 cfs)

Primary OutFlow Max=0.00 cfs @ 5.00 hrs HW=136.00' (Free Discharge)

↑ **2=Culvert** (Passes 0.00 cfs of 2.11 cfs potential flow)

↑ **3=Orifice/Grate** (Controls 0.00 cfs)


↑ **4=Orifice/Grate** (Controls 0.00 cfs)

↑ **5=Orifice/Grate** (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 5.00 hrs HW=136.00' (Free Discharge)

↑ **6=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond IB-3:



Summary for Pond SUB-1: Subsurface System-1

Inflow Area = 0.42 ac, 54.76% Impervious, Inflow Depth = 1.88" for 10-Yr event
 Inflow = 0.89 cfs @ 12.10 hrs, Volume= 0.066 af
 Outflow = 0.01 cfs @ 23.98 hrs, Volume= 0.018 af, Atten= 99%, Lag= 713.0 min
 Primary = 0.01 cfs @ 23.98 hrs, Volume= 0.018 af
 Routed to Reach DP-5 : Wetland Series 'A'

Routing by Stor-Ind method, Time Span= 5.00-32.00 hrs, dt= 0.05 hrs
 Peak Elev= 132.84' @ 23.98 hrs Surf.Area= 1,300 sf Storage= 2,388 cf

Plug-Flow detention time= 630.7 min calculated for 0.018 af (28% of inflow)
 Center-of-Mass det. time= 494.0 min (1,342.6 - 848.6)


Volume	Invert	Avail.Storage	Storage Description
#1	131.00'	5,200 cf	17 x 10 Chambers (Prismatic) Listed below (Recalc) x 10

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
131.00	130	0	0
135.00	130	520	520

Device	Routing	Invert	Outlet Devices
#1	Primary	131.00'	6.0" Round Culvert L= 48.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 131.00' / 130.76' S= 0.0050 '/' Cc= 0.900 n= 0.013, Flow Area= 0.20 sf
#2	Device 1	131.00'	0.2" Vert. Orifice/Grate X 4.00 C= 0.600 Limited to weir flow at low heads
#3	Device 1	131.75'	0.2" Vert. Orifice/Grate X 4.00 C= 0.600 Limited to weir flow at low heads
#4	Device 1	132.50'	0.2" Vert. Orifice/Grate X 4.00 C= 0.600 Limited to weir flow at low heads
#5	Device 1	133.25'	0.2" Vert. Orifice/Grate X 4.00 C= 0.600 Limited to weir flow at low heads
#6	Device 1	133.80'	6.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads

Primary OutFlow Max=0.01 cfs @ 23.98 hrs HW=132.84' (Free Discharge)

1=Culvert (Passes 0.01 cfs of 0.86 cfs potential flow)
 2=Orifice/Grate (Orifice Controls 0.01 cfs @ 6.51 fps)
 3=Orifice/Grate (Orifice Controls 0.00 cfs @ 5.00 fps)
 4=Orifice/Grate (Orifice Controls 0.00 cfs @ 2.76 fps)
 5=Orifice/Grate (Controls 0.00 cfs)
 6=Orifice/Grate (Controls 0.00 cfs)

Pond SUB-1: Subsurface System-1

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Yr Rainfall=5.94"

Printed 8/21/2025

Page 10

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPWA-1:	Runoff Area=4.42 ac 0.00% Impervious Runoff Depth=0.33" Flow Length=397' Tc=13.7 min CN=37 Runoff=0.39 cfs 0.121 af
SubcatchmentPWA-3:	Runoff Area=0.20 ac 0.00% Impervious Runoff Depth=0.07" Tc=6.0 min CN=30 Runoff=0.00 cfs 0.001 af
SubcatchmentPWA-4:	Runoff Area=0.25 ac 0.00% Impervious Runoff Depth=0.07" Tc=6.0 min CN=30 Runoff=0.00 cfs 0.001 af
SubcatchmentPWA-5A:	Runoff Area=0.54 ac 0.00% Impervious Runoff Depth=0.20" Tc=6.0 min CN=34 Runoff=0.01 cfs 0.009 af
SubcatchmentPWA-5B:	Runoff Area=5.02 ac 19.72% Impervious Runoff Depth=0.91" Flow Length=705' Tc=8.7 min CN=47 Runoff=3.26 cfs 0.380 af
SubcatchmentPWA-5C:	Runoff Area=5.04 ac 50.99% Impervious Runoff Depth=2.67" Flow Length=400' Tc=11.2 min CN=69 Runoff=13.03 cfs 1.120 af
SubcatchmentPWA-5D:	Runoff Area=0.42 ac 54.76% Impervious Runoff Depth=2.85" Tc=6.0 min CN=71 Runoff=1.37 cfs 0.100 af
SubcatchmentPWA-5E:	Runoff Area=1.97 ac 0.00% Impervious Runoff Depth=0.24" Flow Length=230' Tc=19.0 min CN=35 Runoff=0.07 cfs 0.039 af
SubcatchmentPWA-5F:	Runoff Area=3.70 ac 49.73% Impervious Runoff Depth=2.57" Tc=6.0 min CN=68 Runoff=10.84 cfs 0.794 af
SubcatchmentPWA-6:	Runoff Area=1.88 ac 0.00% Impervious Runoff Depth=0.07" Flow Length=175' Tc=9.6 min CN=30 Runoff=0.02 cfs 0.010 af
SubcatchmentPWA-7A:	Runoff Area=8.81 ac 48.01% Impervious Runoff Depth=2.40" Tc=6.0 min CN=66 Runoff=23.86 cfs 1.759 af
SubcatchmentPWA-7B:	Runoff Area=1.49 ac 0.00% Impervious Runoff Depth=0.16" Flow Length=267' Tc=13.2 min CN=33 Runoff=0.03 cfs 0.020 af
SubcatchmentPWA-8:	Runoff Area=1.60 ac 0.00% Impervious Runoff Depth=0.09" Flow Length=100' Tc=8.5 min CN=31 Runoff=0.02 cfs 0.012 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.10' Max Vel=1.50 fps Inflow=0.07 cfs 0.039 af 18.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=8.78 cfs Outflow=0.07 cfs 0.039 af
Reach DP-1: Northern Wetlands Culvert	Inflow=0.39 cfs 0.121 af Outflow=0.39 cfs 0.121 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.00 cfs 0.001 af Outflow=0.00 cfs 0.001 af

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 25-Yr Rainfall=5.94"

Printed 8/21/2025

Page 11

Reach DP-4: Poppy LnInflow=0.00 cfs 0.001 af
Outflow=0.00 cfs 0.001 af**Reach DP-5: Wetland Series 'A'**Inflow=0.11 cfs 0.079 af
Outflow=0.11 cfs 0.079 af**Reach DP-6: Wetland Series 'B' & 'C'**Inflow=0.02 cfs 0.010 af
Outflow=0.02 cfs 0.010 af**Reach DP-7: #4 Poppy Ln**Inflow=0.03 cfs 0.020 af
Outflow=0.03 cfs 0.020 af**Reach DP-8: Wetland Series 'D' & 'E'**Inflow=0.02 cfs 0.012 af
Outflow=0.02 cfs 0.012 af**Pond Forebay-1: PCB-18**Peak Elev=141.50' Storage=2 cf Inflow=3.26 cfs 0.380 af
Outflow=3.26 cfs 0.380 af**Pond IB-1:**Peak Elev=140.12' Storage=14,584 cf Inflow=16.29 cfs 1.499 af
Discarded=4.51 cfs 1.499 af Primary=0.02 cfs 0.001 af Secondary=0.00 cfs 0.000 af Outflow=4.54 cfs 1.500 af**Pond IB-2:**Peak Elev=137.71' Storage=4,578 cf Inflow=10.84 cfs 0.794 af
Discarded=4.34 cfs 0.794 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=4.34 cfs 0.794 af**Pond IB-3:**Peak Elev=137.62' Storage=18,340 cf Inflow=23.86 cfs 1.759 af
Discarded=5.94 cfs 1.759 af Primary=0.00 cfs 0.000 af Secondary=0.00 cfs 0.000 af Outflow=5.94 cfs 1.759 af**Pond SUB-1: Subsurface System-1**Peak Elev=133.73' Storage=3,550 cf Inflow=1.37 cfs 0.100 af
Outflow=0.02 cfs 0.031 af**Total Runoff Area = 35.34 ac Runoff Volume = 4.366 af Average Runoff Depth = 1.48"**
72.10% Pervious = 25.48 ac 27.90% Impervious = 9.86 ac

23-10524 - Post - R7

Type III 24-hr 100-Yr Rainfall=8.55"

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 12

Time span=5.00-32.00 hrs, dt=0.05 hrs, 541 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPWA-1:	Runoff Area=4.42 ac 0.00% Impervious Runoff Depth=1.19" Flow Length=397' Tc=13.7 min CN=37 Runoff=3.05 cfs 0.440 af
SubcatchmentPWA-3:	Runoff Area=0.20 ac 0.00% Impervious Runoff Depth=0.55" Tc=6.0 min CN=30 Runoff=0.04 cfs 0.009 af
SubcatchmentPWA-4:	Runoff Area=0.25 ac 0.00% Impervious Runoff Depth=0.55" Tc=6.0 min CN=30 Runoff=0.05 cfs 0.012 af
SubcatchmentPWA-5A:	Runoff Area=0.54 ac 0.00% Impervious Runoff Depth=0.90" Tc=6.0 min CN=34 Runoff=0.26 cfs 0.041 af
SubcatchmentPWA-5B:	Runoff Area=5.02 ac 19.72% Impervious Runoff Depth=2.25" Flow Length=705' Tc=8.7 min CN=47 Runoff=10.65 cfs 0.943 af
SubcatchmentPWA-5C:	Runoff Area=5.04 ac 50.99% Impervious Runoff Depth=4.82" Flow Length=400' Tc=11.2 min CN=69 Runoff=23.82 cfs 2.025 af
SubcatchmentPWA-5D:	Runoff Area=0.42 ac 54.76% Impervious Runoff Depth=5.06" Tc=6.0 min CN=71 Runoff=2.44 cfs 0.177 af
SubcatchmentPWA-5E:	Runoff Area=1.97 ac 0.00% Impervious Runoff Depth=1.00" Flow Length=230' Tc=19.0 min CN=35 Runoff=0.92 cfs 0.164 af
SubcatchmentPWA-5F:	Runoff Area=3.70 ac 49.73% Impervious Runoff Depth=4.70" Tc=6.0 min CN=68 Runoff=20.00 cfs 1.450 af
SubcatchmentPWA-6:	Runoff Area=1.88 ac 0.00% Impervious Runoff Depth=0.55" Flow Length=175' Tc=9.6 min CN=30 Runoff=0.36 cfs 0.087 af
SubcatchmentPWA-7A:	Runoff Area=8.81 ac 48.01% Impervious Runoff Depth=4.46" Tc=6.0 min CN=66 Runoff=45.18 cfs 3.276 af
SubcatchmentPWA-7B:	Runoff Area=1.49 ac 0.00% Impervious Runoff Depth=0.81" Flow Length=267' Tc=13.2 min CN=33 Runoff=0.53 cfs 0.101 af
SubcatchmentPWA-8:	Runoff Area=1.60 ac 0.00% Impervious Runoff Depth=0.64" Flow Length=100' Tc=8.5 min CN=31 Runoff=0.40 cfs 0.085 af
Reach 3R: 'Wetland Series J'	Avg. Flow Depth=0.33' Max Vel=3.22 fps Inflow=0.92 cfs 0.164 af 18.0" Round Pipe n=0.013 L=143.0' S=0.0070 ' Capacity=8.78 cfs Outflow=0.92 cfs 0.164 af
Reach DP-1: Northern Wetlands Culvert	Inflow=3.05 cfs 0.440 af Outflow=3.05 cfs 0.440 af
Reach DP-3: #48 Rinzee Rd	Inflow=0.04 cfs 0.009 af Outflow=0.04 cfs 0.009 af

23-10524 - Post - R7

Type III 24-hr 100-Yr Rainfall=8.55"

Prepared by Civil Design Consultants, Inc

Printed 8/21/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 13

Reach DP-4: Poppy LnInflow=0.05 cfs 0.012 af
Outflow=0.05 cfs 0.012 af**Reach DP-5: Wetland Series 'A'**Inflow=3.03 cfs 0.433 af
Outflow=3.03 cfs 0.433 af**Reach DP-6: Wetland Series 'B' & 'C'**Inflow=0.36 cfs 0.087 af
Outflow=0.36 cfs 0.087 af**Reach DP-7: #4 Poppy Ln**Inflow=0.56 cfs 0.105 af
Outflow=0.56 cfs 0.105 af**Reach DP-8: Wetland Series 'D' & 'E'**Inflow=0.40 cfs 0.085 af
Outflow=0.40 cfs 0.085 af**Pond Forebay-1: PCB-18**Peak Elev=141.73' Storage=145 cf Inflow=10.65 cfs 0.943 af
Outflow=10.77 cfs 0.943 af**Pond IB-1:**Peak Elev=141.55' Storage=40,489 cf Inflow=34.58 cfs 2.968 af
Discarded=6.07 cfs 2.862 af Primary=0.83 cfs 0.106 af Secondary=0.00 cfs 0.000 af Outflow=6.90 cfs 2.968 af**Pond IB-2:**Peak Elev=138.67' Storage=14,368 cf Inflow=20.00 cfs 1.450 af
Discarded=4.96 cfs 1.433 af Primary=0.71 cfs 0.016 af Secondary=0.00 cfs 0.000 af Outflow=5.67 cfs 1.450 af**Pond IB-3:**Peak Elev=139.44' Storage=45,431 cf Inflow=45.18 cfs 3.276 af
Discarded=7.76 cfs 3.273 af Primary=0.03 cfs 0.004 af Secondary=0.00 cfs 0.000 af Outflow=7.79 cfs 3.277 af**Pond SUB-1: Subsurface System-1**Peak Elev=134.06' Storage=3,974 cf Inflow=2.44 cfs 0.177 af
Outflow=0.50 cfs 0.106 af**Total Runoff Area = 35.34 ac Runoff Volume = 8.809 af Average Runoff Depth = 2.99"**
72.10% Pervious = 25.48 ac 27.90% Impervious = 9.86 ac

DRAINAGE REPORT

Murphy's Farm
Dracut, MA

TAB 5



Checklist for Stormwater Report

A. Introduction

Important: When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the [Massachusetts Stormwater Handbook](#). The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.¹ This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8²
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

¹ The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

² For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



Checklist for Stormwater Report

B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.


Note: Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature

		September 1, 2025
Signature and Date		

Checklist

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?

- ☒ New development
- ☐ Redevelopment
- ☐ Mix of New Development and Redevelopment



Checklist for Stormwater Report

Checklist (continued)

LID Measures: Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

- ☐ No disturbance to any Wetland Resource Areas
- ☐ Site Design Practices (e.g. clustered development, reduced frontage setbacks)
- ☐ Reduced Impervious Area (Redevelopment Only)
- ☐ Minimizing disturbance to existing trees and shrubs
- ☐ LID Site Design Credit Requested:
 - ☐ Credit 1
 - ☐ Credit 2
 - ☐ Credit 3
- ☐ Use of "country drainage" versus curb and gutter conveyance and pipe
- ☐ Bioretention Cells (includes Rain Gardens)
- ☐ Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
- ☐ Treebox Filter
- ☐ Water Quality Swale
- ☐ Grass Channel
- ☐ Green Roof
- ☐ Other (describe): _____

Standard 1: No New Untreated Discharges

- ☒ No new untreated discharges
- ☒ Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- ☒ Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



Checklist for Stormwater Report

Checklist (continued)

Standard 2: Peak Rate Attenuation

- ☐ Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- ☐ Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
- ☒ Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

Standard 3: Recharge

- ☒ Soil Analysis provided.
- ☒ Required Recharge Volume calculation provided.
- ☐ Required Recharge volume reduced through use of the LID site Design Credits.
- ☒ Sizing the infiltration, BMPs is based on the following method: Check the method used.
 - ☒ Static
 - ☐ Simple Dynamic
 - ☐ Dynamic Field¹
- ☐ Runoff from all impervious areas at the site discharging to the infiltration BMP.
- ☒ Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
- ☒ Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
- ☐ Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
 - ☐ Site is comprised solely of C and D soils and/or bedrock at the land surface
 - ☐ M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
 - ☐ Solid Waste Landfill pursuant to 310 CMR 19.000
 - ☐ Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- ☒ Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- ☐ Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

¹ 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



Checklist for Stormwater Report

Checklist (continued)

Standard 3: Recharge (continued)

- ☒ The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
- ☐ Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
 - Provisions for storing materials and waste products inside or under cover;
 - Vehicle washing controls;
 - Requirements for routine inspections and maintenance of stormwater BMPs;
 - Spill prevention and response plans;
 - Provisions for maintenance of lawns, gardens, and other landscaped areas;
 - Requirements for storage and use of fertilizers, herbicides, and pesticides;
 - Pet waste management provisions;
 - Provisions for operation and management of septic systems;
 - Provisions for solid waste management;
 - Snow disposal and plowing plans relative to Wetland Resource Areas;
 - Winter Road Salt and/or Sand Use and Storage restrictions;
 - Street sweeping schedules;
 - Provisions for prevention of illicit discharges to the stormwater management system;
 - Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
 - Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
 - List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.
- ☒ A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
 - ☒ Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
 - ☐ is within the Zone II or Interim Wellhead Protection Area
 - ☐ is near or to other critical areas
 - ☒ is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
 - ☐ involves runoff from land uses with higher potential pollutant loads.
 - ☐ The Required Water Quality Volume is reduced through use of the LID site Design Credits.
 - ☒ Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



Checklist for Stormwater Report

Checklist (continued)

Standard 4: Water Quality (continued)

- ☒ The BMP is sized (and calculations provided) based on:
 - ☒ The ½" or 1" Water Quality Volume or
 - ☐ The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- ☒ The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the propriety BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- ☐ A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- ☐ The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- ☐ The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- ☐ The NPDES Multi-Sector General Permit does **not** cover the land use.
- ☐ LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- ☐ All exposure has been eliminated.
- ☐ All exposure has **not** been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- ☐ The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

Standard 6: Critical Areas

- ☐ The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- ☐ Critical areas and BMPs are identified in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

- ☐ The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:
 - ☐ Limited Project
 - ☐ Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
 - ☐ Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
 - ☐ Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
 - ☐ Bike Path and/or Foot Path
 - ☐ Redevelopment Project
 - ☐ Redevelopment portion of mix of new and redevelopment.
- ☐ Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.
- ☐ The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
 - Construction Period Operation and Maintenance Plan;
 - Names of Persons or Entity Responsible for Plan Compliance;
 - Construction Period Pollution Prevention Measures;
 - Erosion and Sedimentation Control Plan Drawings;
 - Detail drawings and specifications for erosion control BMPs, including sizing calculations;
 - Vegetation Planning;
 - Site Development Plan;
 - Construction Sequencing Plan;
 - Sequencing of Erosion and Sedimentation Controls;
 - Operation and Maintenance of Erosion and Sedimentation Controls;
 - Inspection Schedule;
 - Maintenance Schedule;
 - Inspection and Maintenance Log Form.
- ☐ A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



Checklist for Stormwater Report

Checklist (continued)

Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- ☐ The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has **not** been included in the Stormwater Report but will be submitted **before** land disturbance begins.
- ☐ The project is **not** covered by a NPDES Construction General Permit.
- ☐ The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- ☒ The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

Standard 9: Operation and Maintenance Plan

- ☒ The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
 - ☒ Name of the stormwater management system owners;
 - ☒ Party responsible for operation and maintenance;
 - ☒ Schedule for implementation of routine and non-routine maintenance tasks;
 - ☒ Plan showing the location of all stormwater BMPs maintenance access areas;
 - ☐ Description and delineation of public safety features;
 - ☒ Estimated operation and maintenance budget; and
 - ☒ Operation and Maintenance Log Form.
- ☐ The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
 - ☐ A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
 - ☐ A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

Standard 10: Prohibition of Illicit Discharges

- ☒ The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- ☐ An Illicit Discharge Compliance Statement is attached;
- ☒ NO Illicit Discharge Compliance Statement is attached but will be submitted **prior to** the discharge of any stormwater to post-construction BMPs.

Project: Murphy's Farm
Location: Dracut, MA
Client: The Homes at Murphy's Farm LLC

Project Number: 23-10524
Prepared By: Thomas Schomburg, EIT
Date: August 21, 2025

STORMWATER MANAGEMENT STANDARDS CALCULATIONS

Standard 1: Velocity & Rip-Rap Apron Sizing and Gradation Calculations

Outlet:	Q ₁₀ : (CFS)	Velocity (FPS)	Req'd	D _o : (FT)	L _A : (FT)	W ₁ : (FT)	W ₂ : (FT)	T _w : (FT)	d ₅₀ : (FT)
PFES-1	0.00	0.00	No	1	7.0	3.0	10.0	0.5	0.00
PFES-2	0.00	0.00	No	1.25	8.8	3.8	12.5	0.625	0.00
PFES-9	0.00	0.00	No	1.5	10.5	4.5	15.0	0.75	0.00

Conclusion: No riprap aprons are required, however a riprap apron is provided for each outfall. The Stormwater Management System conforms to Standard 1.

Standard 2: Peak Discharge Summary (CFS)

	2-Year (3.08-IN)	10-Year (4.68-IN)	25-Year (5.94-IN)	100-Year (8.55-IN)
Design Point 1				
Pre-Development Conditions:	0.00	0.06	0.45	3.53
Post Development Conditions:	0.00	0.05	0.39	3.05
Design Point 3				
Pre-Development Conditions:	0.00	0.00	0.02	0.51
Post Development Conditions:	0.00	0.00	0.00	0.04
Design Point 4				
Pre-Development Conditions:	0.00	0.00	0.02	0.40
Post Development Conditions:	0.00	0.00	0.00	0.05
Design Point 5				
Pre-Development Conditions:	0.00	0.03	0.23	3.31
Post Development Conditions:	0.00	0.02	0.11	3.03
Design Point 6				
Pre-Development Conditions:	0.00	0.00	0.02	0.40
Post Development Conditions:	0.00	0.00	0.02	0.36
Design Point 7				
Pre-Development Conditions:	0.00	0.00	0.05	1.05
Post Development Conditions:	0.00	0.00	0.03	0.56

	2-Year (3.08-IN)	10-Year (4.68-IN)	25-Year (5.94-IN)	100-Year (8.55-IN)
Design Point 8				
Pre-Development Conditions:	0.00	0.00	0.04	0.71
Post Development Conditions:	0.00	0.00	0.02	0.40

Conclusion: The Stormwater Management System conforms to Standard 2.

Standard 3: Recharge Calculations (Static Method)

Infiltration Basin 1

Hydrologic Soils Group:	A	B	C	D	
Total Proposed Impervious Area:	3.43	0.13	0.00	0.00	3.56
Target Factor:	0.60	0.35	0.25	0.10	
Required Recharge Volume:	7,471	165	0	0	7,636 CF
Volume Below Lowest Outlet:					12,661 CF
Elevation of Lowest Invert:					140.00

Determine Drawdown Time

Saturated Hydraulic Conductivity (Rawls Rate):	12.34 IN/HR
Bottom Area of Infiltration Basin:	12,689 SF
Drawdown Time:	1.0 HRS

Infiltration Basin 2

Hydrologic Soils Group:	A	B	C	D	
Total Proposed Impervious Area:	1.79	0.05	0.00	0.00	1.84
Target Factor:	0.60	0.35	0.25	0.10	
Required Recharge Volume:	3,899	64	0	0	3,962 CF
Volume Below Lowest Outlet:					4,528 CF
Elevation of Lowest Invert:					137.70

Determine Drawdown Time

Saturated Hydraulic Conductivity (Rawls Rate):	19.8 IN/HR
Bottom Area of Infiltration Basin:	8,663 SF
Drawdown Time:	0.3 HRS

Infiltration Basin 3

Hydrologic Soils Group:	A	B	C	D	
Total Proposed Impervious Area:	4.23	0.00	0.00	0.00	4.23
Target Factor:	0.60	0.35	0.25	0.10	
Required Recharge Volume:	9,213	0	0	0	9,213 CF
Volume Below Lowest Outlet:					26,209 CF
Elevation of Lowest Invert:					138.20

Determine Drawdown Time

Saturated Hydraulic Conductivity (Rawls Rate):	19.8 IN/HR
Bottom Area of Infiltration Basin:	9,701 SF
Drawdown Time:	1.6 HRS

Subsurface System 1

See Stormtech Cutsheet for WQV & TSS

Capture Area Adjustment

Increase in Site Impervious:	9.86 Ac.
Impervious Draining to Basins:	9.63 Ac.
Adjusted Recharge Volume:	21,308 CF
Recharge Volume Provided:	43,398 CF
Percentage of Impervious Draining to Basins	98%

TSS Removal Rate Calculations

44% Pretreatment for Infiltration Basins (Typical):

	TSS Removal Rate	Starting TSS Load	Amount Removed	Remaining Load
Deep Sump Catch Basin	25%	1	0.25	0.75
Sediment Forebay	25%	0.75	0.19	0.56
TSS Removed at Discharge from Pond:				44%

44% Pretreatment for Infiltration Basins 1, 2 and 3:

	TSS Removal Rate	Starting TSS Load	Amount Removed	Remaining Load
Sediment Forebay	25%	1	0.25	0.75
Sediment Forebay	25%	0.75	0.19	0.56
TSS Removed at Discharge from Pond:				44%

Treatment Provided at Discharge From Infiltration Basins 1, 2, and 3

	TSS Removal Rate	Starting TSS Load	Amount Removed	Remaining Load
Deep Sump Catch Basin	25%	1	0.25	0.75
Sediment Forebay & Infiltration Basin:	80%	0.75	0.60	0.15
TSS Removed at Discharge from Pond:				85.0%

Treatment Provided at Discharge From Subsurface-1

	TSS Removal Rate	Starting TSS Load	Amount Removed	Remaining Load
Deep Sump Catch Basins	25%	1	0.25	0.75
Contech CDS	80%	0.75	0.60	0.15
TSS Removed at Discharge from Pond:				85.0%

Conclusion: The volume provided below the lowest invert in the infiltration basin and subsurface systems exceeds the Water Quality Volume and TSS Removal Rate is greater than 80%. BMPs with infiltration rates of greater than 2.41 in/hr have the required 44% TSS removal rate prior to infiltration. The Stormwater Management System conforms to Standard 4.
required >90% TSS and 60% TP removal for the local bylaw.

Standard 5: Land Uses With Higher Potential Pollutant Loads

Conclusion: The proposed use is not considered a Land Use with Higher Potential Pollutant Loads. This Standard is NOT Applicable.

Standard 6: Critical Areas

Conclusion: The project is not located within an Area of Critical Environmental Concern. Proposed BMPs and discharges are located outside of the 100-Ft buffer afforded to vernal pools. The Stormwater Management System conforms to Standard 4.

Standard 7: Redevelopment

Conclusion: The development does not meet the criteria for redevelopment.

Standard 8: Construction Period Controls

Conclusion: The project is covered by a NPDES Construction General Permit. No SWPPP has been prepared at this time but will be prepared prior to the start of construction. A Construction Period Pollution Prevention Plan has been prepared and provided. The Stormwater Management System Conforms to Standard 8.

Standard 9: Operations and Maintenance Plan

Conclusion: An Operations and Maintenance Plan has been prepared and provided with this summary. The Stormwater Management System Conforms to Standard 9.

Standard 10: Illicit Discharges to Drainage System

Conclusion: All off-site discharges are comprised entirely of stormwater. The Stormwater Management System Conforms to Standard 10.

Project: Murphy's Farm
Location: Dracut, MA
Client: The Homes at Murphy's Farm LLC

Project Number: 23-10524
Prepared By: Thomas Schomburg, EIT
Date: May 5, 2025

FOREBAY SIZING CALCULATIONS

Infiltration Basin 1 - Forebay PWA-5B

Watershed Characteristics

Impervious Area (Ai): 0.99 Acres

Required (0.1-IN x Ai): 359 CF

Sediment Forebay Volume: 498 CF

OK

Stage / Storage Tables

Sediment Forebay:	Elevation	Surface Area (SF)	Incremental Storage (CF)	Total Storage (CF)
	137.0	69	0	0
	138.0	230	149.5	149.5
	139.0	466	348	497.5

Infiltration Basin 1 - Forebay PWA-5C

Watershed Characteristics

Impervious Area (Ai): 2.57 Acres

Required (0.1-IN x Ai): 933 CF

Sediment Forebay Volume: 1065 CF

OK

Stage / Storage Tables

Sediment Forebay:	Elevation	Surface Area (SF)	Incremental Storage (CF)	Total Storage (CF)
	139.1	200	0	0
	140.0	505	317.25	317.25
	141.0	990	747.5	1064.75

Infiltration Basin 2 - Forebay

Watershed Characteristics

Impervious Area (Ai): 1.84 Acres

Required (0.1-IN x Ai): 668 CF

Sediment Forebay Volume: 698 CF

OK

Stage / Storage Tables

Sediment Forebay:	Elevation	Surface Area (SF)	Incremental Storage (CF)	Total Storage (CF)
	136.0	160	0	0
	137.2	350	306	306
	138.0	630	392	698

Infiltration Basin 3 - Forebay

Watershed Characteristics

Impervious Area (Ai): 4.23 Acres

Required (0.1-IN x Ai): 1535 CF

Sediment Forebay Volume: 1850 CF

OK

Stage / Storage Tables

Sediment Forebay:	Elevation	Surface Area (SF)	Incremental Storage (CF)	Total Storage (CF)
	136.0	490	0	0
	138.0	1360	1850	1850

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Type III 24-hr 100-Yr Rainfall=8.55"

Printed 8/22/2025

Page 1

Stage-Area-Storage for Pond IB-1:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
139.10	12,689	0	141.70	22,038	43,700
139.15	12,842	638	141.75	22,302	44,808
139.20	12,995	1,284	141.80	22,565	45,930
139.25	13,149	1,938	141.85	22,828	47,065
139.30	13,302	2,599	141.90	23,091	48,213
139.35	13,455	3,268	141.95	23,354	49,374
139.40	13,608	3,945	142.00	23,617	50,548
139.45	13,762	4,629	142.05	23,759	51,733
139.50	13,915	5,321	142.10	23,902	52,924
139.55	14,068	6,020	142.15	24,044	54,123
139.60	14,221	6,728	142.20	24,186	55,329
139.65	14,374	7,442	142.25	24,329	56,541
139.70	14,528	8,165	142.30	24,471	57,761
139.75	14,681	8,895	142.35	24,613	58,988
139.80	14,834	9,633	142.40	24,755	60,223
139.85	14,987	10,379	142.45	24,898	61,464
139.90	15,141	11,132	142.50	25,040	62,712
139.95	15,294	11,893	142.55	25,182	63,968
140.00	15,447	12,661	142.60	25,325	65,231
140.05	15,592	13,437	142.65	25,467	66,500
140.10	15,738	14,220	142.70	25,609	67,777
140.15	15,883	15,011	142.75	25,752	69,061
140.20	16,029	15,809	142.80	25,894	70,353
140.25	16,174	16,614	142.85	26,036	71,651
140.30	16,319	17,426	142.90	26,178	72,956
140.35	16,465	18,246	142.95	26,321	74,269
140.40	16,610	19,073	143.00	26,463	75,588
140.45	16,756	19,907			
140.50	16,901	20,748			
140.55	17,046	21,597			
140.60	17,192	22,453			
140.65	17,337	23,316			
140.70	17,483	24,187			
140.75	17,628	25,064			
140.80	17,773	25,949			
140.85	17,919	26,842			
140.90	18,064	27,741			
140.95	18,210	28,648			
141.00	18,355	29,562			
141.05	18,618	30,487			
141.10	18,881	31,424			
141.15	19,144	32,375			
141.20	19,407	33,338			
141.25	19,671	34,315			
141.30	19,934	35,305			
141.35	20,197	36,309			
141.40	20,460	37,325			
141.45	20,723	38,355			
141.50	20,986	39,397			
141.55	21,249	40,453			
141.60	21,512	41,522			
141.65	21,775	42,605			

23-10524 - Post - R7*Type III 24-hr 100-Yr Rainfall=8.55"*

Prepared by Civil Design Consultants, Inc

Printed 8/22/2025

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC

Page 2

Stage-Area-Storage for Pond IB-2:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
137.20	8,663	0	139.80	12,340	27,470
137.25	8,742	435	139.85	12,407	28,089
137.30	8,820	874	139.90	12,475	28,711
137.35	8,899	1,317	139.95	12,542	29,336
137.40	8,978	1,764	140.00	12,609	29,965
137.45	9,056	2,215			
137.50	9,135	2,670			
137.55	9,214	3,128			
137.60	9,293	3,591			
137.65	9,371	4,058			
137.70	9,450	4,528			
137.75	9,529	5,003			
137.80	9,607	5,481			
137.85	9,686	5,963			
137.90	9,765	6,450			
137.95	9,843	6,940			
138.00	9,922	7,434			
138.05	9,989	7,932			
138.10	10,056	8,433			
138.15	10,124	8,937			
138.20	10,191	9,445			
138.25	10,258	9,956			
138.30	10,325	10,471			
138.35	10,392	10,989			
138.40	10,459	11,510			
138.45	10,527	12,035			
138.50	10,594	12,563			
138.55	10,661	13,094			
138.60	10,728	13,629			
138.65	10,795	14,167			
138.70	10,862	14,709			
138.75	10,930	15,253			
138.80	10,997	15,802			
138.85	11,064	16,353			
138.90	11,131	16,908			
138.95	11,198	17,466			
139.00	11,266	18,028			
139.05	11,333	18,593			
139.10	11,400	19,161			
139.15	11,467	19,733			
139.20	11,534	20,308			
139.25	11,601	20,886			
139.30	11,669	21,468			
139.35	11,736	22,053			
139.40	11,803	22,641			
139.45	11,870	23,233			
139.50	11,937	23,828			
139.55	12,004	24,427			
139.60	12,072	25,029			
139.65	12,139	25,634			
139.70	12,206	26,243			
139.75	12,273	26,855			

23-10524 - Post - R7

Prepared by Civil Design Consultants, Inc

HydroCAD® 10.20-5c s/n 06435 © 2023 HydroCAD Software Solutions LLC


Type III 24-hr 100-Yr Rainfall=8.55"


Printed 8/22/2025

Page 3



Stage-Area-Storage for Pond IB-3:

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
136.00	9,701	0	141.20	21,176	78,971
136.10	9,902	980	141.30	21,424	81,101
136.20	10,103	1,980	141.40	21,672	83,256
136.30	10,304	3,001	141.50	21,920	85,436
136.40	10,505	4,041	141.60	22,167	87,640
136.50	10,706	5,102	141.70	22,415	89,869
136.60	10,906	6,182	141.80	22,663	92,123
136.70	11,107	7,283	141.90	22,910	94,402
136.80	11,308	8,404	142.00	23,158	96,705
136.90	11,509	9,545	142.10	23,429	99,034
137.00	11,710	10,706	142.20	23,700	101,391
137.10	11,911	11,887	142.30	23,971	103,774
137.20	12,112	13,088	142.40	24,242	106,185
137.30	12,313	14,309	142.50	24,513	108,623
137.40	12,514	15,550	142.60	24,784	111,088
137.50	12,715	16,812	142.70	25,055	113,580
137.60	12,915	18,093	142.80	25,326	116,099
137.70	13,116	19,395	142.90	25,597	118,645
137.80	13,317	20,716	143.00	25,868	121,218
137.90	13,518	22,058	143.10	26,139	123,818
138.00	13,719	23,420	143.20	26,410	126,446
138.10	13,943	24,803	143.30	26,681	129,100
138.20	14,167	26,209	143.40	26,952	131,782
138.30	14,392	27,637	143.50	27,223	134,491
138.40	14,616	29,087	143.60	27,494	137,227
138.50	14,840	30,560	143.70	27,765	139,990
138.60	15,064	32,055	143.80	28,036	142,780
138.70	15,289	33,573	143.90	28,307	145,597
138.80	15,513	35,113	144.00	28,578	148,441
138.90	15,737	36,675			
139.00	15,962	38,260			
139.10	16,186	39,868			
139.20	16,410	41,497			
139.30	16,634	43,150			
139.40	16,859	44,824			
139.50	17,083	46,521			
139.60	17,307	48,241			
139.70	17,531	49,983			
139.80	17,756	51,747			
139.90	17,980	53,534			
140.00	18,204	55,343			
140.10	18,452	57,176			
140.20	18,699	59,033			
140.30	18,947	60,916			
140.40	19,195	62,823			
140.50	19,443	64,755			
140.60	19,690	66,711			
140.70	19,938	68,693			
140.80	20,186	70,699			
140.90	20,433	72,730			
141.00	20,681	74,786			
141.10	20,929	76,866			






I:\AD.CONTECH\CPI.COM\ROOT\STORMWATER\URIS\DICTIONS\US\A\MAI_SDE DESIGN TOOLS\STANDARD DETAILS\CDS1515-3-C-DTL.DWG 8/6/2018 4:16 PM



THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF THE FOLLOWING U.S. PATENTS: 5,780,848; 6,641,720; 6,511,096; 6,581,789; RELATED FOREIGN PATENTS, OR OTHER PATENTS PENDING.

CDS1515-3-C DESIGN NOTES

CDS1515-3-C RATED TREATMENT CAPACITY IS 1.0 CFS, OR PER LOCAL REGULATIONS.
THE STANDARD CDS1515-3-C CONFIGURATION IS SHOWN.



FRAME AND COVER
(DIAMETER VARIES)
N.T.S.

SITE SPECIFIC
DATA REQUIREMENTS

STRUCTURE ID				
WATER QUALITY FLOW RATE (CFS OR L/s)				*
PEAK FLOW RATE (CFS OR L/s)				*
RETURN PERIOD OF PEAK FLOW (YRS)				*
SCREEN APERTURE (2400 OR 4700)				*
PIPE DATA:		I.E.	MATERIAL	DIAMETER
INLET PIPE 1		*	*	*
INLET PIPE 2		*	*	*
OUTLET PIPE		*	*	*
RIM ELEVATION				*
ANTI-FLOTATION BALLAST		WIDTH	HEIGHT	
		*	*	
NOTES/SPECIAL REQUIREMENTS:				
* PER ENGINEER OF RECORD				

GENERAL NOTES

- CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
- FOR SITE SPECIFIC DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHT, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS LLC REPRESENTATIVE. www.ContechES.com
- CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.
- STRUCTURE SHALL MEET AASHTO HS20 LOAD RATING, ASSUMING EARTH COVER OF 0' - 2', AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M306 AND BE CAST WITH THE CONTECH LOGO..
- IF REQUIRED, PVC HYDRAULIC SHEAR PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS NECESSARY DURING MAINTENANCE CLEANING.
- CDS STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C-478 AND AASHTO LOAD FACTOR DESIGN METHOD.

INSTALLATION NOTES

- ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
- CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE.
- CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS AND ASSEMBLE STRUCTURE.
- CONTRACTOR TO PROVIDE, INSTALL, AND GROUT INLET AND OUTLET PIPE(S). MATCH PIPE INVERTS WITH ELEVATIONS SHOWN. ALL PIPE CENTERLINES TO MATCH PIPE OPENING CENTERLINES.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.



www.contechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

CDS1515-3-C
ONLINE CDS
STANDARD DETAIL

[illegible]

**CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION
BASED ON THE RATIONAL RAINFALL METHOD**

**THE HOMES AT MURPHY'S FARM
ANDOVER, MA**

Area **0.24 ac**
Weighted C **0.9**
 t_c **6 min**
CDS Model **1515-3**

Unit Site Designation **CDS**
Rainfall Station # **67**

CDS Treatment Capacity **1.0 cfs**

<u>Rainfall Intensity¹</u> <u>(in/hr)</u>	<u>Percent Rainfall Volume¹</u>	<u>Cumulative Rainfall Volume</u>	<u>Total Flowrate (cfs)</u>	<u>Treated Flowrate (cfs)</u>	<u>Incremental Removal (%)</u>
0.08	41.0%	41.0%	0.02	0.02	39.4
0.16	23.9%	64.9%	0.03	0.03	22.6
0.24	11.5%	76.5%	0.05	0.05	10.8
0.32	7.4%	83.9%	0.07	0.07	6.9
0.40	4.4%	88.3%	0.09	0.09	4.1
0.48	2.9%	91.2%	0.10	0.10	2.6
0.56	1.8%	93.0%	0.12	0.12	1.6
0.64	1.2%	94.2%	0.14	0.14	1.0
0.72	1.6%	95.8%	0.16	0.16	1.4
0.80	0.8%	96.6%	0.17	0.17	0.7
1.00	0.6%	97.1%	0.22	0.22	0.5
1.40	1.4%	98.6%	0.31	0.31	1.1
1.80	0.9%	99.5%	0.39	0.39	0.6
2.20	0.5%	100.0%	0.48	0.48	0.3
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
					93.6
Removal Efficiency Adjustment ² =					0.0%
Predicted % Annual Rainfall Treated =					100.0%
Predicted Net Annual Load Removal Efficiency =					93.6%

1 - Based on 7 years of data from NCDC station #3276, Groveland, Essex County, MA

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

Storm Drainage Computations

NameMurphy's FarmClientThe Homes at Murphy's Farm LLCSubjectStormdrain Calculation

Proj. No.23-10524Date8/20/2025Comp.TWSCheckWJH

Design Parameters25 Year Storm15 "Min. Pipe SizeProject File:1 (1-Boston, 2-Barnstable, 3-Worcester, 4-Springfield, 5-Pittsfield' Manning's roughness coefficient0.013

(NOTE ENTER CELLS AS HIGHLIGHTED IN FIRST ROW)

LOCATION		RAINFALL CONCENTRATION PERIOD IN MINUTES		COMBINED RUNOFF COEFF.		TRIBUTARY AREA IN ACRES		C x A		RAINFALL INTENSITY (i)	PEAK FLOW	P I P E								PROFILE			
FROM DRAINAGE NO.	TO DRAINAGE NO.											SIZE	n VALUE	SLOPE	LENGTH	FULL CAPACITY	FULL VELOCITY	PEAK FLOW CONDITIONS		INVERT ELEVATION		RIM ELEVATION & DEPTH OF COVER	
		PIPE	TOTAL	C	INC	TOTAL	INC	TOTAL		IN/HR	CFS	IN		FT/FT	FT	CFS	FT/S	VELOCITY	d/D	UPPER END	LOWER END	UPPER RIM	DEPTH
PCB-1	PDMH-1		5.00	0.61	0.290	0.290	0.18	0.18		6.00	1.06	12	0.013	0.005	19	2.57	3.3	3.1	0.44				
PCB-2	PDMH-2		5.00	0.52	0.130	0.130	0.07	0.07		6.00	0.41	12	0.013	0.005	11	2.52	3.2	2.3	0.27				
PDMH-2	SUB-1		0.085.10			0.420	0.00	0.24		6.00	1.47	12	0.013	0.005	10	2.52	3.2	3.3	0.54				
PCB-10	PDMH-8		5.00	0.72	0.460	0.460	0.33	0.33		6.00	1.98	12	0.013	0.005	12	2.52	3.2	3.5	0.66				
PCB-11	PDMH-8		5.00	0.61	0.500	0.500	0.30	0.30		6.00	1.82	12	0.013	0.005	9	2.52	3.2	3.5	0.62				
PDMH-8	PDMH-7		0.045.06			0.960	0.00	0.63		6.00	3.80	15	0.013	0.010	106	6.46	5.3	5.5	0.55				
PCB-7	PDMH-7		5.00	0.79	0.320	0.320	0.25	0.25		6.00	1.52	15	0.013	0.005	17	4.57	3.7	3.3	0.39				
PCB-8	PDMH-7		5.00	0.55	0.810	0.810	0.44	0.44		6.00	2.65	15	0.013	0.005	15	4.57	3.7	3.8	0.54				
PDMH-7	PDMH-9		0.075.38			2.090	0.00	1.33		6.00	7.97	18	0.013	0.008	158	9.39	5.3	6.0	0.70				
PDMH-9	PDMH-10		0.075.82			2.090	0.00	1.33		6.00	7.97	18	0.013	0.008	366	9.39	5.3	6.0	0.70				
PCB-29	PDMH-10		5.00	0.51	0.760	0.760	0.39	0.39		6.00	2.34	15	0.013	0.010	13	6.46	5.3	4.8	0.41				
PDMH-10	PDMH-11		0.056.85			2.850	0.00	1.72		5.80	9.96	24	0.013	0.008	207	20.23	6.4	6.4	0.49				
PCB-28	PDMH-11		5.00	0.55	0.280	0.280	0.15	0.15		6.00	0.92	15	0.013	0.010	15	6.46	5.3	3.7	0.25				
PDMH-11	PFES-10		0.077.39			3.130	0.00	1.87		5.80	10.86	24	0.013	0.008	109	20.23	6.4	6.5	0.52				
PCB-5	PDMH-6		5.00	0.79	0.560	0.560	0.44	0.44		6.00	2.65	12	0.013	0.050	11	7.96	10.1	9.0	0.39				
PCB-6	PDMH-6		5.00	0.57	1.020	1.020	0.58	0.58		6.00	3.49	12	0.013	0.050	8	7.96	10.1	9.8	0.46				
PDMH-6	PDMH-5		0.015.02			1.580	0.00	1.02		6.00	6.14	15	0.013	0.050	172	14.44	11.8	11.2	0.45				
PDMH-5	PDMH-4		0.015.28			1.580	0.00	1.02		6.00	6.14	15	0.013	0.010	130	6.46	5.3	6.0	0.77				
PCB-3	PDMH-4		5.00	0.80	0.410	0.410	0.33	0.33		6.00	1.96	15	0.013	0.005	23	4.57	3.7	3.5	0.45				
PCB-4	PDMH-4		5.00	0.51	0.850	0.850	0.44	0.44		6.00	2.62	15	0.013	0.005	17	4.57	3.7	3.8	0.54				
PDMH-4	PFES-3		0.075.64			2.840	0.00	1.79		6.00	10.72	24	0.013	0.010	161	22.61	7.2	7.0	0.48				
PCB-14	PDMH-14		5.00	0.67	0.360	0.360	0.24	0.24		6.00	1.44	15	0.013	0.010	35	6.46	5.3	4.2	0.31				
PDMH-14	PDMH-13		0.145.14			0.360	0.00	0.24		6.00	1.44	15	0.013	0.010	84	6.46	5.3	4.2	0.31				
PCB-13	PDMH-3		5.00	0.85	0.270	0.270	0.23	0.23		6.00	1.37	15	0.013	0.010	34	6.46	5.3	4.2	0.31				
PDMH-13	PDMH-12		0.145.48			0.630	0.00	0.47		6.00	2.81	15	0.013	0.015	64	7.78	6.3	5.8	0.41				
PCB-12	PDMH-12		5.00	0.88	0.300	0.300	0.26	0.26		6.00	1.58	15	0.013	0.010	26	6.46	5.3	4.3	0.33				
PDMH-12	PFES-4		0.185.66			0.930	0.00	0.73		6.00	4.39	18	0.013	0.010	74	10.50	5.9	5.7	0.45				

PCB-30	PDMH-22		5.00	0.20	0.250	0.250	0.05	0.05	6.00	0.30	15	0.013	0.010	171	6.46	5.3	2.5	0.13				
PCB-22	PDMH-22		5.00	0.85	0.260	0.260	0.22	0.22	6.00	1.32	15	0.013	0.010	50	6.46	5.3	4.0	0.29				
PCB-21	PDMH-22		5.00	0.76	0.310	0.310	0.24	0.24	6.00	1.42	15	0.013	0.010	50	6.46	5.3	4.2	0.31				
PDMH-22	PDMH-21	0.21	6.15			0.820	0.00	0.51	5.80	2.94	15	0.013	0.010	83	6.46	5.3	5.1	0.47				
PCB-20	PDMH-21		5.00	0.73	0.760	0.760	0.56	0.56	6.00	3.35	15	0.013	0.010	32	6.46	5.3	5.3	0.51				
PDMH-21	PDMH-20	0.27	6.42			1.580	0.00	1.07	5.80	6.18	15	0.013	0.010	68	6.46	5.3	6.0	0.78				
PCB-23	PDMH-20		5.00	0.73	0.760	0.760	0.56	0.56	6.00	3.35	15	0.013	0.010	38	6.46	5.3	5.3	0.51				
PCB-19	PDMH-20		5.00	0.69	0.590	0.590	0.41	0.41	6.00	2.43	15	0.013	0.010	45	6.46	5.3	4.9	0.42				
PDMH-20	PDMH-19	0.12	6.60			2.930	0.00	2.03	5.80	11.76	24	0.013	0.010	129	22.61	7.2	7.3	0.51				
PCB-18	PDMH-19		5.00	0.74	0.450	0.450	0.34	0.34	6.00	2.01	15	0.013	0.010	31	6.46	5.3	4.6	0.38				
PDMH-19	PDMH-18	0.18	6.90			3.380	0.00	2.36	5.80	13.71	24	0.013	0.010	100	22.61	7.2	7.5	0.56				
PCB-26	PDMH-23		5.00	0.40	0.770	0.770	0.31	0.31	6.00	1.85	15	0.013	0.010	15	6.46	5.3	4.5	0.36				
PCB-27	PDMH-23		5.00	0.76	0.100	0.100	0.08	0.08	6.00	0.46	15	0.013	0.010	15	6.46	5.3	2.9	0.17				
PDMH-23	PDMH-16	0.09	5.06			0.870	0.00	0.38	6.00	2.30	15	0.013	0.010	114	6.46	5.3	4.8	0.41				
PCB-16	PDMH-16		5.00	0.42	2.030	2.030	0.85	0.85	6.00	5.08	15	0.013	0.010	10	6.46	5.3	5.8	0.66				
PCB-17	PDMH-16		5.00	0.71	0.300	0.300	0.21	0.21	6.00	1.28	15	0.013	0.010	9	6.46	5.3	4.0	0.29				
PDMH-16	PDMH-17	0.04	5.45			3.200	0.00	1.45	6.00	8.67	18	0.013	0.010	88	10.50	5.9	6.6	0.69				
PCB-24	PDMH-17		5.00	0.43	0.240	0.240	0.10	0.10	6.00	0.62	15	0.013	0.010	11	6.46	5.3	3.3	0.21				
PCB-25	PDMH-17		5.00	0.71	0.110	0.110	0.08	0.08	6.00	0.47	15	0.013	0.010	11	6.46	5.3	2.9	0.17				
PDMH-17	PDMH-18	0.06	5.67			3.550	0.00	1.63	6.00	9.76	18	0.013	0.010	117	10.50	5.9	6.7	0.76				
PDMH-18	PFES-8	0.29	7.12			6.930	0.00	3.99	5.80	23.14	30	0.013	0.010	148	41.00	8.4	8.6	0.53				

Project: Murphy's Farm
Client: The Homes at Murphy's Farm LLC
Project Number: 24-10524

Prepared By: TWS
Checked By: WJH
Date: 12/30/24
Revised: 8/21/25



344 North Main Street | Andover • MA 01810
 (978) 416-0920 | www.civildci.com

GRATE INLET CAPACITY CALCULATION SHEET							
Design Criteria							
Orifice Flow				Weir Flow			
$Q = 0.0108A \cdot d^{0.5}$				$Q = 3.33L(H)^{1.5}$			
Where,							
A	= the open area in the grate (square inches)						
d	= the depth of water over the grate (inches)						
L	= the perimeter of the grate (feet)						
H	= the gutter depth of water (feet)						
Qc	= the grate capacity (CFS)						
Q25	= the maximum 25-yr grate flow (CFS)						
Structure	Low Point	A	d	L	H	Qc	Q25
PCB-1&2	no			4	0.22	1.4	1.0
PCB-3&4	yes	212	6			5.6	2.6
PCB-5&6	yes	212	6			5.6	3.5
PCB-7&8	yes	212	6			5.6	2.7
PCB-10&11	no			4	0.5	4.7	2
PCB-12	yes	212	6			5.6	1.6
PCB-13&14	no			4	0.5	4.7	1.4
PCB-26 (DBL)	no			6	0.22	2.1	1.9
PCB-27	no			4	0.22	1.4	0.5
PCB-24&25	no			4	0.22	1.4	0.6
PCB-16&17	yes	212	6			5.6	5.1
PCB-22&21	no			4	0.5	4.7	1.4
PCB-20&23	yes	212	6			5.6	3.4
PCB-18	no			4	0.5	4.7	2
PCB-30	yes	212	6			5.6	0.3
PCB-15	yes	212	18			9.7	8.7



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 606 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.)
Slope (%) 5

Description of Location: See plans

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way 38 feet Wetlands 38 feet
Property Line 76 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	A	Sandy Loam	10YR 3/2		Cnc : Dpl:				Single Grain	Loose	
12-32	B	Loamy Sand	7.5YR 4/6		Cnc : Dpl:				Single Grain	Loose	
32-120	C	Medium Sand	10YR 6/3	48"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:
Test Pit logs for BMPs on Form 11



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 605 12/4/24
Hole # Date Time Weather Latitude Longitude
1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.)
Slope (%)

Description of Location: See plans

2. Soil Parent Material: Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: Depth to Weeping in Hole Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-72	Fill	-	-		Cnc : Dpl:				-	-	
72-108	C	Loamy Sand	7.5YR 4/6		Cnc : Dpl:		25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: CDCI-6

Hole #

12/7/23

Date

Time

Weather

Latitude

Longitude

1. Land Use Vacant lot
(e.g., woodland, agricultural field, vacant lot, etc.)

Dec./Con.
Vegetation

Yes
Surface Stones (e.g., cobbles, stones, boulders, etc.)

5
Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____

Landform

Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet

Drainage Way >100 feet

Wetlands >100 feet

Property Line >100 feet

Drinking Water Well >100 feet

Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☒ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No

If yes: _____ Depth to Weeping in Hole

_____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-24	Fill	-	-		Cnc : Dpl:				-	-	
24-80	C	Coarse Sand	10YR 5/4		Cnc : Dpl:		25		Single Grain	Loose	Ledge @ 80"
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 603 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-24	Fill	-	-		Cnc : Dpl:				-	-	
24-120	C	Gravelly Sand	10YR 5/3	60"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 604 12/4/24 _____
Hole # Date Time Weather Latitude Longitude
1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-24	Fill	-	-		Cnc : Dpl:				-	-	
24-108	C	Sand	10YR 7/3	48"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 608 12/4/24 _____
Hole # Date Time Weather Latitude Longitude
1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-48	Fill	-	-		Cnc : Dpl:				-	-	
48-120	C	Medium Sand	10YR 7/4	84"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 609 12/4/24 _____
 Hole # Date Time Weather Latitude Longitude
 1. Land Use Vacant lot Dec./Con. Yes
 (e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.)
 Description of Location: See plans 5
 Slope (%)

2. Soil Parent Material: _____
 Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line 65 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-48	Fill	-	-		Cnc : Dpl:				-	-	
48-120	C	Medium Sand	10YR 5/3		Cnc : Dpl:		25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 497 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-60	Fill	-	-		Cnc : Dpl:				-	-	
60-120	C	Loamy Sand	10YR 7/3		Cnc : Dpl:		15-25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 498 12/4/24 _____
Hole # Date Time Weather Latitude Longitude
1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-60	Fill	-	-		Cnc : Dpl:				-	-	
60-120	C	Fine Sand	10YR 7/3		Cnc : Dpl:		15-25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 499 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes 5
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-60	Fill	-	-		Cnc : Dpl:				-	-	
60-138	C	Fine Sand	10YR 7/3		Cnc : Dpl:		15-25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 600 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes 5
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-90	Fill	-	-		Cnc : Dpl:				-	-	
90-126	C	Sand	10YR 7/3		Cnc : Dpl:		25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 602 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☒ Yes ☐ No If Yes: ☒ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-66	Fill	-	-		Cnc : Dpl:				-	-	
66-84	B	Sand	10YR 5/4		Cnc : Dpl:		15-25		Single Grain	Loose	
84-120	C	Sand	10YR 7/3	86"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 25 12/4/24
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line 63 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-30	B	Loamy Sand	10YR 6/6		Cnc : Dpl:				Single Grain	Loose	
30-120	C	Gravelly Sand	10YR 6/4	72"	Cnc : Dpl:	>5	25-35		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 26 12/4/24 _____ _____ _____
 Hole # Date Time Weather Latitude Longitude
 1. Land Use Vacant lot Dec./Con. Yes
 (e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
 Description of Location: See plans Slope (%)

2. Soil Parent Material: _____
 Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
 Property Line 67 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-24	B	Loamy Sand	10YR 6/6		Cnc : Dpl:				Single Grain	Loose	
24-72	C	Gravelly Sand	10YR 6/4		Cnc : Dpl:		25-35		Single Grain	Loose	
72-120	C	Sand	10YR 6/2	72"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 27 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line >100 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-66	B	Gravelly Sand	10YR 6/6		Cnc : Dpl:		25-35		Single Grain	Loose	
66-120	C	Sand	10YR 6/1	66"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 494 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.)
Slope (%) 5

Description of Location: See plans

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way 40 feet Wetlands 40 feet
Property Line 60 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-30	B	Loamy Sand	10YR 5/6		Cnc : Dpl:				Single Grain	Loose	
30-84	C	Gravelly Sand	10YR 6/4		Cnc : Dpl:		25-35		Single Grain	Loose	
84-120	C	Sand	10YR 6/1	84"	Cnc : Dpl:	>5	25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 495 12/4/24 _____
 Hole # Date Time Weather Latitude Longitude
 1. Land Use Vacant lot Dec./Con. Yes
 (e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.)
5
 Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____
 Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way 85 feet Wetlands 85 feet
 Property Line 55 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-72	C	Medium Sand	10YR 6/6		Cnc : Dpl:				Single Grain	Loose	
72-132	C2	Fine Sand	10YR 7/4	84"	Cnc : Dpl:	>5	15-25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: 496 12/4/24 _____
Hole # Date Time Weather Latitude Longitude

1. Land Use Vacant lot Dec./Con. Yes
(e.g., woodland, agricultural field, vacant lot, etc.) Vegetation Surface Stones (e.g., cobbles, stones, boulders, etc.) 5
Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____
Landform Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet Drainage Way >100 feet Wetlands >100 feet
Property Line 60 feet Drinking Water Well >100 feet Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No If yes: _____ Depth to Weeping in Hole _____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	B	Loamy Sand	10YR 5/6		Cnc : Dpl:				Single Grain	Loose	
12-72	C	Medium Sand	10YR 6/4		Cnc : Dpl:		25		Single Grain	Loose	
72-120	C2	Fine Sand	10YR 6/1	84"	Cnc : Dpl:	>5	15-25		Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: CDCI-18

Hole #

4/3/24

Date

Time

Weather

Latitude

Longitude

1. Land Use Vacant lot
(e.g., woodland, agricultural field, vacant lot, etc.)

Dec./Con.

Vegetation

Yes

Surface Stones (e.g., cobbles, stones, boulders, etc.)

5

Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____

Landform

Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet

Drainage Way 70 feet

Wetlands 70 feet

Property Line >100 feet

Drinking Water Well >100 feet

Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☐ Yes ☒ No

If yes: _____ Depth to Weeping in Hole

_____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-24	B	Sand	10YR 5/6		Cnc : Dpl:				Single Grain	Loose	
24-104	C	Gravelly Sand	10YR 5/3	80"	Cnc : Dpl:	>5	25-35	10+	Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:



Commonwealth of Massachusetts
City/Town of

Form 11 - Soil Suitability Assessment for On-Site Sewage Disposal

C. On-Site Review *(minimum of two holes required at every proposed primary and reserve disposal area)*

Deep Observation Hole Number: CDCI-19

Hole #

4/3/24

Date

Time

Weather

Latitude

Longitude

1. Land Use Vacant lot
(e.g., woodland, agricultural field, vacant lot, etc.)

Dec./Con.

Vegetation

Yes

Surface Stones (e.g., cobbles, stones, boulders, etc.)

5

Slope (%)

Description of Location: See plans

2. Soil Parent Material: _____

Landform

Position on Landscape (SU, SH, BS, FS, TS, Plain)

3. Distances from: Open Water Body >100 feet

Drainage Way 90 feet

Wetlands 90 feet

Property Line >100 feet

Drinking Water Well >100 feet

Other _____ feet

4. Unsuitable Materials Present: ☐ Yes ☒ No If Yes: ☐ Disturbed Soil/Fill Material ☐ Weathered/Fractured Rock ☐ Bedrock

5. Groundwater Observed: ☒ Yes ☐ No

If yes: 90" Depth to Weeping in Hole

_____ Depth to Standing Water in Hole

Soil Log

Depth (in)	Soil Horizon /Layer	Soil Texture (USDA)	Soil Matrix: Color-Moist (Munsell)	Redoximorphic Features			Coarse Fragments % by Volume		Soil Structure	Soil Consistence (Moist)	Other
				Depth	Color	Percent	Gravel	Cobbles & Stones			
0-12	B	Sand	10YR 5/6		Cnc : Dpl:				Single Grain	Loose	
12-120	C	Gravelly Sand	10YR 5/3	60"	Cnc : Dpl:	>5	25-35	10+	Single Grain	Loose	
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						
					Cnc : Dpl:						

Additional Notes:

TEST PIT LOGS

Address: Murhpy's Farm, Dracut, MA

Date: 12/7/2023

S.E.: William Hall

Witness: Tina Rivard

Note: Areas where test pits were performed have been stripped of top and subsoil.

CDCI-1

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-120	C	10YR5/4	Coarse Sand

Many cobbles and stones

Not mottling observed

No water observed

CDCI-3

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-156	C	10YR5/4	Coarse Sand

Many cobbles and stones

Not mottling observed

No water observed

CDCI-5

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-126	C	10YR5/4	Coarse Sand

Many cobbles and stones

Not mottling observed

No water observed

CDCI-7

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-72	Sandy Fill	-----	-----

Not mottling observed

No water observed

Ledge encountered at 72"

CDCI-9

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-102	C1	10YR5/4	Coarse Sand
102-144	C2	10YR6/3	Loamy Sand

Many cobbles and stones in C1 layer

Not mottling observed

No water observed

CDCI-2

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-132	C	10YR5/4	Coarse Sand

Many cobbles and stones

Not mottling observed

No water observed

CDCI-4

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-120	C	10YR5/4	Coarse Sand

Many cobbles and stones

Not mottling observed

No water observed

CDCI-6

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-24	Fill	-----	-----
24-80	C	10YR5/4	Coarse Sand

Many cobbles and stones

Not mottling observed

No water observed

Ledge encountered at 80"

CDCI-8

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-80	C1	10YR5/4	Coarse Sand
80-144	C2	10YR6/3	Loamy Sand

Many cobbles and stones in C1 layer

Not mottling observed

No water observed

CDCI-10

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-84	C1	10YR5/4	Coarse Sand
84-136	C2	10YR6/3	F. Loamy Sand

Many cobbles and stones in C1 layer

Mottling @ 72"

Weeping @ 84"

Address: Murhpy's Farm, Dracut, MA

Date: 12/7/2023

S.E.: William Hall

Witness: Tina Rivard

Note: Areas where test pits were performed have been stripped of top and subsoil.

CDCI-11

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-90	C1	10YR5/4	Coarse Sand
90-166	C2	10YR6/3	F. Loamy Sand

Many cobbles and stones in C1 layer
Mottling @ 128"
Weeping @ 160"

CDCI-12

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-80	C1	10YR5/4	Coarse Sand
80-144	C2	10YR6/3	F. Loamy Sand

Many cobbles and stones in C1 layer
Mottling @ 112"
Weeping @ 144"

Address: Murphy's Farm, Dracut, MA
Date: 4/3/2024
S.E.: Thomas Schomburg
Witness: N/a

Note: Test pits CDCI-14 - CDCI-23 performed in areas that have been stripped of top and subsoil. Soil has begun to weather.

CDCI-13

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-16	A	10YR3/2	Sandy Loam
16-36	B	10YR5/6	Sandy Loam
36-80	C	10YR5/3	Sandy Loam

Mottling @ 32"
Water @ 40"

CDCI-15

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	A	10YR3/2	Sandy Loam
12-32	B	10YR5/6	Sandy Loam
32-96	C	10YR5/3	Sandy Loam

Mottling @ 30"
Water @ 30"

CDCI-17

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-16	B	10YR5/6	Fine Sand
16-80	C	10YR5/3	Fine Sand
80-108	C2	10YR5/3	Gravelly Sand

Many cobbles and stones in C Layer
C2 Layer primarily gravel
Mottling @ 24"
Water @ 80"

CDCI-19

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	B	10YR5/6	Sand
12-120	C	10YR5/3	Gravelly Sand

Many cobbles and stones in C Layer
Mottling @ 60"
Water @ 90"

CDCI-14

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-16	A	10YR3/2	Sandy Loam
16-32	B	10YR5/6	Sandy Loam
32-108	C	10YR5/3	Sandy Loam

Mottling @ 30"
Water @ 30"

CDCI-16

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-48	FILL	-----	-----
48-80	C	10YR5/3	Loamy Sand

Mottling @ 56"
Water @ 72"
Ledge @ 80"

CDCI-18

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-24	B	10YR5/6	Sand
24-104	C	10YR5/3	Gravelly Sand

Many cobbles and stones in C Layer
Mottling @ 80"
No water observed

CDCI-20

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	B	10YR5/6	Sand
12-102	C	10YR5/6	Gravelly Sand
102-138	2C	10YR5/3	F. Loamy Sand

Many cobbles and stones in C Layer
Mottling @ 102"
No water observed

Address: Murphy's Farm, Dracut, MA

Date: 4/3/2024

S.E.: Thomas Schomburg

Witness: N/a

Note: Test pits CDCI-14 - CDCI-23 performed in areas that have been stripped of top and subsoil. Soil has begun to weather.

CDCI-21

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-24	B	10YR5/6	Sand
24-48	C	10YR5/6	Gravelly Sand
48-80	2C	10YR5/3	F. Loamy Sand

Many cobbles and stones in C Layer

No mottling observed

No water observed

Ledge encountered at 80"

CDCI-22

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-16	B	10YR5/6	Sand
16-60	C	10YR5/6	Gravelly Sand
60-80	2C	10YR5/3	F. Loamy Sand

Many cobbles and stones in C Layer

No mottling observed

No water observed

Ledge encountered at 80"

CDCI-23

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-16	B	10YR5/6	Sand
16-54	C	10YR5/6	Gravelly Sand

Many cobbles and stones in C Layer

No mottling observed

No water observed

Ledge encountered at 54"

CDCI-24

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/2	Sand
8-16	B	10YR5/6	Sand
16-60	C	10YR5/6	Gravelly Sand
60-72	2C	10YR5/3	F. Loamy Sand

Many cobbles and stones in C Layer

Mottling @ 32"

Water @ 72"

Ledge encountered at 72"

Address: Murphy's Farm, Dracut, MA
Date: 12/4/2024
S.E.: Thomas Schomburg & Steven Cummings
Witness: N/A

Note: Test pits CDCI-25 - CDCI-608 performed in areas that have been stripped of top and subsoil. Soil has begun to weather.

CDCI-25

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-30	B	10YR6/6	Loamy Sand
30-120	C	10YR6/4	Gravelly Sand

CDCI-26

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-24	B	10YR6/6	Loamy Sand
24-72	C	10YR6/4	Gravelly Sand
72-120		10YR6/2	Sand

Mottling @ 72"

No water observed

Mottling @ 72"

No water observed

TP-27

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-66		10YR6/6	Gravelly Sand
66-120		10YR6/1	Sand

TP-470

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-10	A	10YR3/3	Sandy Loam
10-26	B	10YR5/6	Loamy Sand
26-78	C	10YR7/3	Fine Sand

Mottling @ 66"

No water observed

No mottling observed

No water observed

TP-471

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	A	10YR3/3	Loamy Sand
12-24	B	10YR5/6	Loamy Sand
24-80	C	10YR7/3	Fine Sand

TP-472

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	A	10YR5/6	Loamy Sand
12-24	B	10YR5/3	Loamy Sand
24-72	C	10YR7/3	Fine Sand

No mottling observed

No water observed

No mottling observed

No water observed

TP-473

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/3	Sandy Loam
8-18	B	10YR5/6	Loamy Sand
18-72	C	10YR7/3	Fine Sand

TP-474

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/3	Sandy Loam
8-20	B	10YR5/6	Loamy Sand
20-72	C	10YR6/4	Medium Sand

No mottling observed

No water observed

No mottling observed

No water observed

Address: Murphy's Farm, Dracut, MA
Date: 12/4/2024
S.E.: Thomas Schomburg & Steven Cummings
Witness: N/A

TP-475

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/2	Loamy Sand
8-18	B	10YR3/6	Loamy Sand
18-72	C	10YR6/4	Medium Sand

No mottling observed
No water observed

TP-477

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-6	A	10YR3/3	Sandy Loam
6-28	B	10YR5/4	Loamy Sand
28-72	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-479

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-10	A	10YR3/2	Loamy Sand
10-22	B	10YR5/4	Loamy Sand
22-80	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-481

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/2	Loamy Sand
8-16	B	10YR5/4	Loamy Sand
16-80	C	10YR7/3	Medium Sand

Mottling @ 48"
No water observed

TP-476

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-16	A	10YR3/2	Loamy Sand
16-28	B	10YR3/4	Loamy Sand
28-72	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-478

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-6	A	10YR3/3	Sandy Loam
6-26	B	10YR5/4	Loamy Sand
26-72	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-480

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-6	A	10YR3/3	Sandy Loam
6-18	B	10YR5/6	Loamy Sand
18-72	C	10YR7/3	Sand

No mottling observed
No water observed

TP-480

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-6	A	10YR3/3	Sandy Loam
6-18	B	10YR5/6	Loamy Sand
18-72	C	10YR7/3	Sand

No mottling observed
No water observed

Address: Murphy's Farm, Dracut, MA
Date: 12/4/2024
S.E.: Thomas Schomburg & Steven Cummings
Witness: N/A

TP-482

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/3	Sandy Loam
8-28	B	10YR5/6	Loamy Sand
28-78	C	10YR7/3	Medium Sand

Mottling @ 48"
No water observed

TP-484

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-10	A	10YR3/3	Sandy Loam
10-24	B	10YR6/6	Loamy Sand
24-78	C	10YR8/3	Medium Sand

Mottling @ 36"
No water observed

TP-486

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-6		10YR3/3	Sandy Loam
6-24		10YR5/8	Loamy Sand
24-72		10YR7/4	Medium Sand

No mottling observed
No water observed

TP-488

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/2	Loamy Sand
8-20	B	10YR5/8	Loamy Sand
20-72	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-483

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-16	A	10YR5/2	Loamy Sand
16-24	B	10YR5/4	Loamy Sand
24-74	C	10YR7/3	Fine Sand

Mottling @ 36"
No water observed

TP-485

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-10	A	10YR5/2	Loamy Sand
10-32	B	10YR5/4	Loamy Sand
32-84	C	10YR7/3	Fine Sand

Mottling @ 36"
No water observed

TP-487

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/2	Loamy Sand
8-24	B	10YR5/8	Loamy Sand
24-72	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-489

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-6		10YR3/3	Sandy Loam
6-22		10YR5/8	Loamy Sand
22-72		10YR7/4	Medium Sand

No mottling observed
No water observed

Address: Murphy's Farm, Dracut, MA
Date: 12/4/2024
S.E.: Thomas Schomburg & Steven Cummings
Witness: N/A

TP-490

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-6	A	10YR3/2	Loamy Sand
6-16	B	10YR5/8	Loamy Sand
16-48	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-492

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	A	10YR3/2	Loamy Sand
12-24	B	10YR5/8	Loamy Sand
24-72	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-494

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-30	B	10YR5/6	Loamy Sand
30-84		10YR6/4	Gravelly Sand
84-120		10YR6/1	Sand

Mottling @ 84"
No water observed

TP-496

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	B	10YR5/6	Loamy Sand
12-72	C	10YR6/4	Medium Sand
72-120	C2	10YR6/1	Fine Sand

Mottling @ 84"
No water observed

TP-491

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8		10YR3/3	Sandy Loam
8-28		10YR5/8	Loamy Sand
28-74		10YR7/4	Medium Sand

Mottling @ 60"
No water observed

TP-493

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-8	A	10YR3/3	Sandy Loam
8-24	B	10YR5/8	Loamy Sand
24-78	C	10YR7/4	Medium Sand

No mottling observed
No water observed

TP-495

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-72	C	10YR6/6	Medium Sand
72-132	C2	10YR7/4	Fine Sand

Mottling @ 84"
No water observed

TP-497

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-60	Fill	-	-
60-120	C	10YR7/3	Loamy Sand

No mottling observed
No water observed

Address: Murphy's Farm, Dracut, MA
Date: 12/4/2024
S.E.: Thomas Schomburg & Steven Cummings
Witness: N/A

TP-498

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-60	Fill	-	-
60-120	C	10YR7/3	Fine Sand

No mottling observed
No water observed

TP-600

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-90	Fill	-	-
90-126	C	10YR7/3	Sand

No mottling observed
No water observed

TP-602

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-66	Fill	-	-
66-84	B	10YR5/4	Sand
84-120	C	10YR7/3	Sand

Mottling @ 86"
No water observed

TP-604

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-24	Fill	-	-
24-108	C	10YR7/3	Sand

Mottling @ 48"
No water observed

TP-499

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-60	Fill	-	-
60-138	C	10YR7/3	Fine Sand

No mottling observed
No water observed

TP-601

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-96	Fill	-	-
96-120	C	10YR7/3	Sand

Mottling @ 96"
No water observed

TP-603

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-24	Fill	-	-
24-120	C	10YR5/3	Gravelly Sand

Mottling @ 60"
No water observed

TP-605

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-72	Fill	-	-
72-108	C	10YR7/3	Sand

Mottling @ 60"
No water observed

Address: Murphy's Farm, Dracut, MA
Date: 12/4/2024
S.E.: Thomas Schomburg & Steven Cummings
Witness: N/A

TP-606

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-12	A	10YR3/2	Sandy Loam
12-32	B	7.5YR4/6	Loamy Sand
32-120	C	10YR6/3	Medium Sand

Mottling @ 48"

No water observed

TP-608

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-48	Fill	-	-
48-120	C	10YR7/4	Medium Sand

Mottling @ 84"

No water observed

TP-610

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-66	Fill	-	-
66-168	C	10YR3/2	Medium Sand

Mottling @ 104"

No water observed

TP-607

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-48	Fill	-	-
48-72	C	10YR5/3	Sand

Pit terminated early, no space to put material. See TP-609

No mottling observed

No water observed

TP-609

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-48	Fill	-	-
48-120	C	10YR 5/3	Medium Sand

No mottling observed

No water observed

TP-611

<u>Depth</u>	<u>Horizon</u>	<u>Color</u>	<u>Texture</u>
0-27	Fill	-	-
27-132	C	10YR5/2	Medium Sand

No mottling observed

No water observed



SITE LOCATION: MURPHY'S FARM

PID #:

TECHNICIAN: TWS

DATE: 4/22/25

WEATHER/TEMPERATURE: 70° / PARTLY CLOUDY

FIELD PERMEABILITY TEST #: 1

D - reservoir diameter (cm)	8.25
d - well hole diameter (cm)	8.3
H - height of water in well (cm)	18.0
Depth below ground surface (cm)	140

Soil Texture	GRAVELLY SAND
Soil Structure	SINGLE GRAIN
α^* (cm-1)	0.36
C - Factor	1.36

[illegible]

Quasi Steady-State Rate of Fall (R) = 40 cm/min

$$K_{fs} = 2.8 \times 10^{-4} \text{ m/s} = 39.69 \text{ in/hr}$$

$$K_{fs} (FS=2) = 39.69 \div 2 = 19.8 \text{ in/hr}$$



SITE LOCATION:

PID #: _____

TECHNICIAN: _____

WEATHER/TEMPERATURE:

D - reservoir diameter (cm)	8.25	Soil Texture	GRAVELLY SAND
d - well hole diameter (cm)	8.3	Soil Structure	SINGLE GRAIN
H - height of water in well (cm)	15.0	α^* (cm ⁻¹)	0.36
Depth below ground surface (cm)	65	C - Factor	1.36

[illegible]

Quasi Steady-State Rate of Fall (R) = 10 cm/min

$$K_{fs} = 6.9 \times 10^{-5} \text{ m/s} = 9.78 \text{ in/hr}$$

$$FS(2) \Rightarrow 4.89 \text{ in/hr}$$



SITE LOCATION:

PID #: _____

TECHNICIAN: _____

WEATHER/TEMPERATURE:

D - reservoir diameter (cm)	8.25	Soil Texture	GRAVELLY SAND
d - well hole diameter (cm)	8.3	Soil Structure	SINGLE GRAIN
H - height of water in well (cm)	15.0	α^* (cm-1)	0.36
Depth below ground surface (cm)	133	C - Factor	1.36

[illegible]

Quasi Steady-State Rate of Fall (R) = 40 cm/min

$$K_{fs} = 2.8 \times 10^{-4} \text{ m/s} = 39.69 \text{ in/hr}$$

$$FS(2) \Rightarrow 19.8 \text{ in/hr}$$



**Engineering
Technologies
Canada Ltd.**

OWNER'S NAME: SEE P-1

SITE LOCATION:

PID #: _____

TEST PIT #: P-4 @ SUB 3 (TP-601)

TECHNICIAN:

DATE: 4/22/25

WEATHER/TEMPERATURE:

FIELD PERMEABILITY TEST #:

D - reservoir diameter (cm)	8.25
d - well hole diameter (cm)	8.3
H - height of water in well (cm)	15.0
Depth below ground surface (cm)	92

Soil Texture GRAVELLY SAND
Soil Structure SINGLE GRAIN
 α^* (cm-1) 0.36
C - Factor 1.36

[illegible]

Quasi Steady-State Rate of Fall (R) = 11 cm/min

$$K_{fs} = 7.6 \times 10^{-5} \text{ m/s} = 10.77 \text{ in/hr}$$

$$FS(2) \Rightarrow 5.39 \text{ m/hr}$$



SITE LOCATION: _____

PID #: _____

TECHNICIAN: _____

DATE: 4/22/25

WEATHER/TEMPERATURE:

D - reservoir diameter (cm)	8.25
d - well hole diameter (cm)	8.3
H - height of water in well (cm)	15.0
Depth below ground surface (cm)	129

Soil Structure SG α^* (cm⁻¹) 6.36

C - Factor 1.36

Quasi Steady-State Rate of Fall (R) = 40 cm/min

$$K_{fs} = 2.8 \times 10^{-4} \text{ m/s} = 39.69 \text{ in/hr}$$

$$FS(2) \Rightarrow 19.8 \text{ in/hr}$$



SITE LOCATION:

PID #: _____

TECHNICIAN: _____

WEATHER/TEMPERATURE:

FIELD PERMEABILITY TEST #:

D - reservoir diameter (cm)	8.25	Soil Texture	60. Sand
d - well hole diameter (cm)	8.3	Soil Structure	SG
H - height of water in well (cm)	15.0	α^* (cm-1)	0.36
Depth below ground surface (cm)	92	C - Factor	1.36

[illegible]

Quasi Steady-State Rate of Fall (R) = 40 cm/min

$$K_{fs} = 2.8 \times 10^{-4} \text{ m/s} = 39.96 \text{ in/hr}$$

$$FS(2) \Rightarrow 19.8 \text{ m/hr}$$



OWNER'S NAME: SEE P-1

SITE LOCATION:

PID #: _____

TECHNICIAN: _____

TEST PIT #: P-7 C TP-25

DATE: _____

WEATHER/TEMPERATURE: _____

FIELD PERMEABILITY TEST #:

D - reservoir diameter (cm) 6.25

Soil Texture GR. SAND

d - well hole diameter (cm) 8.3

Soil Structure	56
----------------	----

H - height of water in well (cm)	15.0
----------------------------------	------

 α^* (cm⁻¹) 0.36

Depth below ground surface (cm)	123
---------------------------------	-----

C - Factor	1.36
------------	------

[illegible]

Quasi Steady-State Rate of Fall (R) = 40 cm/min

$$K_{fs} = 2.8 \times 10^{-4} \text{ m/s} = 36.96 \text{ in/hr}$$

$$FS(2) = 19.8 \text{ in/hr}$$



$$FS(2) = 19.8 \text{ in/hr}$$

LONG TERM OPERATIONS AND MAINTENANCE PROGRAM

September 1, 2025

This Long-Term Operations and Maintenance Program Plan has been prepared in accordance with the Stormwater Management Policy issued by the Department of Environmental Protection (DEP) for the proposed multi-family residential development located at Murphy's Farm in Dracut, MA. Upon a period beginning twelve months after the completion of the roadway, all structural BMP's shall be inspected twice annually, once in April and once in November. The inspection shall be performed as indicated below:

Street Sweeping

Street sweeping can be an effective method to reduce pollutant loading in runoff generated from pavement. Street sweeping shall be performed quarterly, using a high efficiency vacuum sweeper or regenerative air sweeper, with sweeping scheduled primarily in the spring and fall.

Snow Storage / Removal

Snow plowed from the proposed roadway will be placed or disposed of in accordance with the policy developed by DEP. Under no circumstances shall snow plowed or removed from the road be stockpiled within wetland resource areas. If conditions arise where snow storage areas are at capacity the Operator is required to remove and dispose of snow off site in conformance with all local, state and federal regulations.

Catch Basins

Catch basins shall be inspected and/or cleaned at least four times per year and at the end of the foliage and snow removal seasons. Sediment shall be removed four times per year or whenever the depth of the deposits is greater than or equal to one half the depth from the bottom of the invert of the lowest pipe in the basin. Sediment shall be removed and disposed of with a truck-mounted vacuum unit or other appropriate apparatus. The sediment will be disposed of at an approved offsite location in accordance with all applicable local, state, and federal regulations.

Drainage Outfalls

The outlets of the storm water management system will be inspected biannually. Any evidence of erosion or other damage will be reported to the appropriate town representative and repaired as soon as possible. Any sediment should be removed from the outlet structures.

Sediment Forebay

Sediments and associated pollutants are removed only when sediment forebays are actually cleaned out, so regular maintenance is essential. Frequently removing accumulated sediments will make it less likely that sediments will be re-suspended. At a minimum, inspect sediment forebays monthly and clean them out at least four times per year. Stabilize the floor and sidewalls of the sediment forebay before making it operational, otherwise the practice will discharge excess amounts of suspended sediments. When mowing grasses, keep the grass height no greater than 6 inches. Set mower blades no lower than 3 to 4 inches. Check for signs of riling and gulying and repair as needed. After removing the sediment, replace any vegetation damaged during the clean-out by either reseeding or resodding. When reseeding, incorporate practices such as hydroseeding with a tackifier, blanket, or similar practice to ensure that no scour occurs in the forebay while the seeds germinate and develop roots.

Infiltration Basin

Infiltration basins are prone to clogging and failure, so it is imperative to develop and implement aggressive maintenance plans and schedules. Installing the required pretreatment BMPs will significantly reduce maintenance requirements for the basin. Inspections and preventive maintenance must be performed at least twice a year.

Once the basin is in use, inspect it after every major storm for the first few months to ensure it is stabilized and functioning properly and if necessary, take corrective action. Note how long water remains standing in the basin after a storm; standing water within the basin 48 to 72 hours after a storm indicates that the infiltration capacity may have been overestimated. If the ponding is due to clogging, immediately address the reasons for the clogging (such as upland sediment erosion, excessive compaction of soils, or low spots).

Thereafter, inspect the infiltration basin at least twice per year. Important items to check during the inspection include:

- Signs of differential settlement,
- Cracking,
- Erosion,
- Leakage in the embankments,
- Tree growth on the embankments,
- Condition of riprap,
- Operation of the drawdown device,
- Sediment accumulation and
- The health of the turf.

At least twice a year, mow the buffer area, side slopes, and basin bottom. Remove grass clippings and accumulated organic matter to prevent an impervious organic mat from forming. Remove trash and debris at the same time. Use deep tilling to break up clogged surfaces and revegetate immediately. Remove sediment from the basin as necessary but wait until the floor of the basin is thoroughly dry. Use light equipment to remove the top layer to not compact the underlying soil. Deeply till the remaining soil and revegetate as soon as possible. Inspect and clean pretreatment devices associated with basins at least twice a year, and ideally every other month.

Stormceptor (CDS)

Inspection and Maintenance is fundamental to the long-term performance of a Stormceptor oil/grit separator system. Stormceptors should be inspected post construction, prior to the discharge of any stormwater. Additional inspections should occur every 6 months for the first year to determine the sediment accumulation rate. After the first year, inspections should occur based on first-year observations or local requirements, whichever is stricter. Cleanings should be performed with a standard vacuum truck.

Subsurface Systems

The Subsurface systems shall be inspected twice annually, once in April and once in November as well as after any major storm (2-Year recurrence or greater). If upon visual inspection it is found that sediment has accumulated, a stadia rod should be inserted into the inspection port to determine the depth of sediment. When the average depth of sediment exceeds 3" throughout the length of the chamber, a clean-out should be performed. Cleanings should be performed with a standard vacuum truck. Any and all debris and/or sediments shall be removed from the units and be disposed of at an approved offsite location in accordance with all applicable local, state, and federal regulations. Outlet structures should be visually inspected for clogging conditions, and cleaned as required.

Mosquito Control Plan

Mosquito pupae and larvae need at least four days of ponded water to emerge as adults. Ensure that Infiltration Basin and subsurface system maintenance is performed as required so that the period of infiltration is less than 72 hours per DEP requirements.

Owner:

The Homes At Murphy's Farm, LLC
(c/o Kevin O'Brien)
18 Cassimere Street
Andover, MA 01810

Applicant / Responsible Party (During Construction):

The Homes At Murphy's Farm, LLC
(c/o Kevin O'Brien)
18 Cassimere Street
Andover, MA 01810

Responsible Party (After Construction):

A Property Management company shall be created and shall be responsible for the maintenance of the stormwater basins, subsurface systems, drainage outfalls, catch basins, and stormceptors.

Construction Period Pollution Prevention Plan:

A Stormwater Pollution Prevention Plan (SWPPP) will be prepared prior to construction to address the project's NPDES obligations with the EPA. The SWPPP will address the requirements of the Construction Period Pollution Prevention Plan.

System Map:

See Comprehensive Permit Site Plan for Murphy's Farm and attached sketch for the location of all stormwater management facilities.

Estimated Operations and Maintenance Budget

It is anticipated that the stormwater management system will require an annual budget of \$10,000 to maintain.

CDS[®] Inspection and Maintenance Guide



Maintenance

The CDS system should be inspected at regular intervals and maintained when necessary to ensure optimum performance. The rate at which the system collects pollutants will depend more heavily on site activities than the size of the unit. For example, unstable soils or heavy winter sanding will cause the grit chamber to fill more quickly but regular sweeping of paved surfaces will slow accumulation.

Inspection

Inspection is the key to effective maintenance and is easily performed. Pollutant transport and deposition may vary from year to year and regular inspections will help ensure that the system is cleaned out at the appropriate time. At a minimum, inspections should be performed twice per year (e.g. spring and fall) however more frequent inspections may be necessary in climates where winter sanding operations may lead to rapid accumulations, or in equipment washdown areas. Installations should also be inspected more frequently where excessive amounts of trash are expected.

The visual inspection should ascertain that the system components are in working order and that there are no blockages or obstructions in the inlet and separation screen. The inspection should also quantify the accumulation of hydrocarbons, trash, and sediment in the system. Measuring pollutant accumulation can be done with a calibrated dipstick, tape measure or other measuring instrument. If absorbent material is used for enhanced removal of hydrocarbons, the level of discoloration of the sorbent material should also be identified during inspection. It is useful and often required as part of an operating permit to keep a record of each inspection. A simple form for doing so is provided.

Access to the CDS unit is typically achieved through two manhole access covers. One opening allows for inspection and cleanout of the separation chamber (cylinder and screen) and isolated sump. The other allows for inspection and cleanout of sediment captured and retained outside the screen. For deep units, a single manhole access point would allow both sump cleanout and access outside the screen.

The CDS system should be cleaned when the level of sediment has reached 75% of capacity in the isolated sump or when an appreciable level of hydrocarbons and trash has accumulated. If absorbent material is used, it should be replaced when significant discoloration has occurred. Performance will not be impacted until 100% of the sump capacity is exceeded however it is recommended that the system be cleaned prior to that for easier removal of sediment. The level of sediment is easily determined by measuring from finished grade down to the top of the sediment pile. To avoid underestimating the level of sediment in the chamber, the measuring device must be lowered to the top of the sediment pile carefully. Particles at the top of the pile typically offer less resistance to the end of the rod than consolidated particles toward the bottom of the pile. Once this measurement is recorded, it should be compared to the as-built drawing for the unit to determine whether the height of the sediment pile off the bottom of the sump floor exceeds 75% of the total height of isolated sump.

Cleaning

Cleaning of a CDS system should be done during dry weather conditions when no flow is entering the system. The use of a vacuum truck is generally the most effective and convenient method of removing pollutants from the system. Simply remove the manhole covers and insert the vacuum hose into the sump. The system should be completely drained down and the sump fully evacuated of sediment. The area outside the screen should also be cleaned out if pollutant build-up exists in this area.

In installations where the risk of petroleum spills is small, liquid contaminants may not accumulate as quickly as sediment. However, the system should be cleaned out immediately in the event of an oil or gasoline spill should be cleaned out immediately. Motor oil and other hydrocarbons that accumulate on a more routine basis should be removed when an appreciable layer has been captured. To remove these pollutants, it may be preferable to use absorbent pads since they are usually less expensive to dispose than the oil/water emulsion that may be created by vacuuming the oily layer. Trash and debris can be netted out to separate it from the other pollutants. The screen should be power washed to ensure it is free of trash and debris.

Manhole covers should be securely seated following cleaning activities to prevent leakage of runoff into the system from above and also to ensure that proper safety precautions have been followed. Confined space entry procedures need to be followed if physical access is required. Disposal of all material removed from the CDS system should be done in accordance with local regulations. In many jurisdictions, disposal of the sediments may be handled in the same manner as the disposal of sediments removed from catch basins or deep sump manholes.



CDS Model	Diameter		Distance from Water Surface to Top of Sediment Pile		Sediment Storage Capacity	
	ft	m	ft	m	y ³	m ³
CDS1515	3	0.9	3.0	0.9	0.5	0.4
CDS2015	4	1.2	3.0	0.9	0.9	0.7
CDS2015	5	1.3	3.0	0.9	1.3	1.0
CDS2020	5	1.3	3.5	1.1	1.3	1.0
CDS2025	5	1.3	4.0	1.2	1.3	1.0
CDS3020	6	1.8	4.0	1.2	2.1	1.6
CDS3025	6	1.8	4.0	1.2	2.1	1.6
CDS3030	6	1.8	4.6	1.4	2.1	1.6
CDS3035	6	1.8	5.0	1.5	2.1	1.6
CDS4030	8	2.4	4.6	1.4	5.6	4.3
CDS4040	8	2.4	5.7	1.7	5.6	4.3
CDS4045	8	2.4	6.2	1.9	5.6	4.3
CDS5640	10	3.0	6.3	1.9	8.7	6.7
CDS5653	10	3.0	7.7	2.3	8.7	6.7
CDS5668	10	3.0	9.3	2.8	8.7	6.7
CDS5678	10	3.0	10.3	3.1	8.7	6.7

Table 1: CDS Maintenance Indicators and Sediment Storage Capacities



Support

- Drawings and specifications are available at www.contechstormwater.com.
- Site-specific design support is available from our engineers.

©2017 Contech Engineered Solutions LLC, a QUIKRETE Company

Contech Engineered Solutions LLC provides site solutions for the civil engineering industry. Contech's portfolio includes bridges, drainage, sanitary sewer, stormwater, earth stabilization and wastewater treatment products. For information, visit www.ContechES.com or call 800.338.1122

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS AN EXPRESSED WARRANTY OR AN IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE. SEE THE CONTECH STANDARD CONDITION OF SALES (VIEWABLE AT WWW.CONTECHES.COM/COS) FOR MORE INFORMATION.


The product(s) described may be protected by one or more of the following US patents: 5,322,629; 5,624,576; 5,707,527; 5,759,415; 5,788,848; 5,985,157; 6,027,639; 6,350,374; 6,406,218; 6,641,720; 6,511,595; 6,649,048; 6,991,114; 6,998,038; 7,186,058; 7,296,692; 7,297,266; 7,517,450 related foreign patents or other patents pending.

CDS Inspection & Maintenance Log

CDS Model: _____ Location: _____

[illegible]

1. The water depth to sediment is determined by taking two measurements with a stadia rod: one measurement from the manhole opening to the top of the sediment pile and the other from the manhole opening to the water surface. If the difference between these measurements is less than the values listed in table 1 the system should be cleaned out. **Note: to avoid underestimating the volume of sediment in the chamber, the measuring device must be carefully lowered to the top of the sediment pile.**
2. For optimum performance, the system should be cleaned out when the floating hydrocarbon layer accumulates to an appreciable thickness. In the event of an oil spill, the system should be cleaned immediately.



PROJECT NOTES:

1. SEE SHEET C-1 FOR FULL PROJECT NOTES
2. SEE CONSTRUCTION SEQUENCING NOTES ON SHEET D-1.
3. CONTRACTOR IS TO VERIFY THE LOCATION, DEPTH, AND CONDITION OF THE EXISTING SEWER AND WATER PRIOR TO CONSTRUCTION.
4. PROPOSED WATER AND SEWER MAINS TO MAINTAIN 10'-FT OF HORIZONTAL SEPARATION. WHERE SANITARY SEWERS CROSS WATER MAINS, THE SEWER SHALL BE LAID AT SUCH AN ELEVATION THAT THE CROWN OF THE SEWER IS AT LEAST 18 INCHES BELOW THE INVERT OF THE WATER MAIN. IF THE ELEVATION OF THE SEWER CANNOT BE VARIED TO MEET THIS REQUIREMENT, THE WATER MAIN SHALL BE RELOCATED TO PROVIDE THIS SEPARATION OR CONSTRUCTED WITH MECHANICAL JOINT PIPE FOR A DISTANCE OF 10 FEET ON EACH SIDE OF THE SEWER. ONE FULL LENGTH OF WATER MAIN SHALL BE CENTERED OVER THE SEWER SO THAT BOTH JOINTS WILL BE AS FAR FROM THE SEWER AS POSSIBLE. WHENEVER IT IS IMPOSSIBLE TO OBTAIN VERTICAL SEPARATION AS STIPULATED ABOVE, BOTH THE WATER MAIN AND SEWER SHALL BE ENCASED IN CONCRETE FOR A MINIMUM DISTANCE OF 10 FEET FROM THE CROSSING POINT OF THE OTHER PIPE AS MEASURED NORMALLY FROM ALL POINTS ALONG THE PIPE.
5. PROPOSED GAS AND ELECTRIC SERVICE LOCATIONS TO BE CONFIRMED BY THE UTILITY COMPANY.
6. DOWNSPOUT/GUTTER LOCATIONS TO BE COORDINATED WITH ARCHITECT

08/21/25	REVISED LAYOUT
05/09/25	REV. PER PEER REVIEW COMMENTS
03/27/25	REV. PER PEER REVIEW COMMENTS
02/25/25	REV. PER PEER REVIEW COMMENTS
01/21/25	REV. PER INTERNAL REVIEW
12/30/24	REV. PER PEER REVIEW COMMENTS
10/04/24	REV. PER PEER REVIEW COMMENTS
DATE	DESCRIPTION

APPLICANT:

THE HOMES AT MURPHY'S FARM LLC
18 CASSIMERE STREET
ANDOVER, MA 01810

PROJECT:

MURPHY'S FARM
DRACUT, MA 01826

DATE ISSUED: APRIL 22, 2024

PROJECT #: 23-10524

PREPARED BY: TWS

PROFESSIONAL ENGINEER FOR CIVIL DESIGN
CONSULTANTS, INC.

CIVIL DESIGN
CONSULTANTS, INC.

344 North Main Street | Andover, MA 01810
(978) 448-0500 | www.civil055.com

DRAWING TITLE:

OVERALL GRADING & UTILITIES PLAN

DRAWING #:

C-4C

LEGEND	
PROPERTY LINE	
ABUTTERS PROPERTY LINE	
EXISTING EDGE OF PAVEMENT	
LIMIT OF BORDERING VEGETATED WETLAND (B/VW)	
WETLAND FLAG	ΔNF 80
WETLAND	
50 FT BUFFER ZONE TO B/VW	
100 FT BUFFER ZONE TO B/VW	
EXISTING CONTOUR	
EXISTING WATERSHED BOUNDARY	
EXISTING TC	
HYDROLOGIC SOILS GROUP A	
HYDROLOGIC SOILS GROUP B	
HYDROLOGIC SOILS GROUP C	
HYDROLOGIC SOILS GROUP D	

SOILS SUMMARY:	
SYMBOL	DESCRIPTION
32B	WAREHAM LFS, 0-5% SLOPES
51A	SWANSEA MUCK, 0-1% SLOPES
52A	FREETOWN MUCK, 0-1% SLOPES
253B	HINKLEY LS, 3-8% SLOPES
253C	HINKLEY LS, 8-15% SLOPES
253D	HINKLEY LS, 15-25% SLOPES
54B	MERRIMAC FSL, 3-8% SLOPES
255B	WINDSOR LS, 3-8% SLOPES
255C	WINDSOR LS, 8-15% SLOPES
256A	DERFIELD LFS, 0-3% SLOPES
420C	CANTON FSL, 8-15% SLOPES
422B	CANTON FSL, 0-8% SLOPES
600	PITS, GRAVEL
601	PITS, QUARRY
653	UDORTHERTS, SANDY
654	UDORTHERTS, LOAMY

HSG	A/D
A/D	B/D
B/D	A
A	A
A	A
A	A
A	A
A	A
B	N/A
N/A	N/A
N/A	N/A
N/A	N/A



08/21/25	REVISED LAYOUT
05/09/25	REV. PER PEER REVIEW COMMENTS
03/27/25	REV. PER PEER REVIEW COMMENTS
02/25/25	REV. PER PEER REVIEW COMMENTS
01/21/25	REV. PER INTERNAL REVIEW
12/30/24	REV. PER PEER REVIEW COMMENTS
10/04/24	REV. PER PEER REVIEW COMMENTS
DATE	DESCRIPTION

APPLICANT:
THE HOMES AT MURPHY'S FARM LLC
18 CASSIMERE STREET
ANDOVER, MA 01810

PROJECT:
MURPHY'S FARM
DRACUT, MA 01826

DATE ISSUED:	APRIL 22, 2024
PROJECT #:	23-10524
PREPARED BY:	TWS

PROFESSIONAL ENGINEER FOR CIVIL DESIGN
CONSULTANTS, INC.



DRAWING TITLE:
EXISTING WATERSHED PLAN

DRAWING #:
EWA

LEGEND	
PROPERTY LINE	
PROPOSED BUILDING	
PROPOSED POROUS PAVEMENT	
PROPOSED BIT. CONC.	
EXISTING CONTOUR	
PROPOSED CONTOUR	1129
PROPOSED RETAINING WALL	
PROPOSED WATERSHED BOUNDARY	
PROPOSED TC	
HYDROLOGIC SOILS GROUP A	
HYDROLOGIC SOILS GROUP B	

SOILS SUMMARY:

SYMBOL	DESCRIPTION	HSG
32B	WAREHAM LFS, 0-5% SLOPES	A/D
51A	SWANSEA MUCK, 0-1% SLOPES	B/D
52A	FREETOWN MUCK, 0-1% SLOPES	A
253B	HINKLEY LS, 3-8% SLOPES	A
253C	HINKLEY LS, 8-15% SLOPES	A
253D	HINKLEY LS, 15-25% SLOPES	A
254B	MERRIMAC FSL, 3-8% SLOPES	A
255B	WINDSOR LS, 3-8% SLOPES	A
255C	WINDSOR LS, 8-15% SLOPES	A
256A	DEERFIELD LFS, 0-3% SLOPES	B
420C	CANTON FSL, 8-15% SLOPES	N/A
422B	CANTON FSL, 0-8% SLOPES	N/A
600	PITS, GRAVEL	N/A
601	PITS, QUARRY	N/A
653	UDORTMENTS, SANDY	N/A
654	UDORTMENTS, LOAMY	N/A



09/01/25	REVISED LAYOUT
05/09/25	REV. PER PEER REVIEW COMMENTS
03/27/25	REV. PER PEER REVIEW COMMENTS
02/25/25	REV. PER PEER REVIEW COMMENTS
01/21/25	REV. PER INTERNAL REVIEW
12/30/24	REV. PER PEER REVIEW COMMENTS
10/04/24	REV. PER PEER REVIEW COMMENTS
DATE	DESCRIPTION

APPLICANT:
THE HOMES AT MURPHY'S FARM LLC
18 CASSIMERE STREET
ANDOVER, MA 01810

PROJECT:
MURPHY'S FARM
DRACUT, MA 01826

DATE ISSUED:	APRIL 22, 2024
PROJECT #:	23-10524
PREPARED BY:	TWS

PROFESSIONAL ENGINEER FOR CIVIL DESIGN
CONSULTANTS, INC.



DRAWING TITLE:
PROPOSED WATERSHED PLAN

DRAWING #:
PWP-1