



# HANCOCK ASSOCIATES



**Stormwater Report**  
*In Support Of*  
**A Comprehensive Permit and Notice of Intent Filing**  
*For*  
**2041 Bridge Street**  
**(Map 19, Lot 39)**  
**Dracut, MA**

---

**PREPARED BY:**  
Hancock Associates  
#27164

**PREPARED FOR:**  
Marsh Hill Management, LLC  
February 2025  
*REVISED: October 2025*

## Table of Contents

Introduction.....	1
Standard 1: No New Untreated Discharges.....	1
Standard 2: Peak Rate Attenuation .....	1
Standard 3: Recharge .....	3
Standard 4: Water Quality.....	4
Standard 5: Land Uses with Higher Potential Pollutant Loads .....	6
Standard 6: Critical Area.....	6
Standard 7: Redevelopment.....	6
Standard 8: Construction Period Pollution Prevention and Erosion & Sedimentation Control .....	6
Standard 9: Operations and Maintenance Plan.....	8
Standard 10: Prohibition of Illicit Discharges.....	11

## Tables

Table 1: Peak Rates of Runoff.....	3
------------------------------------	---

### Appendices

Appendix I Locus Map
Appendix II Stormwater Checklist
Appendix III Stormwater Best Management Practice Plan
Appendix IV NRCS Soils Map
Appendix V Pre and Post Development Watershed Plans
Appendix VI Hydrocad Output
Appendix VII Hydrocad Output for Recharge Volume
Appendix VIII Water Quality Sizing Information
Appendix IX Mounding Analysis
Appendix X Pipe Velocities
Appendix XI Operations and Maintenance Log

## Introduction

Marsh Hill Management, LLC proposes to construct a multi-family residential building at the property of 2041 Bridge Street, Dracut, MA located at the intersection of Marsh Hill Road and Bridge Street. Associated infrastructure related to the building will be constructed and includes paved vehicular and pedestrian ways, stormwater management systems, and utility services. The project area is currently comprised of undeveloped wooded land. The project area is accessed by Marsh Hill Road and consists of 5.3± acres and is bounded by Bridge Street to the west, Marsh Hill Road to the south, A.L. Prime Gas Station to the North and the Old Pasture Road residential subdivision to the east. Elevations on site range from 178 in the southeastern corner of the lot and drop to 137 due west at the edge of the wetlands, in the middle of the property and extend to the western property line on Bridge Street.

The project site is located on the side of a hill with wetlands located at the toe slope. In the existing condition, stormwater runoff runs down the hill side to the wetlands. The proposed stormwater system was designed to mimic the existing drainage pattern.

The proposed stormwater management system will include catch basins with deep sumps and hoods and hydrodynamic separators which will convey stormwater from the proposed parking areas and buildings to underground infiltration systems via a network of pipes. The proposed underground infiltration systems will reduce peak rates of runoff by promoting infiltration. Overflow from underground infiltration systems is governed by outlet control structure (OCS) and conveyed to the wetlands via flared end structures (FES) and energy dissipating rip rap aprons.

The proposed stormwater management system was designed to meet the Stormwater Management Standards described in the Massachusetts Stormwater Handbook and the town of Dracut's local Stormwater Management requirements. The following report describes the system's compliance with these standards.

## Standard 1: No New Untreated Discharges

The Massachusetts Stormwater Handbook states that no new stormwater conveyances may discharge untreated stormwater directly to or cause erosions in wetlands or waters of the Commonwealth. Stormwater from the site will be collected via deep sump catch basins with hoods and a network of pipes. The network of pipes connects to a hydrodynamic separator which provides 44% pretreatment. Flows from the hydrodynamic separator then outlet into underground infiltration systems, providing an additional 80% TSS removal. Overflow from the underground infiltration systems flows to energy dissipating rip rap aprons to prevent scouring and erosion to the wetland resource area.

## Standard 2: Peak Rate Attenuation

The Massachusetts Stormwater Handbook states that stormwater management systems shall be designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates. A summary of the existing and proposed discharge rates follows. The proposed condition discharge rates of runoff are at or below the existing rates to the same discharge points. Please see the attached "Pre-Development Watershed Plan" and "Post Development Watershed Plan" figures (Appendix IV) and HydroCAD output (Appendix V) for more information.

For the purpose of these calculations the following assumptions were made:

- MassMapper online GIS elevation data was used to delineate watershed boundary upgradient of the project area where on-site survey did not gather data.
- The same total watershed area of the drainage areas is used to compare the existing and proposed.
- The Natural Resources Conservation Service (NRCS) Web Soil Survey of Middlesex County defines soils in the project area as:
  - 300B, Montauk fine sandy loam, 3 to 8 percent slopes, Hydrologic Soil Group C

- 300C, Montauk fine sandy loam, 8 to 15 percent slopes, Hydrologic Soil Group C
- 51A, Swansea Muck, 0 to 3 percent slopes, Hydrologic Soil Group B/D
- On-site soil testing has confirmed Hydrologic Soils Groups and confirmed the presence of sandy parent soils in certain areas of the site.

One drainage areas have been modeled to represent the existing condition:

- Drainage Area 1S consists of wooded, paved and landscaped areas mapped as Hydrologic Soil Group C soils. Stormwater runoff from 1S drains via overland flow to the wetlands at the western half of the property.

In the proposed condition a stormwater management system will collect and treat stormwater runoff from the project site. This system will include deep sump hooded catch basins, isolator rows, and underground infiltration systems. Ten main drainage areas have been modeled to represent the proposed condition:

- Drainage Area 10S consists of wooded, paved, and landscaped areas mapped as Hydrologic Soil Group C soils. Stormwater runoff from 10S drains via overland flow to the wetlands at the western half of the property.
- Drainage Areas 11S, 12S, 13S, 14S, 15S, & 16S consists of wooded, paved, and landscaped areas mapped as Hydrologic Soil Group C soils. Stormwater runoff from these subcatchments drains via overland flow to deep sump and hooded catch basin/area drains. From the catch basins/area drains, stormwater travels to the underground infiltration systems via a network of pipes and drain manholes. From the underground infiltration systems discharge will then flow to the wetlands at the western half of the property via a flared end structure and rip rap aprons.
- Drainage Area, 20S consists of roof areas from the proposed building and mapped as Hydrologic Soil Group C soils. Stormwater runoff from 20S is captured by gutters and directed to downspouts. From the downspouts, stormwater travels to the underground infiltration systems via a network of pipes and drain manholes. From the underground infiltration systems discharge will then flow to the wetlands at the western half of the property via a flared end structure and rip rap aprons.
- Drainage Area, 21S & 22S consists of wooded, paved, and landscaped areas from off-site stormwater flows mapped as Hydrologic Soil Group C soils. Stormwater runoff from these subcatchments drains via overland flow to grassed drainage swales before being directed to a double grate, deep sump and hooded catch basin. From the catch basins, stormwater travels to a flared end structure and rip rap apron where discharge will then flow to the wetlands at the western half of the property.
- Drainage Area 17S consists of approximately 600 SF of pavement at the proposed driveway entrance to the site which is not captured internally by the site. The runoff from this portion of the site flows to the municipal drainage system in Marsh Hill Road which ultimately discharges to Peppermint Brook as the on site wetlands do as well.
- The analysis point 10R is representative of the combined wetlands and Peppermint Brook which are connected via a 12" concrete pipe located under bridge street. Runoff flows overland through the wetlands, and through the street drainage system to ultimately discharge to Peppermint Brook.

The following table compares the peak rates of runoff under the existing and proposed conditions using the latest NRCC Extreme Precipitation data:

*Table 1: Peak Rates of Runoff*

Discharge Point	Peak Rate (cfs)							
	2-Year Storm (3.04" Rainfall Depth)		10-Year Storm (4.60" Rainfall Depth)		25-Year Storm (5.83" Rainfall Depth)		100-Year Storm (8.37" Rainfall Depth)	
	Existing	Proposed	Existing	Proposed	Existing	Proposed	Existing	Proposed
1S/10R	3.76	2.92	9.03	6.60	13.67	10.95	23.83	19.90

cfs – Cubic Feet per Second

Discharge Point	Volume Table (cf)							
	2-Year Storm (3.04" Rainfall Depth)		10-Year Storm (4.60" Rainfall Depth)		25-Year Storm (5.83" Rainfall Depth)		100-Year Storm (8.37" Rainfall Depth)	
	Existing	Proposed	Existing	Proposed	Existing	Proposed	Existing	Proposed
1S/10R	14,114	10,368	31,559	24,018	47,204	37,505	82,301	70,206

cf – Cubic Feet

## Standard 3: Recharge

-The Massachusetts Stormwater Handbook states that loss of annual recharge to groundwater shall be eliminated or minimized. The annual recharge from the post-development site shall approximate the annual recharge from the pre-development conditions based on soil type. Recharge volumes are provided for all of the proposed impervious areas. For the purpose of these calculations, all of the development areas are considered to be Hydrologic Soil Group C. The required recharge volume is 0.25" multiplied by the area of impervious surfaces. Please see the attached Hydrocad summaries for the recharge volumes provided within the infiltration chambers (Appendix VI). The required volume is as follows:

-Required Recharge Volume, HSG C = Target Depth \* Impervious Area = 0.25" \* 56,970 SF = 1,187 CF

-The recharge volume is provided below the lowest outlets within the underground infiltration systems. The total recharge volume provided is 8,508 cubic feet. Since the volume provided is greater than the required recharge volume, the standard is met.

**P.UIS1 = 1,892 CF**

**P.UIS2 = 2,397 CF**

**P.UIS3 = 3,944 CF**

**P.UIS4 = 275 CF**

**TOTAL = 8,508 CF**

The Massachusetts Stormwater Handbook states that the recharge volume must drain within 72 hours. Observations in deep hole soil testing performed on-site indicate that the soil that the chamber system will be installed upon is sand. Please see the soil testing logs shown on the Grading Drainage and Utility Plan in the Permit Site Plan Set. The following "drawdown" calculation assumes two different Rawl's Rates; a Rawl's Rate of 2.41 inches per hour, corresponding to texture class "Loamy Sand" for P.UIS 2 & 3 and assumes a Rawl's Rate of 8.27 inches per hour, corresponding to texture class "Sand" for P.UIS 1 & 4. The Rawl's rates used in the calculations below are based on in situ soil testing to determine soil texture classification.

### **P.UIS1**

Drawdown Time = Storage Volume / (Rawl's Rate \* Bottom Area)  
= 1,892 CF / (8.27 in/hr \* 1,435 SF) = 1.9 Hours

### **P.UIS2**

Drawdown Time = Storage Volume / (Rawl's Rate \* Bottom Area)  
= 2,397 CF / (2.41 in/hr \* 1,271 SF) = 9.4 Hours

### **P.UIS3**

Drawdown Time = Storage Volume / (Rawl's Rate \* Bottom Area)  
= 3,944 CF / (2.41 in/hr \* 1,924 SF) = 10.2 Hours

### **P.UIS4**

Drawdown Time = Storage Volume / (Rawl's Rate \* Bottom Area)  
= 275 CF / (8.27 in/hr \* 364 SF) = 1.1 Hours

Since the drawdown times listed above are less than 72 hours, the requirement is met.

## Standard 4: Water Quality

### **State Requirements:**

The Massachusetts Stormwater Handbook states that systems shall be designed to remove 80% of the average annual post-development construction load of Total Suspended Solids (TSS) and 44% pretreatment for areas of rapidly infiltrating soils (infiltration rate > 2.4 inches per hour).

Water Quality Depth = 1" (for soils with infiltration rates > 2.4 inches per hour)  
 Water Quality Volume = 1" x Impervious Area = 1" x 56,970 SF = 4,748 CF

Since 8,508 CF (>4,748 CF) is retained via the underground infiltration systems, the standard is met.

### **Local Requirements:**

Per the requirements of the Town of Dracut Stormwater Rules and Regulations, stormwater runoff from vehicular paved areas will be treated for at least 90% TSS (Total Suspended Solids) and 60% Total Phosphorus (TP). To achieve this, 1" multiplied by the total post construction impervious area shall be retained.

Required Retention Depth = 1" (per local requirements)  
 Required Retention Volume = 1" x Impervious Area = 1" x 56,970 SF = 4,748 CF

Since 8,508 CF (>4,748 CF) is retained via the underground infiltration systems, the standard is met for TSS and TP removal.

### ***TSS Removal Train per State Requirements***

#### Contech CDS TSS removal calculations

Calculations for average TSS removal for each proposed CDS system is provided in Appendix VIII.

#### Isolator Row Sizing calculations

Per the StormTech Design Manual:

MC-3500 chambers are rated for a 0.24 cfs treatment flow rate for a minimum of 80% TSS removal.

SC-310 chambers are rated for a 0.10 cfs treatment flow rate for a minimum of 80% TSS removal.

The Massachusetts Department of Environmental Protection Wetlands Program Standard Method to Convert Required Water Quality Volume to a Discharge Rate for Sizing Flow Based Manufactured Proprietary Stormwater Treatment Practices, the Q rate associated with the 1-inch water quality volume is calculated using the following equation:

$$Q1 = (qu)(A)(WQV)$$

Where:

Q1 = flow rate associated with first 1-inch of runoff

qu = the unit peak discharge, in csm/in. [per Figure 4 on page 7 in MassDEP Q Rate, Sept. 10, 2013]

A = impervious surface drainage area (in square miles)

WQV = water quality volume in watershed inches (1-inch in this case)

### ***TSS Removal for P.UIS-1***

Tc = 0.1 hr

qu = 774 csm/in

A = 9,485 SF

$$Q1 = (774 \text{ csm/in})(9,485 \text{ SF} / 27,878,400 \text{ SF/mi}^2)(1.0 \text{ in})$$

Q1 = 0.26 CFS (2 MC-3500 isolator row chambers req.) – 9 Provided therefore 80% treatment is provided

Pretreatment

Deep Sump Hooded Catch Basin..... 25% (1 - [0.25 x 1.00] = 0.75 remaining)

Contech CDS1515-3..... 89.4% (0.75 – [0.894 x .75] = 0.0795 remaining)

Total Pretreatment = 92.05% > 44%

Treatment

Isolator Row & Stormtech MC-3500..... 80% (0.0795 - [0.80 x 0.0795] = 0.0159 remaining)  
**Total Suspended Solids Removal** **98.4%** ([1.00 - 0.0159] x 100 = 98.4%)

**TSS Removal for P.UIS-2**

Tc = 0.1 hr

qu = 752 csm/in

A = 3,750 SF

Q1 = (754 csm/in)(3,750 SF / 27,878,400 SF/mi<sup>2</sup>)(0.5 in)

Q1 = .05 CFS (1 MC-3500 isolator row chambers req.) – 7 Provided therefore 80% treatment is provided

Pretreatment

Deep Sump Hooded Catch Basin ..... 25% (1 - [0.25 x 1.00] = 0.75 remaining)

Treatment

Isolator Row & Stormtech MC-3500..... 80% (0.75 - [0.80 x 0.75] = 0.15 remaining)

**Total Suspended Solids Removal** **85%** ([1.00 - 0.15] x 100 = 85%)

**TSS Removal for P.UIS-3**

Tc = 0.1 hr

qu = 774 csm/in

A = 17,350 SF

Q1 = (774 csm/in)(17,350SF / 27,878,400 SF/mi<sup>2</sup>)(1.0 in)

Q1 = 0.48 CFS (2 MC-3500 isolator row chamber req.)

Pretreatment

Deep Sump Hooded Catch Basin..... 25% (1 - [0.25 x 1.00] = 0.75 remaining)

Treatment

Isolator Row & Stormtech MC 3500..... 80% (0.75 - [0.80 x 0.75] = 0.15 remaining)

**Total Suspended Solids Removal** **85%** ([1.00 - 0.15] x 100 = 85%)

**TSS Removal for P.UIS-4**

Tc = 0.1 hr

qu = 774 csm/in

A = 3,250 SF

Q1 = (774 csm/in)(3,250SF / 27,878,400 SF/mi<sup>2</sup>)(1.0 in)

Q1 = 0.09 CFS (1 SC-310 isolator row chamber req.)

Pretreatment

Deep Sump Hooded Catch Basin..... 25% (1 - [0.25 x 1.00] = 0.75 remaining)

Contech CDS1515-3..... 95.7% (0.75 - [0.957 x .75] = 0.03225 remaining)

Total Pretreatment = 96.8% > 44%

Treatment

Isolator Row & Stormtech SC 310..... 80% (0.03225 - [0.80 x 0.03225] = 0.00645 remaining)

**Total Suspended Solids Removal** **99.4%** ([1.00 - 0.00645] x 100 = 99.4%)

## **Standard 5: Land Uses with Higher Potential Pollutant Loads**

The proposed project is not a Land Use with Higher Potential Pollutant Load (LUHPPL).

## **Standard 6: Critical Area**

The proposed project does not discharge to a Critical Area

## **Standard 7: Redevelopment**

The proposed project is not a redevelopment.

## **Standard 8: Construction Period Pollution Prevention and Erosion & Sedimentation Control**

Best management practices (BMP) for erosion and sedimentation control are staked, silt fences, compost wood fiber sock, hydro seeding, and phased development. Many stormwater BMP technologies (e.g., infiltration technologies) are not designed to handle the high concentrations of sediments typically found in construction runoff and must be protected from construction-related sediment loadings. Construction BMP's **must** be maintained. In developing the proposed project certain measures will be implemented to minimize impacts erosion and sedimentation could have on surrounding areas. This section addresses items that involve proper construction techniques, close surveillance of workmanship, and immediate response to emergency situations. The developer must be prepared to provide whatever reasonable measures are necessary to protect the environment during construction and to stabilize all disturbed areas as soon as construction ends. Construction period pollution prevention and erosion and sediment control shall meet the requirements for the 2022 EPA Construction General Permit for all projects requiring coverage under the CGP.

### **Pre-Construction**

1. The contractor shall have a stockpile of materials required to control erosion on-site to be used to supplement or repair erosion control devices. These materials shall include, but are not limited to compost wood fiber sock, silt fence, compost wood fiber sock and crushed stone.
2. The contractor is responsible for erosion control on site and shall utilize erosion control measures where needed, regardless of whether the measures are specified on the plan or in the order of conditions.

### **Preliminary Site Work**

1. Excavated materials should be stockpiled, separating the topsoil for future use on the site. Erosion control shall be utilized along the down slope side of the piles and side slopes shall not exceed 2:1.
2. If intense rainfall is anticipated, the installation of supplemental straw bale dikes, silt fences, or armored dikes shall be considered.
3. Unsuitable excavated material shall be removed from the site.
4. Construction entrance shall be installed.
5. Existing catch basins shall be protected with silt sacks.

### **Ongoing Site Work**

1. Erosion control measures shall be regularly inspected and replaced as needed.
2. Dewatering shall be done in a manner so as not to transmit silt, sand or particulate matter to the receiving water or existing drainage system.

### **Landscaping**

1. Landscaping shall occur as soon as possible to provide permanent stabilization of disturbed surfaces.
2. If the season or adverse weather conditions do not allow the establishment of vegetation, temporary mulching with straw, wood chips weighted with snow fence or branches, or other methods shall be provided.
3. A minimum of 4 inches of topsoil shall be placed and its surface smoothed to the specified grades.
4. The use of herbicides is strongly discouraged.
5. Hydro seeding is encouraged for steep slopes. Application rates on slopes greater than 3:1 shall have a minimum seeding rate of 5-lbs/1000 SF. A latex or fiber tackifier shall be used on these slopes at a minimum rate of 50 lbs. of tackifier per 500 gallons of water used.

## Standard 9: Operations and Maintenance Plan

The information provided herein is intended to provide the base information for operation and maintenance of the site in perpetuity subject to updates and revisions as required at a future date. As such all future property owners must be notified in writing of this plan and be provided with a copy of this plan, a complete set of the design drawings and/or a completed as-built plan showing all the drainage features as they were constructed, which are considered part of this document. Please see the attached Operations and Maintenance Log (Appendix IX).

Stormwater management system owner: Marsh Hill Management, LLC  
The party responsible for operation and maintenance: Marsh Hill Management, LLC

### **Preliminary Stormwater Operation and Maintenance Budget**

Quarterly Inspection and Maintenance x \$1,250 per visit = \$5,000 annually

#### **Illicit Discharge - Practices to Minimize Storm Water Contamination**

- All waste materials will be collected and stored in a securely lidded metal dumpster.
- All trash and debris from the site will be deposited in the dumpster. The dumpster will be emptied on a regular schedule prior to being over full.
- All personnel will be instructed regarding the correct procedure for waste disposal.
- Good housekeeping and spill control practices will be followed to minimize storm water contamination from petroleum products, paints, and cleaning products.
- All site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage.
- Spill kits will be provided with any activity that could provide contamination.
- All paint containers and curing compounds will be tightly sealed and stored when not required for use. Excess paint will not be discharged to the storm sewers, but will be properly disposed according to the manufacturer's instructions.
- All spills will be cleaned up immediately upon discovery. Spills large enough to reach the storm sewers will be reported to the Massachusetts Department of Environmental Protection Northeast Regional Office at 1-888-304-1133.

#### **Deep Sump Hooded Catch Basins**

Inspect deep sump catch basins four times per year including the end of the foliage and snow removal seasons. Sediments must also be removed four times per year or when the depth of deposits is greater than or equal to one half the depth of the sump. Vacuum trucks are to be used to remove trapped sediment and supernatant.

Although catch basin debris often contains concentrations of oil and hazardous materials such as petroleum hydrocarbons and metals, MassDEP classifies them as solid waste. Any contaminated materials must be evaluated in accordance with the Hazardous Waste Regulations, 310 CMR 30.00, and handled as hazardous waste. MassDEP regulations prohibit landfills from accepting materials that contain free draining liquids.

#### **Hydrodynamic separators**

Hydrodynamic separators will be inspected and cleaned in strict accordance with the manufacturer's recommendations and requirements.

#### **Infiltration Basins**

The infiltration basins shall be inspected in early May and the second half of October. Any accumulated silt, trash, or debris shall be removed from the infiltration basins. Outlet control structures should be cleaned as required for proper function. Note any settlement or erosion around drainage inlets, stabilize any eroded areas. The discharge ponds shall be inspected for stability, erosion, siltation and obstructions. Any obstructions including any woody vegetation in the flow path shall be removed. Rip-rap shall be replenished as needed. If silt reaches half way up the rip-rap, it shall be removed and the rocks replaced or replenished as needed.

### **Roof Drain Leaders**

Routine roof inspections shall be performed two times per year. The roof shall be kept clean and free of debris, and the roof drainage systems shall be kept clear. Gutters and downspouts shall be cleaned at least twice per year, or more frequently as necessary.

### **Grass Swale**

Inspect semi-annually the first year, and at least once a year thereafter. Inspect the grass for growth and the side slopes for signs of erosion and formation of rills and gullies. Plant an alternative grass species if the original grass cover is not successfully established. If grass growth is impaired by winter road salt or other deicer use, re-establish the grass in the spring. Trash/Debris Removal: Remove accumulated trash and debris prior to mowing. Sediment Removal: Check on a yearly basis and clean as needed. Use hand methods (i.e., a person with a shovel) when cleaning to minimize disturbance to vegetation and underlying soils.

### **Vegetated Areas Maintenance**

Although not a structural component of the drainage system, the maintenance of vegetated areas may affect the functioning of stormwater management practices. This includes the health/density of vegetative cover and activities such as the application and disposal of lawn and garden care products, disposal of leaves and yard trimmings.

### **Initial Post-Construction Inspection**

During the initial period of vegetation establishment pruning and weeding are required twice in first year by contractor or owner. Any dead vegetation/plantings found after the first year will be replaced. Proper mulching is mandatory and regular watering may be required initially to ensure proper establishment of new vegetation.

### **Long-Term Maintenance**

The planted areas shall be inspected on a semi-annual basis and any litter removed. Weeds and invasive plant species shall be removed by hand. Maintain planted areas adjacent to pavement to prevent soil washout. Immediately clean any soil deposits on pavement. Leaf litter and other detritus shall be removed twice per year. If needed to maintain aesthetic appearance, perennial plantings may be trimmed at the end of the growing season.

Trees and shrubs shall be inspected twice per year to evaluate health and attended to as necessary. Seeded ground cover or grass areas shall not receive mulching. Re-seed bare areas; install appropriate erosion control measures when native soil is exposed or erosion channels are forming. Plant alternative mixtures of grass species in the event of unsuccessful establishment. The grass vegetation should not be cut to a height less than four inches.

### **Pesticide/Herbicide Usage**

No pesticides are to be used unless a single spot treatment is required for a specific control application.

## 2041 Bridge Street, Dracut, MA – Post Construction Maintenance

### Operations and Maintenance Log

Inspections for Year: \_\_\_\_\_

Structural Best Management Practice (Frequency)	Action	Date Completed	Completed By	Comments
Deep Sump Hooded Catch Basin – Inspect/clean four times per year. Clean when sump is 50% full.	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
Stormtech Chambers – Inspect four times per year. Clean per manufacturer's requirements.	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
Roof Drain Leaders – Inspect/clean twice per year.	Inspect/Clean			
	Inspect/Clean			
Grass Swale – Inspect/clean twice per year for first year. Once annually thereafter.	Inspect/Clean			
	Inspect/Clean			
Vegetated Areas Maintenance – Inspect twice per year. Maintain as required.	Inspect			
	Inspect			

- (1) Refer to the Massachusetts Stormwater Management, Volume Two: Stormwater Technical Handbook (March 1997) for recommendations regarding frequency for inspection and maintenance of specific BMP's.
- (2) Inspections to be conducted by qualified professional such as an environmental scientist or civil engineer.

Limited or no use of sodium chloride salts, fertilizers or pesticides recommended.

Other notes: (Included deviations from: Con Comm. Order of Conditions, PB Approval, Construction Sequence and Approved Plan).

Stormwater Control Manager: \_\_\_\_\_

## **Standard 10: Prohibition of Illicit Discharges**

No illicit discharges currently exist and no future illicit discharges will be allowed including wastewater discharges and discharges of stormwater contaminated by contact with process wastes, raw materials, toxic pollutants, hazardous substances, soil, or grease.

## Appendix I Locus Map



Produced by the United States Geological Survey

North American Datum of 1983 (NAD83)

World Geodetic System 1984 (WGS84) Projection and

1:000-meter grid-Universal Transverse Mercator, Zone 19T

This map is not a legal document. Boundaries may be

periodically revised. Scale: Primary scale is government

reservations may not be shown. Obtain permission before

entering private land.

Imagery: NAP, October 2018 - October 2018

Roads: U.S. Census Bureau, 2018

Names: U.S. Census Bureau, 2014 - 2016

Hydrography: National Hydrography Dataset, 2004 - 2023

Contours: National Elevation Dataset, 2004 - 2023

Boundaries: Multiple sources; see metadata file 2020 - 2022

Wetlands: FWS National Wetlands Inventory 1985 - 2013

SCALE 1:24 000

 1 0.5 0 1 2  
KILOMETERS  
1000 500 0 1000 2000  
METERS  
1000 500 0 1000 2000  
MILES  
1000 500 0 1000 2000  
FEET


ROAD CLASSIFICATION

 Expressway  
Secondary Hwy  
Ramp  
Interstate Route  
Local Connector  
Local Road  
4WD  
US Route  
State Route

 UTM GRID AND 2023 MAGNETIC NORTH DECLINATION AT CENTER OF SHEET  
14°45' GN  
212 MILES  
31 MILES  
21 MILES  
NORTH AMERICAN VERTICAL DATUM OF 1988  
This map was produced to conform with the  
National Geospatial Program US Topo Product Standard.  
U.S. National Grid  
1000' x 1000' - 1:24,000 Scale  
Grid Zone Designation 12T  
CH

 CONTOUR INTERVAL: 10 FEET  
NORTH AMERICAN VERTICAL DATUM OF 1988

This map was produced to conform with the

National Geospatial Program US Topo Product Standard.

1	2	3	4	5	6	7	8
1	Nashua North	Windham	4	Nashua South	5	Lawrence	7

8 Wilmington

LOWELL, MA, NH

2024




## Appendix II Stormwater Checklist



# Checklist for Stormwater Report

## A. Introduction

**Important:** When filling out forms on the computer, use only the tab key to move your cursor - do not use the return key.



A Stormwater Report must be submitted with the Notice of Intent permit application to document compliance with the Stormwater Management Standards. The following checklist is NOT a substitute for the Stormwater Report (which should provide more substantive and detailed information) but is offered here as a tool to help the applicant organize their Stormwater Management documentation for their Report and for the reviewer to assess this information in a consistent format. As noted in the Checklist, the Stormwater Report must contain the engineering computations and supporting information set forth in Volume 3 of the [Massachusetts Stormwater Handbook](#). The Stormwater Report must be prepared and certified by a Registered Professional Engineer (RPE) licensed in the Commonwealth.

The Stormwater Report must include:

- The Stormwater Checklist completed and stamped by a Registered Professional Engineer (see page 2) that certifies that the Stormwater Report contains all required submittals.<sup>1</sup> This Checklist is to be used as the cover for the completed Stormwater Report.
- Applicant/Project Name
- Project Address
- Name of Firm and Registered Professional Engineer that prepared the Report
- Long-Term Pollution Prevention Plan required by Standards 4-6
- Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan required by Standard 8<sup>2</sup>
- Operation and Maintenance Plan required by Standard 9

In addition to all plans and supporting information, the Stormwater Report must include a brief narrative describing stormwater management practices, including environmentally sensitive site design and LID techniques, along with a diagram depicting runoff through the proposed BMP treatment train. Plans are required to show existing and proposed conditions, identify all wetland resource areas, NRCS soil types, critical areas, Land Uses with Higher Potential Pollutant Loads (LUHPPL), and any areas on the site where infiltration rate is greater than 2.4 inches per hour. The Plans shall identify the drainage areas for both existing and proposed conditions at a scale that enables verification of supporting calculations.

As noted in the Checklist, the Stormwater Management Report shall document compliance with each of the Stormwater Management Standards as provided in the Massachusetts Stormwater Handbook. The soils evaluation and calculations shall be done using the methodologies set forth in Volume 3 of the Massachusetts Stormwater Handbook.

To ensure that the Stormwater Report is complete, applicants are required to fill in the Stormwater Report Checklist by checking the box to indicate that the specified information has been included in the Stormwater Report. If any of the information specified in the checklist has not been submitted, the applicant must provide an explanation. The completed Stormwater Report Checklist and Certification must be submitted with the Stormwater Report.

<sup>1</sup> The Stormwater Report may also include the Illicit Discharge Compliance Statement required by Standard 10. If not included in the Stormwater Report, the Illicit Discharge Compliance Statement must be submitted prior to the discharge of stormwater runoff to the post-construction best management practices.

<sup>2</sup> For some complex projects, it may not be possible to include the Construction Period Erosion and Sedimentation Control Plan in the Stormwater Report. In that event, the issuing authority has the discretion to issue an Order of Conditions that approves the project and includes a condition requiring the proponent to submit the Construction Period Erosion and Sedimentation Control Plan before commencing any land disturbance activity on the site.



# Checklist for Stormwater Report

---

## B. Stormwater Checklist and Certification

The following checklist is intended to serve as a guide for applicants as to the elements that ordinarily need to be addressed in a complete Stormwater Report. The checklist is also intended to provide conservation commissions and other reviewing authorities with a summary of the components necessary for a comprehensive Stormwater Report that addresses the ten Stormwater Standards.

*Note:* Because stormwater requirements vary from project to project, it is possible that a complete Stormwater Report may not include information on some of the subjects specified in the Checklist. If it is determined that a specific item does not apply to the project under review, please note that the item is not applicable (N.A.) and provide the reasons for that determination.

A complete checklist must include the Certification set forth below signed by the Registered Professional Engineer who prepared the Stormwater Report.

---

### Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined that the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.

Registered Professional Engineer Block and Signature

\_\_\_\_\_  
Signature and Date

---

### Checklist

**Project Type:** Is the application for new development, redevelopment, or a mix of new and redevelopment?

- New development
- Redevelopment
- Mix of New Development and Redevelopment



# Checklist for Stormwater Report

---

## Checklist (continued)

**LID Measures:** Stormwater Standards require LID measures to be considered. Document what environmentally sensitive design and LID Techniques were considered during the planning and design of the project:

- No disturbance to any Wetland Resource Areas
- Site Design Practices (e.g. clustered development, reduced frontage setbacks)
- Reduced Impervious Area (Redevelopment Only)
- Minimizing disturbance to existing trees and shrubs
- LID Site Design Credit Requested:
  - Credit 1
  - Credit 2
  - Credit 3
- Use of "country drainage" versus curb and gutter conveyance and pipe
- Bioretention Cells (includes Rain Gardens)
- Constructed Stormwater Wetlands (includes Gravel Wetlands designs)
- Treebox Filter
- Water Quality Swale
- Grass Channel
- Green Roof
- Other (describe): underground infiltration system

---

## Standard 1: No New Untreated Discharges

- No new untreated discharges
- Outlets have been designed so there is no erosion or scour to wetlands and waters of the Commonwealth
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 2: Peak Rate Attenuation

- Standard 2 waiver requested because the project is located in land subject to coastal storm flowage and stormwater discharge is to a wetland subject to coastal flooding.
- Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm.
- Calculations provided to show that post-development peak discharge rates do not exceed pre-development rates for the 2-year and 10-year 24-hour storms. If evaluation shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm.

### Standard 3: Recharge

- Soil Analysis provided.
- Required Recharge Volume calculation provided.
- Required Recharge volume reduced through use of the LID site Design Credits.
- Sizing the infiltration, BMPs is based on the following method: Check the method used.
  - Static
  - Simple Dynamic
  - Dynamic Field<sup>1</sup>
- Runoff from all impervious areas at the site discharging to the infiltration BMP.
- Runoff from all impervious areas at the site is *not* discharging to the infiltration BMP and calculations are provided showing that the drainage area contributing runoff to the infiltration BMPs is sufficient to generate the required recharge volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume.
- Recharge BMPs have been sized to infiltrate the Required Recharge Volume *only* to the maximum extent practicable for the following reason:
  - Site is comprised solely of C and D soils and/or bedrock at the land surface
  - M.G.L. c. 21E sites pursuant to 310 CMR 40.0000
  - Solid Waste Landfill pursuant to 310 CMR 19.000
  - Project is otherwise subject to Stormwater Management Standards only to the maximum extent practicable.
- Calculations showing that the infiltration BMPs will drain in 72 hours are provided.
- Property includes a M.G.L. c. 21E site or a solid waste landfill and a mounding analysis is included.

---

<sup>1</sup> 80% TSS removal is required prior to discharge to infiltration BMP if Dynamic Field method is used.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 3: Recharge (continued)

- The infiltration BMP is used to attenuate peak flows during storms greater than or equal to the 10-year 24-hour storm and separation to seasonal high groundwater is less than 4 feet and a mounding analysis is provided.
- Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas.

### Standard 4: Water Quality

The Long-Term Pollution Prevention Plan typically includes the following:

- Good housekeeping practices;
- Provisions for storing materials and waste products inside or under cover;
- Vehicle washing controls;
- Requirements for routine inspections and maintenance of stormwater BMPs;
- Spill prevention and response plans;
- Provisions for maintenance of lawns, gardens, and other landscaped areas;
- Requirements for storage and use of fertilizers, herbicides, and pesticides;
- Pet waste management provisions;
- Provisions for operation and management of septic systems;
- Provisions for solid waste management;
- Snow disposal and plowing plans relative to Wetland Resource Areas;
- Winter Road Salt and/or Sand Use and Storage restrictions;
- Street sweeping schedules;
- Provisions for prevention of illicit discharges to the stormwater management system;
- Documentation that Stormwater BMPs are designed to provide for shutdown and containment in the event of a spill or discharges to or near critical areas or from LUHPPL;
- Training for staff or personnel involved with implementing Long-Term Pollution Prevention Plan;
- List of Emergency contacts for implementing Long-Term Pollution Prevention Plan.

- A Long-Term Pollution Prevention Plan is attached to Stormwater Report and is included as an attachment to the Wetlands Notice of Intent.
- Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge:
  - is within the Zone II or Interim Wellhead Protection Area
  - is near or to other critical areas
  - is within soils with a rapid infiltration rate (greater than 2.4 inches per hour)
  - involves runoff from land uses with higher potential pollutant loads.
- The Required Water Quality Volume is reduced through use of the LID site Design Credits.
- Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 4: Water Quality (continued)

- The BMP is sized (and calculations provided) based on:
  - The ½" or 1" Water Quality Volume or
  - The equivalent flow rate associated with the Water Quality Volume and documentation is provided showing that the BMP treats the required water quality volume.
- The applicant proposes to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. This documentation may be in the form of the proprietary BMP checklist found in Volume 2, Chapter 4 of the Massachusetts Stormwater Handbook and submitting copies of the TARP Report, STEP Report, and/or other third party studies verifying performance of the proprietary BMPs.
- A TMDL exists that indicates a need to reduce pollutants other than TSS and documentation showing that the BMPs selected are consistent with the TMDL is provided.

### Standard 5: Land Uses With Higher Potential Pollutant Loads (LUHPPLs)

- The NPDES Multi-Sector General Permit covers the land use and the Stormwater Pollution Prevention Plan (SWPPP) has been included with the Stormwater Report.
- The NPDES Multi-Sector General Permit covers the land use and the SWPPP will be submitted **prior to** the discharge of stormwater to the post-construction stormwater BMPs.
- The NPDES Multi-Sector General Permit does **not** cover the land use.
- LUHPPLs are located at the site and industry specific source control and pollution prevention measures have been proposed to reduce or eliminate the exposure of LUHPPLs to rain, snow, snow melt and runoff, and been included in the long term Pollution Prevention Plan.
- All exposure has been eliminated.
- All exposure has **not** been eliminated and all BMPs selected are on MassDEP LUHPPL list.
- The LUHPPL has the potential to generate runoff with moderate to higher concentrations of oil and grease (e.g. all parking lots with >1000 vehicle trips per day) and the treatment train includes an oil grit separator, a filtering bioretention area, a sand filter or equivalent.

### Standard 6: Critical Areas

- The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area.
- Critical areas and BMPs are identified in the Stormwater Report.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 7: Redevelopments and Other Projects Subject to the Standards only to the maximum extent practicable

The project is subject to the Stormwater Management Standards only to the maximum Extent Practicable as a:

- Limited Project
- Small Residential Projects: 5-9 single family houses or 5-9 units in a multi-family development provided there is no discharge that may potentially affect a critical area.
- Small Residential Projects: 2-4 single family houses or 2-4 units in a multi-family development with a discharge to a critical area
- Marina and/or boatyard provided the hull painting, service and maintenance areas are protected from exposure to rain, snow, snow melt and runoff
- Bike Path and/or Foot Path
- Redevelopment Project
- Redevelopment portion of mix of new and redevelopment.

Certain standards are not fully met (Standard No. 1, 8, 9, and 10 must always be fully met) and an explanation of why these standards are not met is contained in the Stormwater Report.

The project involves redevelopment and a description of all measures that have been taken to improve existing conditions is provided in the Stormwater Report. The redevelopment checklist found in Volume 2 Chapter 3 of the Massachusetts Stormwater Handbook may be used to document that the proposed stormwater management system (a) complies with Standards 2, 3 and the pretreatment and structural BMP requirements of Standards 4-6 to the maximum extent practicable and (b) improves existing conditions.

### Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan must include the following information:

- Narrative;
- Construction Period Operation and Maintenance Plan;
- Names of Persons or Entity Responsible for Plan Compliance;
- Construction Period Pollution Prevention Measures;
- Erosion and Sedimentation Control Plan Drawings;
- Detail drawings and specifications for erosion control BMPs, including sizing calculations;
- Vegetation Planning;
- Site Development Plan;
- Construction Sequencing Plan;
- Sequencing of Erosion and Sedimentation Controls;
- Operation and Maintenance of Erosion and Sedimentation Controls;
- Inspection Schedule;
- Maintenance Schedule;
- Inspection and Maintenance Log Form.

A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report.



# Checklist for Stormwater Report

---

## Checklist (continued)

### Standard 8: Construction Period Pollution Prevention and Erosion and Sedimentation Control (continued)

- The project is highly complex and information is included in the Stormwater Report that explains why it is not possible to submit the Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan with the application. A Construction Period Pollution Prevention and Erosion and Sedimentation Control has **not** been included in the Stormwater Report but will be submitted **before** land disturbance begins.
- The project is **not** covered by a NPDES Construction General Permit.
- The project is covered by a NPDES Construction General Permit and a copy of the SWPPP is in the Stormwater Report.
- The project is covered by a NPDES Construction General Permit but no SWPPP been submitted. The SWPPP will be submitted BEFORE land disturbance begins.

### Standard 9: Operation and Maintenance Plan

- The Post Construction Operation and Maintenance Plan is included in the Stormwater Report and includes the following information:
  - Name of the stormwater management system owners;
  - Party responsible for operation and maintenance;
  - Schedule for implementation of routine and non-routine maintenance tasks;
  - Plan showing the location of all stormwater BMPs maintenance access areas;
  - Description and delineation of public safety features;
  - Estimated operation and maintenance budget; and
  - Operation and Maintenance Log Form.
- The responsible party is **not** the owner of the parcel where the BMP is located and the Stormwater Report includes the following submissions:
  - A copy of the legal instrument (deed, homeowner's association, utility trust or other legal entity) that establishes the terms of and legal responsibility for the operation and maintenance of the project site stormwater BMPs;
  - A plan and easement deed that allows site access for the legal entity to operate and maintain BMP functions.

### Standard 10: Prohibition of Illicit Discharges

- The Long-Term Pollution Prevention Plan includes measures to prevent illicit discharges;
- An Illicit Discharge Compliance Statement is attached;
- NO Illicit Discharge Compliance Statement is attached but will be submitted **prior to** the discharge of any stormwater to post-construction BMPs.

## **Appendix III Stormwater Best Management Practice Plan**

# COMPREHENSIVE PERMIT SITE PLAN

**PROPERTY ADDRESS:**  
**2041 BRIDGE STREET**  
Dracut, Massachusetts 01826

PREPARED FOR:

# Marsh Hill Management, LLC

39 Myrtle Street  
Lowell, Massachusetts 01854

# HANCOCK ASSOCIATES

## Civil Engineers

## Land Surveyors

# Environmental Consultants

34 CHELMSFORD STREET, CHELMSFORD, MA 01824  
VOICE (978) 244-0110, FAX (978) 244-1133  
[WWW.HANCOCKASSOCIATES.COM](http://WWW.HANCOCKASSOCIATES.COM)

MAP 19, LOT 39  
MARSH HILL MANAGEMENT, LLC  
 $225,284 \pm 5.17 \pm \text{ACRES}$

DEED BOOK 31555, PAGE 86  
PLAN BOOK 218, PLAN 49

DEED BOOK 31288, PAGE 159  
PLAN BOOK 218, PLAN 49

DEED BOOK 31443, PAGE 76  
PLAN BOOK 218, PLAN 49

DEED BOOK 32032, PAGE 234  
PLAN BOOK 218, PLAN 49

DEED BOOK 20828, PAGE 29  
PLAN BOOK 118, PLAN 57

PROPOSED MULTI-FAMILY BUILDING (40-UNITS)  
3-STORIES AND GARAGE PARKING  
GAR. ELEV. = 152.0  
FF ELEV. = 166.0

LOBBY ELEV.=152.00

STOR. ELEV. ROOM MECH. ROOM STAIRS PATIO

IP (FD) IN STONEWALL

MASS STATE PLANE COORD. SYSTEM (NAD83)

MARSH HILL ROAD (PUBLIC - VARIABLE WIDTH)

SCALE: 1" = 30'

ACCESS EASEMENT (SEE DETAIL A)  
(SEE 32648-42)

12" PVC SEWER

18" CONC. INV.=133.04 RIM=138.35 SGC

12" RCP CB7

12" RCP CB8

12" RCP CB9

12" RCP CB10

12" RCP CB11

12" RCP CB12

12" RCP CB13

12" RCP CB14

12" RCP CB15

12" RCP CB16

12" RCP CB17

12" RCP CB18

12" RCP CB19

12" RCP CB20

12" RCP CB21

12" RCP CB22

12" RCP CB23

12" RCP CB24

12" RCP CB25

12" RCP CB26

12" RCP CB27

12" RCP CB28

12" RCP CB29

12" RCP CB30

12" RCP CB31

12" RCP CB32

12" RCP CB33

12" RCP CB34

12" RCP CB35

12" RCP CB36

12" RCP CB37

12" RCP CB38

12" RCP CB39

12" RCP CB40

12" RCP CB41

12" RCP CB42

12" RCP CB43

12" RCP CB44

12" RCP CB45

12" RCP CB46

12" RCP CB47

12" RCP CB48

12" RCP CB49

12" RCP CB50

12" RCP CB51

12" RCP CB52

12" RCP CB53

12" RCP CB54

12" RCP CB55

12" RCP CB56

12" RCP CB57

12" RCP CB58

12" RCP CB59

12" RCP CB60

12" RCP CB61

12" RCP CB62

12" RCP CB63

12" RCP CB64

12" RCP CB65

12" RCP CB66

12" RCP CB67

12" RCP CB68

12" RCP CB69

12" RCP CB70

12" RCP CB71

12" RCP CB72

12" RCP CB73

12" RCP CB74

12" RCP CB75

12" RCP CB76

12" RCP CB77

12" RCP CB78

12" RCP CB79

12" RCP CB80

12" RCP CB81

12" RCP CB82

12" RCP CB83

12" RCP CB84

12" RCP CB85

12" RCP CB86

12" RCP CB87

12" RCP CB88

12" RCP CB89

12" RCP CB90

12" RCP CB91

12" RCP CB92

12" RCP CB93

12" RCP CB94

12" RCP CB95

12" RCP CB96

12" RCP CB97

12" RCP CB98

12" RCP CB99

12" RCP CB100

12" RCP CB101

12" RCP CB102

12" RCP CB103

12" RCP CB104

12" RCP CB105

12" RCP CB106

12" RCP CB107

12" RCP CB108

12" RCP CB109

12" RCP CB110

12" RCP CB111

12" RCP CB112

12" RCP CB113

12" RCP CB114

12" RCP CB115

12" RCP CB116

12" RCP CB117

12" RCP CB118

12" RCP CB119

12" RCP CB120

12" RCP CB121

12" RCP CB122

12" RCP CB123

12" RCP CB124

12" RCP CB125

12" RCP CB126

12" RCP CB127

12" RCP CB128

12" RCP CB129

12" RCP CB130

12" RCP CB131

12" RCP CB132

12" RCP CB133

12" RCP CB134

12" RCP CB135

12" RCP CB136

12" RCP CB137

12" RCP CB138

12" RCP CB139

12" RCP CB140

12" RCP CB141

12" RCP CB142

12" RCP CB143

12" RCP CB144

12" RCP CB145

12" RCP CB146

12" RCP CB147

12" RCP CB148

12" RCP CB149

12" RCP CB150

12" RCP CB151

12" RCP CB152

12" RCP CB153

12" RCP CB154

12" RCP CB155

12" RCP CB156

12" RCP CB157

12" RCP CB158

12" RCP CB159

12" RCP CB160

12" RCP CB161

12" RCP CB162

12" RCP CB163

12" RCP CB164

12" RCP CB165

12" RCP CB166

12" RCP CB167

12" RCP CB168

12" RCP CB169

12" RCP CB170

12" RCP CB171

12" RCP CB172

12" RCP CB173

12" RCP CB174

12" RCP CB175

12" RCP CB176

12" RCP CB177

12" RCP CB178

12" RCP CB179

12" RCP CB180

12" RCP CB181

12" RCP CB182

12" RCP CB183

12" RCP CB184

12" RCP CB185

12" RCP CB186

12" RCP CB187

12" RCP CB188

12" RCP CB189

12" RCP CB190

12" RCP CB191

12" RCP CB192

12" RCP CB193

12" RCP CB194

12" RCP CB195

12" RCP CB196

12" RCP CB197

12" RCP CB198

12" RCP CB199

12" RCP CB200

12" RCP CB201

12" RCP CB202

12" RCP CB203

12" RCP CB204

12" RCP CB205

12" RCP CB206

12" RCP CB207

12" RCP CB208

12" RCP CB209

12" RCP CB210

12" RCP CB211

12" RCP CB212

12" RCP CB213

12" RCP CB214

12" RCP CB215

12" RCP CB216

12" RCP CB217

12" RCP CB218

12" RCP CB219

12" RCP CB220

12" RCP CB221

12" RCP CB222

12" RCP CB223

12" RCP CB224

12" RCP CB225

12" RCP CB226

12" RCP CB227

12" RCP CB228

12" RCP CB229

12" RCP CB230

12" RCP CB231

12" RCP CB232

12" RCP CB233

12" RCP CB234

12" RCP CB235

12" RCP CB236

12" RCP CB237

12" RCP CB238

12" RCP CB239

12" RCP CB240

12" RCP CB241

12" RCP CB242

12" RCP CB243

12" RCP CB244

12" RCP CB245

12" RCP CB246

12" RCP CB247

12" RCP CB248

12" RCP CB249

12" RCP CB250

12" RCP CB251

12" RCP CB252

12" RCP CB253

12" RCP CB254

12" RCP CB255

12" RCP CB256

12" RCP CB257

12" RCP CB258

12" RCP CB259

12" RCP CB260

12" RCP CB261

12" RCP CB262

12" RCP CB263

12" RCP CB264

12" RCP CB265

12" RCP CB266

12" RCP CB267

12" RCP CB268

12" RCP CB269

12" RCP CB270

12" RCP CB271

12" RCP CB272

12" RCP CB273

12" RCP CB274

12" RCP CB275

12" RCP CB276

12" RCP CB277

12" RCP CB278

12" RCP CB279

12" RCP CB280

12" RCP CB281

12" RCP CB282

12" RCP CB283

12" RCP CB284

12" RCP CB285

12" RCP CB286

12" RCP CB287

12" RCP CB288

12" RCP CB289

12" RCP CB290

12" RCP CB291

12" RCP CB292

12" RCP CB293

12" RCP CB294

12" RCP CB295

12" RCP CB296

12" RCP CB297

12" RCP CB298

12" RCP CB299

12" RCP CB300

12" RCP CB301

12" RCP CB302

12" RCP CB303

12" RCP CB304

12" RCP CB305

12" RCP CB306

12" RCP CB307

12" RCP CB308

12" RCP CB309

12" RCP CB310

12" RCP CB311

12" RCP CB312

12" RCP CB313

12" RCP CB314

12" RCP CB315

12" RCP CB316

12" RCP CB317

12" RCP CB318

12" RCP CB319

12" RCP CB320

12" RCP CB321

12" RCP CB322

12" RCP CB323

12" RCP CB324

12" RCP CB325

12" RCP CB326

12" RCP CB327

12" RCP CB328

12" RCP CB329

12" RCP CB330

12" RCP CB331

12" RCP CB332

12" RCP CB333

12" RCP CB334

12" RCP CB335

12" RCP CB336

12" RCP CB337

12" RCP CB338

12" RCP CB339

12" RCP CB340

12" RCP CB341

12" RCP CB342

12" RCP CB343

12" RCP CB344

12" RCP CB345

12" RCP CB346

12" RCP CB347

12" RCP CB348

12" RCP CB349

12" RCP CB350

12" RCP CB351

12" RCP CB352

12" RCP CB353

12" RCP CB354

12" RCP CB355

12" RCP CB356

12" RCP CB357

12" RCP CB358

12" RCP CB359

12" RCP CB360

12" RCP CB361

12" RCP CB362

12" RCP CB363

12" RCP CB364

12" RCP CB365

12" RCP CB366

12" RCP CB367

12" RCP CB368

12" RCP CB369

12" RCP CB370

12" RCP CB371

12" RCP CB372

12" RCP CB373

12" RCP CB374

12" RCP CB375

12" RCP CB376

12" RCP CB377

12" RCP CB378

12" RCP CB379

12" RCP CB380

12" RCP CB381

12" RCP CB382

12" RCP CB383

12" RCP CB384

12" RCP CB385

12" RCP CB386

12" RCP CB387

12" RCP CB388

12" RCP CB389

12" RCP CB390

12" RCP CB391

12" RCP CB392

12" RCP CB393

12" RCP CB394

12" RCP CB395

12" RCP CB396

12" RCP CB397

12" RCP CB398

12" RCP CB399

12" RCP CB400

12" RCP CB401

12" RCP CB402

12" RCP CB403

12" RCP CB404

12" RCP CB405

12" RCP CB406

12" RCP CB407

12" RCP CB408

12" RCP CB409

12" RCP CB410

12" RCP CB411

12" RCP CB412

12" RCP CB413

12" RCP CB414

12" RCP CB415

12" RCP CB416

12" RCP CB417

12" RCP CB418

12" RCP CB419

12" RCP CB420

12" RCP CB421

12" RCP CB422

12" RCP CB423

12" RCP CB424

12" RCP CB425

12" RCP CB426

12" RCP CB427

12" RCP CB428

12" RCP CB429

12" RCP CB430

12" RCP CB431

12" RCP CB432

12" RCP CB433

12" RCP CB434

12" RCP CB435

12" RCP CB436

12" RCP CB437

12" RCP CB438

12" RCP CB439

12" RCP CB440

12" RCP CB441

12" RCP CB442

12" RCP CB443

12" RCP CB444

12" RCP CB445

12" RCP CB446

12" RCP CB447

12" RCP CB448

12" RCP CB449

12" RCP CB450

12" RCP CB451

12" RCP CB452

12" RCP CB453

12" RCP CB454

12" RCP CB455

12" RCP CB456

12" RCP CB457

12" RCP CB458

12" RCP CB459

12" RCP CB460

12" RCP CB461

12" RCP CB462

12" RCP CB463

12" RCP CB464

12" RCP CB465

12" RCP CB466

12" RCP CB467

12" RCP CB468

12" RCP CB469

12" RCP CB470

12" RCP CB471

12" RCP CB472

12" RCP CB473

12" RCP CB474

12" RCP CB475

12" RCP CB476

12" RCP CB477

12" RCP CB478

12" RCP CB479

12" RCP CB480

12" RCP CB481

12" RCP CB482

12" RCP CB483

12" RCP CB484

12" RCP CB485

12" RCP CB486

12" RCP CB487

12" RCP CB488

12" RCP CB489

12" RCP CB490

12" RCP CB491

12" RCP CB492

12" RCP CB493

12" RCP CB494

12" RCP CB495

12" RCP CB496

12" RCP CB497

12" RCP CB498

12" RCP CB499

12" RCP CB500

12" RCP CB501

12" RCP CB502

12" RCP CB503

12" RCP CB504

12" RCP CB505

12" RCP CB506

12" RCP CB507

12" RCP CB508

12" RCP CB509

12" RCP CB510

12" RCP CB511

12" RCP CB512

12" RCP CB513

12" RCP CB514

12" RCP CB515

12" RCP CB516

12" RCP CB517

12" RCP CB518

12" RCP CB519

12" RCP CB520

12" RCP CB521

12" RCP CB522

12" RCP CB523

12" RCP CB524

12" RCP CB525

12" RCP CB526

12" RCP CB527

12" RCP CB528

12" RCP CB529

12" RCP CB530

12" RCP CB531

12" RCP CB532

12" RCP CB533

12" RCP CB53

DATE	ISSUE/REVISION DESCRIPTION
10/14/25	DESIGN BY: RCT/MJS
AS SHOWN	DRAWN BY: RCT/MJS
Y: BGG	CHECK BY: JJP


# **STORMWATER BEST MANAGEMENT PRACTICES PLAN**

-SP1.dwg  
MP  
OF 1  
27164

# BMP

## Appendix IV NRCS Soils Map

## Soil Map—Middlesex County, Massachusetts (2041 Bridge Street, Dracut, MA)



Soil Map may not be valid at this scale.

Map Scale: 1:5,310 if printed on A portrait (8.5" x 11") sheet.

0 50 100 200 300 Meters

0 250 500 1000 1500  
Map projection: Web Mercator. Corner coordinates: WGS84. Edge ticks: UTM Zone 19N WGS84




## Natural Resources Conservation Service

Web Soil Survey  
National Cooperative Soil Survey

8/15/2023  
Page 1 of 3

## MAP LEGEND

### Area of Interest (AOI)



Area of Interest (AOI)

### Soils



Soil Map Unit Polygons



Soil Map Unit Lines



Soil Map Unit Points

### Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot

Spoil Area

Stony Spot

Very Stony Spot

Wet Spot

Other

Special Line Features

### Water Features

Streams and Canals

### Transportation

Rails

Interstate Highways

US Routes

Major Roads

Local Roads

### Background

Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:25,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Middlesex County, Massachusetts

Survey Area Data: Version 22, Sep 9, 2022

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 22, 2022—Jun 5, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.



## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
1	Water	1.4	1.1%
6A	Scarboro mucky fine sandy loam, 0 to 3 percent slopes	1.3	1.0%
51A	Swansea muck, 0 to 1 percent slopes	14.0	11.1%
53A	Freetown muck, ponded, 0 to 1 percent slopes	13.8	10.9%
71B	Ridgebury fine sandy loam, 3 to 8 percent slopes, extremely stony	15.2	12.0%
73B	Whitman fine sandy loam, 0 to 3 percent slopes, extremely stony	0.4	0.3%
103B	Charlton-Hollis-Rock outcrop complex, 3 to 8 percent slopes	5.5	4.4%
103C	Charlton-Hollis-Rock outcrop complex, 8 to 15 percent slopes	1.4	1.1%
104C	Hollis-Rock outcrop-Charlton complex, 0 to 15 percent slopes	4.1	3.2%
256A	Deerfield loamy fine sand, 0 to 3 percent slopes	2.2	1.7%
300B	Montauk fine sandy loam, 3 to 8 percent slopes	11.7	9.2%
300C	Montauk fine sandy loam, 8 to 15 percent slopes	12.2	9.6%
310B	Woodbridge fine sandy loam, 3 to 8 percent slopes	2.7	2.1%
311C	Woodbridge fine sandy loam, 8 to 15 percent slopes, very stony	11.4	9.0%
315B	Scituate fine sandy loam, 3 to 8 percent slopes	13.7	10.8%
420B	Canton fine sandy loam, 3 to 8 percent slopes	15.3	12.1%
601	Pits, quarry	0.2	0.2%
<b>Totals for Area of Interest</b>		<b>126.5</b>	<b>100.0%</b>

## Middlesex County, Massachusetts

### 51A—Swansea muck, 0 to 1 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2trl2  
*Elevation:* 0 to 1,140 feet  
*Mean annual precipitation:* 36 to 71 inches  
*Mean annual air temperature:* 39 to 55 degrees F  
*Frost-free period:* 140 to 240 days  
*Farmland classification:* Not prime farmland

#### Map Unit Composition

*Swansea and similar soils:* 80 percent  
*Minor components:* 20 percent  
*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Swansea

##### Setting

*Landform:* Bogs, swamps  
*Landform position (three-dimensional):* Dip  
*Down-slope shape:* Concave  
*Across-slope shape:* Concave  
*Parent material:* Highly decomposed organic material over loose sandy and gravelly glaciofluvial deposits

##### Typical profile

*Oa1 - 0 to 24 inches:* muck  
*Oa2 - 24 to 34 inches:* muck  
*Cg - 34 to 79 inches:* coarse sand

##### Properties and qualities

*Slope:* 0 to 1 percent  
*Depth to restrictive feature:* More than 80 inches  
*Drainage class:* Very poorly drained  
*Runoff class:* Negligible  
*Capacity of the most limiting layer to transmit water (Ksat):* Moderately low to high (0.14 to 14.17 in/hr)  
*Depth to water table:* About 0 to 6 inches  
*Frequency of flooding:* Rare  
*Frequency of ponding:* Frequent  
*Available water supply, 0 to 60 inches:* Very high (about 16.5 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified  
*Land capability classification (nonirrigated):* 8w  
*Hydrologic Soil Group:* B/D  
*Ecological site:* F144AY043MA - Acidic Organic Wetlands  
*Hydric soil rating:* Yes

## Minor Components

### Freetown

*Percent of map unit:* 10 percent

*Landform:* Bogs, swamps

*Landform position (three-dimensional):* Dip

*Down-slope shape:* Concave

*Across-slope shape:* Concave

*Hydric soil rating:* Yes

### Scarboro

*Percent of map unit:* 5 percent

*Landform:* Drainageways, depressions

*Landform position (two-dimensional):* Toeslope

*Landform position (three-dimensional):* Base slope, tread, dip

*Down-slope shape:* Concave

*Across-slope shape:* Concave

*Hydric soil rating:* Yes

### Whitman

*Percent of map unit:* 5 percent

*Landform:* Drainageways, depressions

*Landform position (two-dimensional):* Toeslope

*Landform position (three-dimensional):* Base slope

*Down-slope shape:* Concave

*Across-slope shape:* Concave

*Hydric soil rating:* Yes

## Data Source Information

Soil Survey Area: Middlesex County, Massachusetts

Survey Area Data: Version 22, Sep 9, 2022

## Middlesex County, Massachusetts

### 300B—Montauk fine sandy loam, 3 to 8 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2tyrh

*Elevation:* 0 to 1,030 feet

*Mean annual precipitation:* 36 to 71 inches

*Mean annual air temperature:* 39 to 55 degrees F

*Frost-free period:* 140 to 240 days

*Farmland classification:* All areas are prime farmland

#### Map Unit Composition

*Montauk and similar soils:* 85 percent

*Minor components:* 15 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Montauk

##### Setting

*Landform:* Recessional moraines, ground moraines, hills, drumlins

*Landform position (two-dimensional):* Summit, shoulder, backslope

*Landform position (three-dimensional):* Crest, side slope

*Down-slope shape:* Convex, linear

*Across-slope shape:* Convex

*Parent material:* Coarse-loamy over sandy lodgment till derived from gneiss, granite, and/or schist

##### Typical profile

*Ap - 0 to 4 inches:* fine sandy loam

*Bw1 - 4 to 26 inches:* fine sandy loam

*Bw2 - 26 to 34 inches:* sandy loam

*2Cd - 34 to 72 inches:* gravelly loamy sand

##### Properties and qualities

*Slope:* 3 to 8 percent

*Depth to restrictive feature:* 20 to 39 inches to densic material

*Drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):* Very low to moderately high (0.00 to 1.42 in/hr)

*Depth to water table:* About 18 to 37 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Maximum salinity:* Nonsaline (0.0 to 1.9 mmhos/cm)

*Available water supply, 0 to 60 inches:* Low (about 5.2 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 2s

*Hydrologic Soil Group:* C



*Ecological site:* F144AY007CT - Well Drained Dense Till Uplands  
*Hydric soil rating:* No

### Minor Components

#### Scituate

*Percent of map unit:* 6 percent  
*Landform:* Ground moraines, hills, drumlins  
*Landform position (two-dimensional):* Summit, shoulder, backslope  
*Landform position (three-dimensional):* Crest, side slope  
*Down-slope shape:* Convex, linear  
*Across-slope shape:* Convex  
*Hydric soil rating:* No

#### Canton

*Percent of map unit:* 5 percent  
*Landform:* Hills  
*Landform position (two-dimensional):* Summit, shoulder, backslope  
*Landform position (three-dimensional):* Crest, side slope  
*Down-slope shape:* Convex, linear  
*Across-slope shape:* Convex  
*Hydric soil rating:* No

#### Ridgebury

*Percent of map unit:* 4 percent  
*Landform:* Depressions, ground moraines, hills, drainageways  
*Landform position (two-dimensional):* Footslope, toeslope  
*Landform position (three-dimensional):* Head slope, base slope  
*Down-slope shape:* Concave  
*Across-slope shape:* Concave  
*Hydric soil rating:* Yes

## Data Source Information

Soil Survey Area: Middlesex County, Massachusetts  
Survey Area Data: Version 22, Sep 9, 2022

## Middlesex County, Massachusetts

### 300C—Montauk fine sandy loam, 8 to 15 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2w80p

*Elevation:* 0 to 1,100 feet

*Mean annual precipitation:* 36 to 71 inches

*Mean annual air temperature:* 39 to 55 degrees F

*Frost-free period:* 140 to 240 days

*Farmland classification:* Farmland of statewide importance

#### Map Unit Composition

*Montauk and similar soils:* 85 percent

*Minor components:* 15 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Montauk

##### Setting

*Landform:* Recessional moraines, ground moraines, hills, drumlins

*Landform position (two-dimensional):* Backslope

*Landform position (three-dimensional):* Side slope

*Down-slope shape:* Convex, linear

*Across-slope shape:* Convex

*Parent material:* Coarse-loamy over sandy lodgment till derived from gneiss, granite, and/or schist

##### Typical profile

*Ap - 0 to 4 inches:* fine sandy loam

*Bw1 - 4 to 26 inches:* fine sandy loam

*Bw2 - 26 to 34 inches:* sandy loam

*2Cd - 34 to 72 inches:* gravelly loamy sand

##### Properties and qualities

*Slope:* 8 to 15 percent

*Depth to restrictive feature:* 20 to 39 inches to densic material

*Drainage class:* Well drained

*Runoff class:* Low

*Capacity of the most limiting layer to transmit water (Ksat):* Very low to moderately high (0.00 to 1.42 in/hr)

*Depth to water table:* About 18 to 37 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Maximum salinity:* Nonsaline (0.0 to 1.9 mmhos/cm)

*Available water supply, 0 to 60 inches:* Low (about 5.2 inches)

##### Interpretive groups

*Land capability classification (irrigated):* None specified

*Land capability classification (nonirrigated):* 3e

*Hydrologic Soil Group:* C



*Ecological site:* F144AY007CT - Well Drained Dense Till Uplands  
*Hydric soil rating:* No

### Minor Components

#### Scituate

*Percent of map unit:* 6 percent  
*Landform:* Ground moraines, hills, drumlins  
*Landform position (two-dimensional):* Backslope, footslope  
*Landform position (three-dimensional):* Side slope  
*Down-slope shape:* Convex, linear  
*Across-slope shape:* Convex  
*Hydric soil rating:* No

#### Canton

*Percent of map unit:* 5 percent  
*Landform:* Hills  
*Landform position (two-dimensional):* Backslope  
*Landform position (three-dimensional):* Side slope  
*Down-slope shape:* Convex, linear  
*Across-slope shape:* Convex  
*Hydric soil rating:* No

#### Ridgebury

*Percent of map unit:* 4 percent  
*Landform:* Depressions, ground moraines, hills, drainageways  
*Landform position (two-dimensional):* Footslope, toeslope  
*Landform position (three-dimensional):* Head slope, base slope  
*Down-slope shape:* Concave  
*Across-slope shape:* Concave  
*Hydric soil rating:* Yes


## Data Source Information

Soil Survey Area: Middlesex County, Massachusetts  
Survey Area Data: Version 22, Sep 9, 2022

## Appendix V Existing and Proposed Drainage Figures

## NOTES

1. HYDROLOGIC SOIL GROUP DESCRIPTIONS AND BOUNDARY IS SHOWN HEREON BASED ON AVAILABLE GIS DATA PROVIDED BY MASSMAPPER.



STATE/TOWN LINE

PELHAM, NH  
DRACUT, MA

BRIDGE STREET

CROSS STREET

ROUTE 38

PASTURE RD

LOCUS

MARSH HILL ROAD

SCALE: 1" - 500'

**PROPERTY ADDRESS:**

**2041 BRIDGE STREET**  
Dracut, Massachusetts 01826

PREPARED FOR:

# Marsh Hill Management, LLC

39 Myrtle Street  
Lowell, Massachusetts 01854

# HANCOCK ASSOCIATES

Civil Engineers

Land Surveyors


# Environmental Consultants

34 CHELMSFORD ST., CHELMSFORD, MA 01824  
VOICE (978) 244-0110, FAX (978) 244-1133  
WWW.HANCOCKASSOCIATES.COM


1	MJS	BGG	8/11/25	PEER REVIEW COMMENTS
NO.	BY	APP	DATE	ISSUE/REVISION DESCRIPTION
DATE:	09/17/24		DESIGN BY:	RT/MJS
SCALE:	AS SHOWN		DRAWN BY:	RT/MJS
APPRV'D BY:	BG	CHECK BY:	JP	

# PRE DEVELOPMENT SUBCATCHMENT PLAN

DWG: 27164-SP1.dwg
LAYOUT: PRE
SHEET: 1 OF 1
JOB NO.: 27164





## Appendix VI Hydrocad Output



Overland to Wetlands

# PRE DEVELOPMENT



Routing Diagram for 27164-2

Prepared by Hancock Associates, Printed 10/14/2025  
HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Printed 10/14/2025

Page 2

## **Project Notes**

Rainfall events imported from "Atlas-14-Rain.txt" for 6679 MA Middlesex North

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Printed 10/14/2025

Page 3

**Area Listing (selected nodes)**

Area (sq-ft)	CN	Description (subcatchment-numbers)
78,235	74	>75% Grass cover, Good, HSG C (1S)
3,745	98	Paved parking, HSG C (1S)
4,485	98	Roofs, HSG C (1S)
106,040	70	Woods, Good, HSG C (1S)
<b>192,505</b>	<b>73</b>	<b>TOTAL AREA</b>

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Type III 24-hr 2-Year Rainfall=3.04"**

Printed 10/14/2025

Page 4

**Summary for Subcatchment 1S: Overland to Wetlands**

Runoff = 3.76 cfs @ 12.14 hrs, Volume= 14,114 cf, Depth&gt; 0.88"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
106,040	70	Woods, Good, HSG C
3,745	98	Paved parking, HSG C
4,485	98	Roofs, HSG C
78,235	74	>75% Grass cover, Good, HSG C
192,505	73	Weighted Average
184,275		95.72% Pervious Area
8,230		4.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
1.0	150	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
1.3	60	0.0250	0.79		<b>Shallow Concentrated Flow, Shallow Flow - Slope Change</b> Woodland Kv= 5.0 fps
9.2	560	Total			

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Subcatchment 1S: Overland to Wetlands**

Runoff = 9.03 cfs @ 12.13 hrs, Volume= 31,559 cf, Depth&gt; 1.97"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
106,040	70	Woods, Good, HSG C
3,745	98	Paved parking, HSG C
4,485	98	Roofs, HSG C
78,235	74	>75% Grass cover, Good, HSG C
192,505	73	Weighted Average
184,275		95.72% Pervious Area
8,230		4.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
1.0	150	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
1.3	60	0.0250	0.79		<b>Shallow Concentrated Flow, Shallow Flow - Slope Change</b> Woodland Kv= 5.0 fps
9.2	560	Total			

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Subcatchment 1S: Overland to Wetlands**

Runoff = 13.67 cfs @ 12.13 hrs, Volume= 47,204 cf, Depth&gt; 2.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
106,040	70	Woods, Good, HSG C
3,745	98	Paved parking, HSG C
4,485	98	Roofs, HSG C
78,235	74	>75% Grass cover, Good, HSG C
192,505	73	Weighted Average
184,275		95.72% Pervious Area
8,230		4.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
1.0	150	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
1.3	60	0.0250	0.79		<b>Shallow Concentrated Flow, Shallow Flow - Slope Change</b> Woodland Kv= 5.0 fps
9.2	560	Total			

**27164-2****Type III 24-hr 100-Year Rainfall=8.37"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC



**Summary for Subcatchment 1S: Overland to Wetlands**

Runoff = 23.83 cfs @ 12.13 hrs, Volume= 82,301 cf, Depth&gt; 5.13"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
106,040	70	Woods, Good, HSG C
3,745	98	Paved parking, HSG C
4,485	98	Roofs, HSG C
78,235	74	>75% Grass cover, Good, HSG C
192,505	73	Weighted Average
184,275		95.72% Pervious Area
8,230		4.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
1.0	150	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
1.3	60	0.0250	0.79		<b>Shallow Concentrated Flow, Shallow Flow - Slope Change</b> Woodland Kv= 5.0 fps
9.2	560	Total			



## Routing Diagram for 27164-2

Prepared by Hancock Associates, Printed 10/14/2025  
HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**27164-2**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Area Listing (selected nodes)**

Area (sq-ft)	CN	Description (subcatchment-numbers)
1,000	61	>75% Grass cover, Good, HSG B (10S)
106,075	74	>75% Grass cover, Good, HSG C (10S, 11S, 12S, 13S, 14S, 15S, 18S, 21S, 22S, 23S, 24S, 25S, 26S, 27S, 28S)
35,600	98	Paved parking, HSG C (11S, 12S, 13S, 14S, 15S, 17S, 22S, 23S, 24S, 25S, 26S, 27S)
1,580	98	Retaining Wall, HSG C (12S, 13S, 14S, 15S)
19,085	98	Roofs, HSG C (20S, 21S, 22S)
180	98	Unconnected pavement, HSG C (25S)
175	98	Unconnected pavement, HSG C- ret. walls (23S)
115	98	Unconnected pavement, HSG C-ret walls (24S)
365	98	Unconnected pavement, HSG C-ret. walls (26S, 27S)
28,330	70	Woods, Good, HSG C (10S, 18S, 21S, 22S, 28S)
<b>192,505</b>	<b>80</b>	<b>TOTAL AREA</b>

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Subcatchment 10S: Overland to Wetlands**

Runoff = 0.47 cfs @ 12.10 hrs, Volume= 1,614 cf, Depth> 0.78"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
17,430	70	Woods, Good, HSG C
6,325	74	>75% Grass cover, Good, HSG C
1,000	61	>75% Grass cover, Good, HSG B
24,755	71	Weighted Average
24,755		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	50	0.1700	0.16		<b>Sheet Flow, Sheet Flow</b> Woods: Light underbrush n= 0.400 P2= 3.15"
0.2	20	0.1400	1.87		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
0.5	45	0.0560	1.66		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.0	115				Total

**Summary for Subcatchment 11S: Overland to CB1**

Runoff = 0.48 cfs @ 12.09 hrs, Volume= 1,483 cf, Depth> 1.77"  
 Routed to Pond CB1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
5,500	98	Paved parking, HSG C
4,545	74	>75% Grass cover, Good, HSG C
10,045	87	Weighted Average
4,545		45.25% Pervious Area
5,500		54.75% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Subcatchment 12S: Overland to CB2**

Runoff = 0.32 cfs @ 12.09 hrs, Volume= 1,011 cf, Depth> 2.11"  
 Routed to Pond CB2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
3,545	98	Paved parking, HSG C
440	98	Retaining Wall, HSG C
1,775	74	>75% Grass cover, Good, HSG C
5,760	91	Weighted Average
1,775		30.82% Pervious Area
3,985		69.18% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 13S: Overland to CB3**

Runoff = 0.76 cfs @ 12.09 hrs, Volume= 2,388 cf, Depth> 2.11"  
 Routed to Pond CB3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
9,580	98	Paved parking, HSG C
325	98	Retaining Wall, HSG C
3,700	74	>75% Grass cover, Good, HSG C
13,605	91	Weighted Average
3,700		27.20% Pervious Area
9,905		72.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 14S: Overland to CB4**

Runoff = 0.58 cfs @ 12.08 hrs, Volume= 1,866 cf, Depth> 2.39"  
 Routed to Pond CB4 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Area (sf)	CN	Description
7,175	98	Paved parking, HSG C
*	590	Retaining Wall, HSG C
1,615	74	>75% Grass cover, Good, HSG C
9,380	94	Weighted Average
1,615		17.22% Pervious Area
7,765		82.78% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**Summary for Subcatchment 15S: Overland to CB5**

Runoff = 0.25 cfs @ 12.09 hrs, Volume= 794 cf, Depth> 2.11"  
 Routed to Pond CB5 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
2,985	98	Paved parking, HSG C
*	225	Retaining Wall, HSG C
1,315	74	>75% Grass cover, Good, HSG C
4,525	91	Weighted Average
1,315		29.06% Pervious Area
3,210		70.94% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**Summary for Subcatchment 17S: Overland to Street Drainage**

Runoff = 0.04 cfs @ 12.08 hrs, Volume= 136 cf, Depth> 2.81"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
580	98	Paved parking, HSG C
580		100.00% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Subcatchment 18S: Overland to Drainage Swale**

Runoff = 0.52 cfs @ 12.00 hrs, Volume= 1,436 cf, Depth> 0.88"  
 Routed to Reach 19R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
4,935	70	Woods, Good, HSG C
14,605	74	>75% Grass cover, Good, HSG C
19,540	73	Weighted Average
19,540		100.00% Pervious Area

**Summary for Subcatchment 20S: Roof**

Runoff = 1.02 cfs @ 12.08 hrs, Volume= 3,538 cf, Depth> 2.81"  
 Routed to Pond DMH2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
15,130	98	Roofs, HSG C
15,130		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 21S: Overland to Rear of Building**

Runoff = 1.10 cfs @ 12.11 hrs, Volume= 3,717 cf, Depth> 0.99"  
 Routed to Reach 13R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
40,790	74	>75% Grass cover, Good, HSG C
2,910	70	Woods, Good, HSG C
1,575	98	Roofs, HSG C
45,275	75	Weighted Average
43,700		96.52% Pervious Area
1,575		3.48% Impervious Area

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
7.1	380	Total			

**Summary for Subcatchment 22S: Overland to Rear of Building**

Runoff = 0.93 cfs @ 12.10 hrs, Volume= 2,993 cf, Depth> 1.22"  
Routed to Reach 14R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
23,415	74	>75% Grass cover, Good, HSG C
425	70	Woods, Good, HSG C
2,380	98	Roofs, HSG C
3,320	98	Paved parking, HSG C
29,540	79	Weighted Average
23,840		80.70% Pervious Area
5,700		19.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
1.9	180	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.0200	2.87		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Paved Kv= 20.3 fps
0.8	110	0.1000	2.21		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.6	370	Total			

**Summary for Subcatchment 23S: Overland to AD5**

Runoff = 0.11 cfs @ 12.08 hrs, Volume= 351 cf, Depth> 2.59"  
Routed to Pond AD5 : AD5

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 2-Year Rainfall=3.04"

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Area (sf)	CN	Description
1,335	98	Paved parking, HSG C
*		
175	98	Unconnected pavement, HSG C- ret. walls
115	74	>75% Grass cover, Good, HSG C
1,625	96	Weighted Average
115		7.08% Pervious Area
1,510		92.92% Impervious Area
175		11.59% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(ft/sec)	(cfs)

6.0 **Direct Entry,****Summary for Subcatchment 24S: Overland to AD1**

Runoff = 0.03 cfs @ 12.09 hrs, Volume= 104 cf, Depth> 1.69"  
 Routed to Pond AD1 : AD1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
260	98	Paved parking, HSG C
*		
115	98	Unconnected pavement, HSG C-ret walls
360	74	>75% Grass cover, Good, HSG C
735	86	Weighted Average
360		48.98% Pervious Area
375		51.02% Impervious Area
115		30.67% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(ft/sec)	(cfs)

6.0 **Direct Entry,****Summary for Subcatchment 25S: Overland to AD2**

Runoff = 0.06 cfs @ 12.09 hrs, Volume= 193 cf, Depth> 1.28"  
 Routed to Pond AD2 : AD2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Adj	Description
360	98		Paved parking, HSG C
180	98		Unconnected pavement, HSG C
1,270	74		>75% Grass cover, Good, HSG C
1,810	81	80	Weighted Average, UI Adjusted
1,270			70.17% Pervious Area
540			29.83% Impervious Area
180			33.33% Unconnected

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 26S: Overland to AD3**

Runoff = 0.02 cfs @ 12.09 hrs, Volume= 74 cf, Depth> 1.48"  
 Routed to Pond AD3 : AD3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
185	98	Paved parking, HSG C
*	40	Unconnected pavement, HSG C-ret. walls
	375	>75% Grass cover, Good, HSG C
	600	Weighted Average
375		62.50% Pervious Area
225		37.50% Impervious Area
40		17.78% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 27S: Overland to AD4**

Runoff = 0.11 cfs @ 12.09 hrs, Volume= 335 cf, Depth> 1.55"  
 Routed to Pond AD4 : AD4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
775	98	Paved parking, HSG C
*	325	Unconnected pavement, HSG C-ret. walls
	1,495	>75% Grass cover, Good, HSG C
	2,595	Weighted Average
1,495		57.61% Pervious Area
1,100		42.39% Impervious Area
325		29.55% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Subcatchment 28S: Overland to CB6**

Runoff = 0.14 cfs @ 12.10 hrs, Volume= 485 cf, Depth> 0.83"  
 Routed to Pond 29P : CB6

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 2-Year Rainfall=3.04"

Area (sf)	CN	Description
2,630	70	Woods, Good, HSG C
4,375	74	>75% Grass cover, Good, HSG C
7,005	72	Weighted Average
7,005		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Reach 10R: Wetlands System - Peppermint Brook**

Inflow Area = 192,505 sf, 29.66% Impervious, Inflow Depth > 0.65" for 2-Year event  
 Inflow = 2.92 cfs @ 12.11 hrs, Volume= 10,368 cf  
 Outflow = 2.92 cfs @ 12.11 hrs, Volume= 10,368 cf, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**Summary for Reach 13R: Drainage Swale**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 0.99" for 2-Year event  
 Inflow = 1.10 cfs @ 12.11 hrs, Volume= 3,717 cf  
 Outflow = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf, Atten= 2%, Lag= 1.0 min  
 Routed to Pond DCB2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Max. Velocity= 1.64 fps, Min. Travel Time= 1.5 min  
 Avg. Velocity = 0.54 fps, Avg. Travel Time= 4.5 min

Peak Storage= 95 cf @ 12.13 hrs  
 Average Depth at Peak Storage= 0.18', Surface Width= 4.11'  
 Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 25.08 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight  
 Side Slope Z-value= 3.0 '/' Top Width= 9.00'  
 Length= 145.0' Slope= 0.0069 '/'  
 Inlet Invert= 172.00', Outlet Invert= 171.00'

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.04"

Printed 10/14/2025

‡

### **Summary for Reach 14R: Drainage Swale**

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 1.22" for 2-Year event  
Inflow = 0.93 cfs @ 12.10 hrs, Volume= 2,993 cf  
Outflow = 0.93 cfs @ 12.11 hrs, Volume= 2,991 cf, Atten= 0%, Lag= 0.5 min  
Routed to Pond DCB1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Max. Velocity= 1.61 fps, Min. Travel Time= 0.7 min  
Avg. Velocity = 0.50 fps, Avg. Travel Time= 2.2 min

Peak Storage= 37 cf @ 12.11 hrs  
Average Depth at Peak Storage= 0.16', Surface Width= 3.99'  
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 26.49 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight  
Side Slope Z-value= 3.0 '/' Top Width= 9.00'  
Length= 65.0' Slope= 0.0077 '/'  
Inlet Invert= 174.00', Outlet Invert= 173.50'

‡

### **Summary for Reach 19R: Drainage Swale**

Inflow Area = 19,540 sf, 0.00% Impervious, Inflow Depth > 0.88" for 2-Year event  
Inflow = 0.52 cfs @ 12.00 hrs, Volume= 1,436 cf  
Outflow = 0.48 cfs @ 12.03 hrs, Volume= 1,433 cf, Atten= 8%, Lag= 1.4 min  
Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Max. Velocity= 3.14 fps, Min. Travel Time= 1.8 min  
Avg. Velocity = 1.00 fps, Avg. Travel Time= 5.7 min

Peak Storage= 52 cf @ 12.03 hrs  
Average Depth at Peak Storage= 0.09', Surface Width= 2.02'  
Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.44 cfs

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

1.50' x 0.50' deep channel, n= 0.025 Earth, clean & winding  
 Side Slope Z-value= 3.0 '/' Top Width= 4.50'  
 Length= 340.0' Slope= 0.0882 '/'  
 Inlet Invert= 172.00', Outlet Invert= 142.00'



‡

### Summary for Pond 11P: P.UIS1

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth > 1.89" for 2-Year event  
 Inflow = 0.80 cfs @ 12.09 hrs, Volume= 2,494 cf  
 Outflow = 0.27 cfs @ 12.01 hrs, Volume= 2,494 cf, Atten= 66%, Lag= 0.0 min  
 Discarded = 0.27 cfs @ 12.01 hrs, Volume= 2,494 cf  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf  
 Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 144.88' @ 12.38 hrs Surf.Area= 1,435 sf Storage= 362 cf

Plug-Flow detention time= 6.0 min calculated for 2,494 cf (100% of inflow)  
 Center-of-Mass det. time= 6.0 min ( 819.6 - 813.6 )

Volume	Invert	Avail.Storage	Storage Description
#1A	144.25'	2,065 cf	<b>22.75'W x 63.06'L x 5.50'H Field A</b> 7,890 cf Overall - 2,728 cf Embedded = 5,162 cf x 40.0% Voids
#2A	145.00'	2,728 cf	<b>ADS_StormTech MC-3500 d +Cap x 24 Inside #1</b> Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 24 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,793 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	144.25'	<b>8.270 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	148.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	146.00'	<b>12.0" Round Culvert</b> L= 13.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.00' / 145.80' S= 0.0154 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	146.25'	<b>12.0" Vert. Orifice/Grate</b>	C= 0.600 Limited to weir flow at low heads

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Discarded OutFlow** Max=0.27 cfs @ 12.01 hrs HW=144.32' (Free Discharge)↑  
1=Exfiltration (Exfiltration Controls 0.27 cfs)**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=144.25' TW=141.83' (Dynamic Tailwater)↑  
3=Culvert (Controls 0.00 cfs)

└─2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

└─4=Orifice/Grate (Controls 0.00 cfs)

### Summary for Pond 12P: P.UIS2

Inflow Area = 22,495 sf, 83.93% Impervious, Inflow Depth > 2.45" for 2-Year event  
 Inflow = 1.36 cfs @ 12.08 hrs, Volume= 4,593 cf  
 Outflow = 0.07 cfs @ 11.17 hrs, Volume= 4,064 cf, Atten= 95%, Lag= 0.0 min  
 Discarded = 0.07 cfs @ 11.17 hrs, Volume= 4,064 cf  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 142.89' @ 14.17 hrs Surf.Area= 1,271 sf Storage= 2,054 cf

Plug-Flow detention time= 236.4 min calculated for 4,062 cf (88% of inflow)  
 Center-of-Mass det. time= 181.9 min ( 952.1 - 770.2 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	1,838 cf	<b>22.75'W x 55.89'L x 5.50'H Field A</b> 6,993 cf Overall - 2,398 cf Embedded = 4,595 cf x 40.0% Voids
#2A	141.25'	2,398 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 21 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 21 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,236 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	139.50'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.50' / 139.40' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	143.25'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads	

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Discarded OutFlow** Max=0.07 cfs @ 11.17 hrs HW=140.56' (Free Discharge)↑  
1=Exfiltration (Exfiltration Controls 0.07 cfs)**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=140.50' TW=139.00' (Dynamic Tailwater)↑  
3=Culvert (Passes 0.00 cfs of 2.10 cfs potential flow)  
└─2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)  
└─4=Orifice/Grate (Controls 0.00 cfs)

### Summary for Pond 13P: P.UIS3

Inflow Area = 22,985 sf, 76.88% Impervious, Inflow Depth > 2.22" for 2-Year event  
 Inflow = 1.34 cfs @ 12.09 hrs, Volume= 4,254 cf  
 Outflow = 0.11 cfs @ 11.69 hrs, Volume= 4,254 cf, Atten= 92%, Lag= 0.0 min  
 Discarded = 0.11 cfs @ 11.69 hrs, Volume= 4,254 cf  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 141.93' @ 13.14 hrs Surf.Area= 1,924 sf Storage= 1,662 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 125.1 min ( 922.0 - 796.9 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	2,746 cf	<b>22.75'W x 84.57'L x 5.50'H Field A</b> 10,582 cf Overall - 3,718 cf Embedded = 6,864 cf x 40.0% Voids
#2A	141.25'	3,718 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 33 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 33 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
6,463 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	141.00'	<b>12.0" Round Culvert</b> L= 31.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.00' / 139.90' S= 0.0355 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#4	Device 3	143.45'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Discarded OutFlow** Max=0.11 cfs @ 11.69 hrs HW=140.56' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.11 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=140.50' TW=139.00' (Dynamic Tailwater)

↑ 3=Culvert (Controls 0.00 cfs)

2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

4=Orifice/Grate (Controls 0.00 cfs)

### Summary for Pond 14P: P.UIS4

Inflow Area =	4,525 sf, 70.94% Impervious, Inflow Depth > 2.11" for 2-Year event
Inflow =	0.25 cfs @ 12.09 hrs, Volume= 794 cf
Outflow =	0.07 cfs @ 11.88 hrs, Volume= 794 cf, Atten= 72%, Lag= 0.0 min
Discarded =	0.07 cfs @ 11.88 hrs, Volume= 794 cf
Primary =	0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 140.58' @ 12.44 hrs Surf.Area= 364 sf Storage= 148 cf

Plug-Flow detention time= 10.3 min calculated for 794 cf (100% of inflow)

Center-of-Mass det. time= 10.2 min ( 814.0 - 803.8 )

Volume	Invert	Avail.Storage	Storage Description
#1A	139.80'	269 cf	<b>14.83'W x 24.56'L x 2.33'H Field A</b> 850 cf Overall - 177 cf Embedded = 673 cf x 40.0% Voids
#2A	140.30'	177 cf	<b>ADS_StormTech SC-310 +Cap</b> x 12 Inside #1 Effective Size= 28.9"W x 16.0"H => 2.07 sf x 7.12'L = 14.7 cf Overall Size= 34.0"W x 16.0"H x 7.56'L with 0.44' Overlap 12 Chambers in 4 Rows
446 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	139.80'	<b>8.270 in/hr Exfiltration over Surface area</b> Phase-In= 0.01'
#2	Device 3	141.10'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	140.45'	<b>12.0" Round Culvert</b> L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.45' / 140.20' S= 0.0147 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Discarded OutFlow** Max=0.07 cfs @ 11.88 hrs HW=139.83' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.07 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=139.80' TW=0.00' (Dynamic Tailwater)

↑ 3=Culvert (Controls 0.00 cfs)

2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond 29P: CB6**

Inflow Area = 7,005 sf, 0.00% Impervious, Inflow Depth > 0.83" for 2-Year event  
 Inflow = 0.14 cfs @ 12.10 hrs, Volume= 485 cf  
 Outflow = 0.14 cfs @ 12.10 hrs, Volume= 485 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.14 cfs @ 12.10 hrs, Volume= 485 cf  
 Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 150.31' @ 12.10 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	150.10'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 150.10' / 150.00' S= 0.0250 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.14 cfs @ 12.10 hrs HW=150.31' TW=147.01' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.14 cfs @ 1.22 fps)

**Summary for Pond AD1: AD1**

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth > 1.69" for 2-Year event  
 Inflow = 0.03 cfs @ 12.09 hrs, Volume= 104 cf  
 Outflow = 0.03 cfs @ 12.09 hrs, Volume= 104 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.03 cfs @ 12.09 hrs, Volume= 104 cf  
 Routed to Pond DMH13 : DMH13

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 160.90' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.80'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.80' / 160.70' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.03 cfs @ 12.09 hrs HW=160.90' TW=160.80' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.03 cfs @ 0.84 fps)

**Summary for Pond AD2: AD2**

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth > 1.28" for 2-Year event  
 Inflow = 0.06 cfs @ 12.09 hrs, Volume= 193 cf  
 Outflow = 0.06 cfs @ 12.09 hrs, Volume= 193 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.06 cfs @ 12.09 hrs, Volume= 193 cf  
 Routed to Pond DMH6 : DMH6

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 160.13' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.00'	<b>12.0" Round Culvert</b> L= 12.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.00' / 159.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.06 cfs @ 12.09 hrs HW=160.13' TW=159.88' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.06 cfs @ 0.98 fps)

### Summary for Pond AD3: AD3

Inflow Area = 600 sf, 37.50% Impervious, Inflow Depth > 1.48" for 2-Year event  
 Inflow = 0.02 cfs @ 12.09 hrs, Volume= 74 cf  
 Outflow = 0.02 cfs @ 12.09 hrs, Volume= 74 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.02 cfs @ 12.09 hrs, Volume= 74 cf  
 Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 159.63' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.55'	<b>12.0" Round Culvert</b> L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.55' / 159.45' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.02 cfs @ 12.09 hrs HW=159.63' TW=159.51' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.02 cfs @ 0.77 fps)

### Summary for Pond AD4: AD4

Inflow Area = 2,595 sf, 42.39% Impervious, Inflow Depth > 1.55" for 2-Year event  
 Inflow = 0.11 cfs @ 12.09 hrs, Volume= 335 cf  
 Outflow = 0.11 cfs @ 12.09 hrs, Volume= 335 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.11 cfs @ 12.09 hrs, Volume= 335 cf  
 Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 158.13' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	157.95'	<b>12.0" Round Culvert</b> L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.95' / 157.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.11 cfs @ 12.09 hrs HW=158.13' TW=148.34' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.11 cfs @ 1.14 fps)

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond AD5: AD5**

Inflow Area = 1,625 sf, 92.92% Impervious, Inflow Depth > 2.59" for 2-Year event  
 Inflow = 0.11 cfs @ 12.08 hrs, Volume= 351 cf  
 Outflow = 0.11 cfs @ 12.08 hrs, Volume= 351 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.11 cfs @ 12.08 hrs, Volume= 351 cf  
 Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 147.38' @ 12.08 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.20'	<b>12.0" Round Culvert</b> L= 11.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.20' / 147.10' S= 0.0091 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.11 cfs @ 12.08 hrs HW=147.38' TW=147.20' (Dynamic Tailwater)  
 ↑1=Culvert (Barrel Controls 0.11 cfs @ 1.71 fps)

**Summary for Pond CB1:**

Inflow Area = 10,045 sf, 54.75% Impervious, Inflow Depth > 1.77" for 2-Year event  
 Inflow = 0.48 cfs @ 12.09 hrs, Volume= 1,483 cf  
 Outflow = 0.48 cfs @ 12.09 hrs, Volume= 1,483 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.48 cfs @ 12.09 hrs, Volume= 1,483 cf  
 Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 147.14' @ 12.09 hrs  
 Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.48 cfs @ 12.09 hrs HW=147.14' TW=145.74' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.48 cfs @ 1.68 fps)

**Summary for Pond CB2:**

Inflow Area = 5,760 sf, 69.18% Impervious, Inflow Depth > 2.11" for 2-Year event  
 Inflow = 0.32 cfs @ 12.09 hrs, Volume= 1,011 cf  
 Outflow = 0.32 cfs @ 12.09 hrs, Volume= 1,011 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.32 cfs @ 12.09 hrs, Volume= 1,011 cf  
 Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 147.07' @ 12.09 hrs

Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.32 cfs @ 12.09 hrs HW=147.07' TW=145.74' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.32 cfs @ 1.51 fps)

**Summary for Pond CB3:**

Inflow Area = 13,605 sf, 72.80% Impervious, Inflow Depth &gt; 2.11" for 2-Year event

Inflow = 0.76 cfs @ 12.09 hrs, Volume= 2,388 cf

Outflow = 0.76 cfs @ 12.09 hrs, Volume= 2,388 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.76 cfs @ 12.09 hrs, Volume= 2,388 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 143.96' @ 12.09 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=0.76 cfs @ 12.09 hrs HW=143.96' TW=142.09' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.76 cfs @ 2.18 fps)

**Summary for Pond CB4:**

Inflow Area = 9,380 sf, 82.78% Impervious, Inflow Depth &gt; 2.39" for 2-Year event

Inflow = 0.58 cfs @ 12.08 hrs, Volume= 1,866 cf

Outflow = 0.58 cfs @ 12.08 hrs, Volume= 1,866 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.58 cfs @ 12.08 hrs, Volume= 1,866 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 143.83' @ 12.08 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 6.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0167 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Primary OutFlow** Max=0.58 cfs @ 12.08 hrs HW=143.83' TW=142.09' (Dynamic Tailwater)  
 ↗ 1=Culvert (Barrel Controls 0.58 cfs @ 2.65 fps)

### Summary for Pond CB5:

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 2.11" for 2-Year event  
 Inflow = 0.25 cfs @ 12.09 hrs, Volume= 794 cf  
 Outflow = 0.25 cfs @ 12.09 hrs, Volume= 794 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.25 cfs @ 12.09 hrs, Volume= 794 cf  
 Routed to Pond DMH5 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 140.97' @ 12.09 hrs  
 Flood Elev= 143.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.60'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.60' / 140.50' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.25 cfs @ 12.09 hrs HW=140.97' TW=140.77' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 0.25 cfs @ 1.63 fps)

### Summary for Pond DCB1:

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 1.21" for 2-Year event  
 Inflow = 0.93 cfs @ 12.11 hrs, Volume= 2,991 cf  
 Outflow = 0.93 cfs @ 12.11 hrs, Volume= 2,991 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.93 cfs @ 12.11 hrs, Volume= 2,991 cf  
 Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 157.77' @ 12.11 hrs  
 Flood Elev= 173.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	157.20'	<b>12.0" Round Culvert</b> L= 131.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.20' / 150.00' S= 0.0550 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.92 cfs @ 12.11 hrs HW=157.77' TW=147.01' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 0.92 cfs @ 2.02 fps)

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond DCB2:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 0.98" for 2-Year event  
 Inflow = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf  
 Outflow = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf  
 Routed to Pond DMH9 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 152.72' @ 12.13 hrs

Flood Elev= 172.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	152.10'	<b>12.0" Round Culvert</b> L= 78.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 152.10' / 148.60' S= 0.0449 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.07 cfs @ 12.13 hrs HW=152.72' TW=143.00' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 1.07 cfs @ 2.11 fps)

**Summary for Pond DMH1:**

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth > 1.89" for 2-Year event  
 Inflow = 0.80 cfs @ 12.09 hrs, Volume= 2,494 cf  
 Outflow = 0.80 cfs @ 12.09 hrs, Volume= 2,494 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.80 cfs @ 12.09 hrs, Volume= 2,494 cf  
 Routed to Pond 11P : P.UIS1

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 145.74' @ 12.09 hrs

Flood Elev= 150.55'

Device	Routing	Invert	Outlet Devices
#1	Primary	145.20'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 145.20' / 145.11' S= 0.0225 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.80 cfs @ 12.09 hrs HW=145.74' TW=144.52' (Dynamic Tailwater)

↑ 1=Culvert (Barrel Controls 0.80 cfs @ 2.67 fps)

**Summary for Pond DMH10:**

Inflow Area = 36,545 sf, 15.60% Impervious, Inflow Depth > 1.14" for 2-Year event  
 Inflow = 1.07 cfs @ 12.11 hrs, Volume= 3,476 cf  
 Outflow = 1.07 cfs @ 12.11 hrs, Volume= 3,476 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.07 cfs @ 12.11 hrs, Volume= 3,476 cf  
 Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 147.01' @ 12.11 hrs

Flood Elev= 154.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.40'	<b>12.0" Round Culvert</b> L= 43.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.40' / 145.80' S= 0.0140 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.07 cfs @ 12.11 hrs HW=147.01' TW=142.35' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 1.07 cfs @ 2.11 fps)

**Summary for Pond DMH11:**

Inflow Area = 52,350 sf, 29.01% Impervious, Inflow Depth &gt; 0.80" for 2-Year event

Inflow = 1.07 cfs @ 12.11 hrs, Volume= 3,476 cf

Outflow = 1.07 cfs @ 12.11 hrs, Volume= 3,476 cf, Atten= 0%, Lag= 0.0 min

Primary = 1.07 cfs @ 12.11 hrs, Volume= 3,476 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 142.35' @ 12.11 hrs

Flood Elev= 152.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.83'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.83' / 141.50' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=1.07 cfs @ 12.11 hrs HW=142.35' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 1.07 cfs @ 1.94 fps)

**Summary for Pond DMH12: DMH12**

Inflow Area = 2,360 sf, 79.87% Impervious, Inflow Depth &gt; 2.31" for 2-Year event

Inflow = 0.14 cfs @ 12.09 hrs, Volume= 454 cf

Outflow = 0.14 cfs @ 12.09 hrs, Volume= 454 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.14 cfs @ 12.09 hrs, Volume= 454 cf

Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.20' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.00'	<b>12.0" Round Culvert</b> L= 208.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.00' / 142.35' S= 0.0224 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Primary OutFlow** Max=0.14 cfs @ 12.09 hrs HW=147.20' TW=142.20' (Dynamic Tailwater)  
↑**1=Culvert** (Inlet Controls 0.14 cfs @ 1.21 fps)

### **Summary for Pond DMH13: DMH13**

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth > 1.69" for 2-Year event  
Inflow = 0.03 cfs @ 12.09 hrs, Volume= 104 cf  
Outflow = 0.03 cfs @ 12.09 hrs, Volume= 104 cf, Atten= 0%, Lag= 0.0 min  
Primary = 0.03 cfs @ 12.09 hrs, Volume= 104 cf  
Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Peak Elev= 160.80' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.70'	<b>12.0" Round Culvert</b> L= 100.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.70' / 147.10' S= 0.1360 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.03 cfs @ 12.09 hrs HW=160.80' TW=147.20' (Dynamic Tailwater)  
↑**1=Culvert** (Inlet Controls 0.03 cfs @ 0.84 fps)

### **Summary for Pond DMH2:**

Inflow Area = 22,495 sf, 83.93% Impervious, Inflow Depth > 2.45" for 2-Year event  
Inflow = 1.36 cfs @ 12.08 hrs, Volume= 4,593 cf  
Outflow = 1.36 cfs @ 12.08 hrs, Volume= 4,593 cf, Atten= 0%, Lag= 0.0 min  
Primary = 1.36 cfs @ 12.08 hrs, Volume= 4,593 cf  
Routed to Pond 12P : P.UIS2

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Peak Elev= 142.89' @ 14.17 hrs  
Flood Elev= 150.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.45'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.45' / 141.36' S= 0.0180 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.35 cfs @ 12.08 hrs HW=142.20' TW=141.77' (Dynamic Tailwater)  
↑**1=Culvert** (Barrel Controls 1.35 cfs @ 2.97 fps)

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond DMH3:**

Inflow Area = 90,755 sf, 42.01% Impervious, Inflow Depth > 0.49" for 2-Year event  
 Inflow = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf  
 Outflow = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 139.53' @ 12.13 hrs

Flood Elev= 149.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	139.00'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.00' / 138.50' S= 0.0152 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=1.07 cfs @ 12.13 hrs HW=139.53' TW=0.00' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 1.07 cfs @ 1.95 fps)

**Summary for Pond DMH4:**

Inflow Area = 22,985 sf, 76.88% Impervious, Inflow Depth > 2.22" for 2-Year event  
 Inflow = 1.34 cfs @ 12.09 hrs, Volume= 4,254 cf  
 Outflow = 1.34 cfs @ 12.09 hrs, Volume= 4,254 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.34 cfs @ 12.09 hrs, Volume= 4,254 cf  
 Routed to Pond 13P : P.UIS3

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 142.09' @ 12.09 hrs

Flood Elev= 146.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.35'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.35' / 141.25' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.34 cfs @ 12.09 hrs HW=142.09' TW=141.35' (Dynamic Tailwater)  
 ↑ 1=Culvert (Barrel Controls 1.34 cfs @ 3.01 fps)

**Summary for Pond DMH5:**

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 2.11" for 2-Year event  
 Inflow = 0.25 cfs @ 12.09 hrs, Volume= 794 cf  
 Outflow = 0.25 cfs @ 12.09 hrs, Volume= 794 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.25 cfs @ 12.09 hrs, Volume= 794 cf  
 Routed to Pond 14P : P.UIS4

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 140.77' @ 12.09 hrs

Flood Elev= 143.90'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.40'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.40' / 140.30' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.25 cfs @ 12.09 hrs HW=140.77' TW=140.25' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.25 cfs @ 1.63 fps)

**Summary for Pond DMH6: DMH6**

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth &gt; 1.28" for 2-Year event

Inflow = 0.06 cfs @ 12.09 hrs, Volume= 193 cf

Outflow = 0.06 cfs @ 12.09 hrs, Volume= 193 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.06 cfs @ 12.09 hrs, Volume= 193 cf

Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 159.88' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.75'	<b>12.0" Round Culvert</b> L= 29.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.75' / 159.45' S= 0.0103 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.06 cfs @ 12.09 hrs HW=159.88' TW=159.51' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.06 cfs @ 0.98 fps)

**Summary for Pond DMH7: DMH7**

Inflow Area = 2,410 sf, 31.74% Impervious, Inflow Depth &gt; 1.33" for 2-Year event

Inflow = 0.09 cfs @ 12.09 hrs, Volume= 267 cf

Outflow = 0.09 cfs @ 12.09 hrs, Volume= 267 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.09 cfs @ 12.09 hrs, Volume= 267 cf

Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 159.51' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.35'	<b>12.0" Round Culvert</b> L= 147.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.35' / 157.85' S= 0.0102 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.09 cfs @ 12.09 hrs HW=159.51' TW=148.34' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.09 cfs @ 1.07 fps)

**27164-2****Type III 24-hr 2-Year Rainfall=3.04"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond DMH8: DMH8**

Inflow Area = 5,005 sf, 37.26% Impervious, Inflow Depth > 1.44" for 2-Year event  
 Inflow = 0.19 cfs @ 12.09 hrs, Volume= 601 cf  
 Outflow = 0.19 cfs @ 12.09 hrs, Volume= 601 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.19 cfs @ 12.09 hrs, Volume= 601 cf  
 Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 148.34' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	148.10'	<b>12.0" Round Culvert</b> L= 72.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 148.10' / 142.35' S= 0.0799 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.19 cfs @ 12.09 hrs HW=148.34' TW=142.20' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.19 cfs @ 1.32 fps)

**Summary for Pond DMH9:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 0.98" for 2-Year event  
 Inflow = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf  
 Outflow = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.08 cfs @ 12.13 hrs, Volume= 3,710 cf  
 Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 143.00' @ 12.13 hrs  
 Flood Elev= 154.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	142.38'	<b>12.0" Round Culvert</b> L= 55.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 142.38' / 139.90' S= 0.0451 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.07 cfs @ 12.13 hrs HW=143.00' TW=139.53' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 1.07 cfs @ 2.11 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Subcatchment 10S: Overland to Wetlands**

Runoff = 1.19 cfs @ 12.09 hrs, Volume= 3,747 cf, Depth> 1.82"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
17,430	70	Woods, Good, HSG C
6,325	74	>75% Grass cover, Good, HSG C
1,000	61	>75% Grass cover, Good, HSG B
24,755	71	Weighted Average
24,755		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	50	0.1700	0.16		<b>Sheet Flow, Sheet Flow</b> Woods: Light underbrush n= 0.400 P2= 3.15"
0.2	20	0.1400	1.87		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
0.5	45	0.0560	1.66		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.0	115				Total

**Summary for Subcatchment 11S: Overland to CB1**

Runoff = 0.85 cfs @ 12.09 hrs, Volume= 2,669 cf, Depth> 3.19"  
 Routed to Pond CB1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
5,500	98	Paved parking, HSG C
4,545	74	>75% Grass cover, Good, HSG C
10,045	87	Weighted Average
4,545		45.25% Pervious Area
5,500		54.75% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Subcatchment 12S: Overland to CB2**

Runoff = 0.54 cfs @ 12.08 hrs, Volume= 1,724 cf, Depth> 3.59"  
 Routed to Pond CB2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
3,545	98	Paved parking, HSG C
440	98	Retaining Wall, HSG C
1,775	74	>75% Grass cover, Good, HSG C
5,760	91	Weighted Average
1,775		30.82% Pervious Area
3,985		69.18% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 13S: Overland to CB3**

Runoff = 1.27 cfs @ 12.08 hrs, Volume= 4,072 cf, Depth> 3.59"  
 Routed to Pond CB3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
9,580	98	Paved parking, HSG C
325	98	Retaining Wall, HSG C
3,700	74	>75% Grass cover, Good, HSG C
13,605	91	Weighted Average
3,700		27.20% Pervious Area
9,905		72.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 14S: Overland to CB4**

Runoff = 0.92 cfs @ 12.08 hrs, Volume= 3,057 cf, Depth> 3.91"  
 Routed to Pond CB4 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

Area (sf)	CN	Description
7,175	98	Paved parking, HSG C
*	590	Retaining Wall, HSG C
1,615	74	>75% Grass cover, Good, HSG C
9,380	94	Weighted Average
1,615		17.22% Pervious Area
7,765		82.78% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**Summary for Subcatchment 15S: Overland to CB5**

Runoff = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf, Depth> 3.59"  
 Routed to Pond CB5 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
2,985	98	Paved parking, HSG C
*	225	Retaining Wall, HSG C
1,315	74	>75% Grass cover, Good, HSG C
4,525	91	Weighted Average
1,315		29.06% Pervious Area
3,210		70.94% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**Summary for Subcatchment 17S: Overland to Street Drainage**

Runoff = 0.06 cfs @ 12.08 hrs, Volume= 211 cf, Depth> 4.36"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
580	98	Paved parking, HSG C
580		100.00% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Subcatchment 18S: Overland to Drainage Swale**

Runoff = 1.25 cfs @ 12.00 hrs, Volume= 3,210 cf, Depth> 1.97"  
 Routed to Reach 19R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
4,935	70	Woods, Good, HSG C
14,605	74	>75% Grass cover, Good, HSG C
19,540	73	Weighted Average
19,540		100.00% Pervious Area

**Summary for Subcatchment 20S: Roof**

Runoff = 1.56 cfs @ 12.08 hrs, Volume= 5,498 cf, Depth> 4.36"  
 Routed to Pond DMH2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
15,130	98	Roofs, HSG C
15,130		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 21S: Overland to Rear of Building**

Runoff = 2.48 cfs @ 12.11 hrs, Volume= 8,020 cf, Depth> 2.13"  
 Routed to Reach 13R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
40,790	74	>75% Grass cover, Good, HSG C
2,910	70	Woods, Good, HSG C
1,575	98	Roofs, HSG C
45,275	75	Weighted Average
43,700		96.52% Pervious Area
1,575		3.48% Impervious Area

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
7.1	380	Total			

**Summary for Subcatchment 22S: Overland to Rear of Building**

Runoff = 1.92 cfs @ 12.10 hrs, Volume= 6,049 cf, Depth> 2.46"  
 Routed to Reach 14R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
23,415	74	>75% Grass cover, Good, HSG C
425	70	Woods, Good, HSG C
2,380	98	Roofs, HSG C
3,320	98	Paved parking, HSG C
29,540	79	Weighted Average
23,840		80.70% Pervious Area
5,700		19.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
1.9	180	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.0200	2.87		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Paved Kv= 20.3 fps
0.8	110	0.1000	2.21		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.6	370	Total			

**Summary for Subcatchment 23S: Overland to AD5**

Runoff = 0.16 cfs @ 12.08 hrs, Volume= 560 cf, Depth> 4.13"  
 Routed to Pond AD5 : AD5

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

**27164-2****Type III 24-hr 10-Year Rainfall=4.60"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Area (sf)	CN	Description
1,335	98	Paved parking, HSG C
*		
175	98	Unconnected pavement, HSG C- ret. walls
115	74	>75% Grass cover, Good, HSG C
1,625	96	Weighted Average
115		7.08% Pervious Area
1,510		92.92% Impervious Area
175		11.59% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(ft/sec)	(cfs)

6.0 **Direct Entry,****Summary for Subcatchment 24S: Overland to AD1**

Runoff = 0.06 cfs @ 12.09 hrs, Volume= 189 cf, Depth> 3.09"  
 Routed to Pond AD1 : AD1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
260	98	Paved parking, HSG C
*		
115	98	Unconnected pavement, HSG C-ret walls
360	74	>75% Grass cover, Good, HSG C
735	86	Weighted Average
360		48.98% Pervious Area
375		51.02% Impervious Area
115		30.67% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(ft/sec)	(cfs)

6.0 **Direct Entry,****Summary for Subcatchment 25S: Overland to AD2**

Runoff = 0.12 cfs @ 12.09 hrs, Volume= 384 cf, Depth> 2.54"  
 Routed to Pond AD2 : AD2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Adj	Description
360	98		Paved parking, HSG C
180	98		Unconnected pavement, HSG C
1,270	74		>75% Grass cover, Good, HSG C
1,810	81	80	Weighted Average, UI Adjusted
1,270			70.17% Pervious Area
540			29.83% Impervious Area
180			33.33% Unconnected

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 26S: Overland to AD3**

Runoff = 0.05 cfs @ 12.09 hrs, Volume= 141 cf, Depth> 2.81"  
 Routed to Pond AD3 : AD3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
185	98	Paved parking, HSG C
*	40	Unconnected pavement, HSG C-ret. walls
	375	>75% Grass cover, Good, HSG C
	600	Weighted Average
375		62.50% Pervious Area
225		37.50% Impervious Area
40		17.78% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 27S: Overland to AD4**

Runoff = 0.20 cfs @ 12.09 hrs, Volume= 628 cf, Depth> 2.90"  
 Routed to Pond AD4 : AD4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
775	98	Paved parking, HSG C
*	325	Unconnected pavement, HSG C-ret. walls
	1,495	>75% Grass cover, Good, HSG C
	2,595	Weighted Average
1,495		57.61% Pervious Area
1,100		42.39% Impervious Area
325		29.55% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Subcatchment 28S: Overland to CB6**

Runoff = 0.35 cfs @ 12.09 hrs, Volume= 1,104 cf, Depth> 1.89"  
 Routed to Pond 29P : CB6

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 10-Year Rainfall=4.60"

Area (sf)	CN	Description
2,630	70	Woods, Good, HSG C
4,375	74	>75% Grass cover, Good, HSG C
7,005	72	Weighted Average
7,005		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Reach 10R: Wetlands System - Peppermint Brook**

Inflow Area = 192,505 sf, 29.66% Impervious, Inflow Depth > 1.50" for 10-Year event  
 Inflow = 6.60 cfs @ 12.10 hrs, Volume= 24,018 cf  
 Outflow = 6.60 cfs @ 12.10 hrs, Volume= 24,018 cf, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**Summary for Reach 13R: Drainage Swale**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 2.13" for 10-Year event  
 Inflow = 2.48 cfs @ 12.11 hrs, Volume= 8,020 cf  
 Outflow = 2.45 cfs @ 12.12 hrs, Volume= 8,010 cf, Atten= 1%, Lag= 0.8 min  
 Routed to Pond DCB2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Max. Velocity= 2.14 fps, Min. Travel Time= 1.1 min  
 Avg. Velocity = 0.68 fps, Avg. Travel Time= 3.6 min

Peak Storage= 166 cf @ 12.12 hrs  
 Average Depth at Peak Storage= 0.30', Surface Width= 4.77'  
 Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 25.08 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight  
 Side Slope Z-value= 3.0 '/' Top Width= 9.00'  
 Length= 145.0' Slope= 0.0069 '/'  
 Inlet Invert= 172.00', Outlet Invert= 171.00'

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025



### **Summary for Reach 14R: Drainage Swale**

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 2.46" for 10-Year event  
Inflow = 1.92 cfs @ 12.10 hrs, Volume= 6,049 cf  
Outflow = 1.91 cfs @ 12.10 hrs, Volume= 6,046 cf, Atten= 0%, Lag= 0.4 min  
Routed to Pond DCB1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Max. Velocity= 2.05 fps, Min. Travel Time= 0.5 min  
Avg. Velocity = 0.61 fps, Avg. Travel Time= 1.8 min

Peak Storage= 61 cf @ 12.10 hrs  
Average Depth at Peak Storage= 0.25' , Surface Width= 4.49'  
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 26.49 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight  
Side Slope Z-value= 3.0 '/' Top Width= 9.00'  
Length= 65.0' Slope= 0.0077 '/'  
Inlet Invert= 174.00', Outlet Invert= 173.50'



### **Summary for Reach 19R: Drainage Swale**

Inflow Area = 19,540 sf, 0.00% Impervious, Inflow Depth > 1.97" for 10-Year event  
Inflow = 1.25 cfs @ 12.00 hrs, Volume= 3,210 cf  
Outflow = 1.18 cfs @ 12.02 hrs, Volume= 3,205 cf, Atten= 6%, Lag= 0.9 min  
Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Max. Velocity= 4.20 fps, Min. Travel Time= 1.3 min  
Avg. Velocity = 1.26 fps, Avg. Travel Time= 4.5 min

Peak Storage= 95 cf @ 12.02 hrs  
Average Depth at Peak Storage= 0.15' , Surface Width= 2.37'  
Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.44 cfs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

1.50' x 0.50' deep channel, n= 0.025 Earth, clean & winding  
 Side Slope Z-value= 3.0 '/' Top Width= 4.50'  
 Length= 340.0' Slope= 0.0882 '/'  
 Inlet Invert= 172.00', Outlet Invert= 142.00'



### Summary for Pond 11P: P.UIS1

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth > 3.34" for 10-Year event  
 Inflow = 1.39 cfs @ 12.09 hrs, Volume= 4,393 cf  
 Outflow = 0.27 cfs @ 11.83 hrs, Volume= 4,393 cf, Atten= 80%, Lag= 0.0 min  
 Discarded = 0.27 cfs @ 11.83 hrs, Volume= 4,393 cf  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf  
 Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 145.56' @ 12.52 hrs Surf.Area= 1,435 sf Storage= 1,090 cf

Plug-Flow detention time= 21.8 min calculated for 4,391 cf (100% of inflow)  
 Center-of-Mass det. time= 21.7 min ( 819.7 - 797.9 )

Volume	Invert	Avail.Storage	Storage Description
#1A	144.25'	2,065 cf	<b>22.75'W x 63.06'L x 5.50'H Field A</b> 7,890 cf Overall - 2,728 cf Embedded = 5,162 cf x 40.0% Voids
#2A	145.00'	2,728 cf	<b>ADS_StormTech MC-3500 d +Cap x 24 Inside #1</b> Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 24 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,793 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	144.25'	<b>8.270 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	148.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	146.00'	<b>12.0" Round Culvert</b> L= 13.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.00' / 145.80' S= 0.0154 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	146.25'	<b>12.0" Vert. Orifice/Grate</b>	C= 0.600 Limited to weir flow at low heads

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Discarded OutFlow** Max=0.27 cfs @ 11.83 hrs HW=144.31' (Free Discharge)

1=Exfiltration (Exfiltration Controls 0.27 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=144.25' TW=141.83' (Dynamic Tailwater)

3=Culvert (Controls 0.00 cfs)

2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

4=Orifice/Grate (Controls 0.00 cfs)

**Summary for Pond 12P: P.UIS2**

Inflow Area = 22,495 sf, 83.93% Impervious, Inflow Depth > 3.95" for 10-Year event  
 Inflow = 2.16 cfs @ 12.08 hrs, Volume= 7,399 cf  
 Outflow = 0.73 cfs @ 12.36 hrs, Volume= 6,059 cf, Atten= 66%, Lag= 16.8 min  
 Discarded = 0.07 cfs @ 9.95 hrs, Volume= 4,463 cf  
 Primary = 0.65 cfs @ 12.36 hrs, Volume= 1,596 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 143.62' @ 12.36 hrs Surf.Area= 1,271 sf Storage= 2,736 cf

Plug-Flow detention time= 182.6 min calculated for 6,059 cf (82% of inflow)  
 Center-of-Mass det. time= 109.9 min ( 872.1 - 762.2 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	1,838 cf	<b>22.75'W x 55.89'L x 5.50'H Field A</b> 6,993 cf Overall - 2,398 cf Embedded = 4,595 cf x 40.0% Voids
#2A	141.25'	2,398 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 21 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 21 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,236 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	139.50'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.50' / 139.40' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	143.25'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads	

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Discarded OutFlow** Max=0.07 cfs @ 9.95 hrs HW=140.56' (Free Discharge)↑  
1=Exfiltration (Exfiltration Controls 0.07 cfs)**Primary OutFlow** Max=0.65 cfs @ 12.36 hrs HW=143.62' TW=139.69' (Dynamic Tailwater)↑  
3=Culvert (Passes 0.65 cfs of 5.68 cfs potential flow)  
└─2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)  
└─4=Orifice/Grate (Orifice Controls 0.65 cfs @ 2.08 fps)

### Summary for Pond 13P: P.UIS3

Inflow Area = 22,985 sf, 76.88% Impervious, Inflow Depth > 3.72" for 10-Year event  
 Inflow = 2.19 cfs @ 12.08 hrs, Volume= 7,128 cf  
 Outflow = 0.11 cfs @ 11.16 hrs, Volume= 5,977 cf, Atten= 95%, Lag= 0.0 min  
 Discarded = 0.11 cfs @ 11.16 hrs, Volume= 5,977 cf  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 143.05' @ 14.40 hrs Surf.Area= 1,924 sf Storage= 3,379 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 187.1 min ( 970.2 - 783.1 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	2,746 cf	<b>22.75'W x 84.57'L x 5.50'H Field A</b> 10,582 cf Overall - 3,718 cf Embedded = 6,864 cf x 40.0% Voids
#2A	141.25'	3,718 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 33 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 33 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
6,463 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	141.00'	<b>12.0" Round Culvert</b> L= 31.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.00' / 139.90' S= 0.0355 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#4	Device 3	143.45'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Discarded OutFlow** Max=0.11 cfs @ 11.16 hrs HW=140.56' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.11 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=140.50' TW=139.00' (Dynamic Tailwater)

↑ 3=Culvert (Controls 0.00 cfs)

2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

4=Orifice/Grate (Controls 0.00 cfs)

**Summary for Pond 14P: P.UIS4**

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 3.59" for 10-Year event  
 Inflow = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf  
 Outflow = 0.21 cfs @ 12.23 hrs, Volume= 1,354 cf, Atten= 51%, Lag= 9.0 min  
 Discarded = 0.07 cfs @ 11.72 hrs, Volume= 1,256 cf  
 Primary = 0.14 cfs @ 12.23 hrs, Volume= 98 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 141.15' @ 12.23 hrs Surf.Area= 364 sf Storage= 285 cf

Plug-Flow detention time= 20.5 min calculated for 1,354 cf (100% of inflow)  
 Center-of-Mass det. time= 20.4 min ( 809.4 - 789.0 )

Volume	Invert	Avail.Storage	Storage Description
#1A	139.80'	269 cf	<b>14.83'W x 24.56'L x 2.33'H Field A</b> 850 cf Overall - 177 cf Embedded = 673 cf x 40.0% Voids
#2A	140.30'	177 cf	<b>ADS_StormTech SC-310 +Cap</b> x 12 Inside #1 Effective Size= 28.9"W x 16.0"H => 2.07 sf x 7.12'L = 14.7 cf Overall Size= 34.0"W x 16.0"H x 7.56'L with 0.44' Overlap 12 Chambers in 4 Rows
446 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	139.80'	<b>8.270 in/hr Exfiltration over Surface area</b> Phase-In= 0.01'
#2	Device 3	141.10'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	140.45'	<b>12.0" Round Culvert</b> L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.45' / 140.20' S= 0.0147 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Discarded OutFlow** Max=0.07 cfs @ 11.72 hrs HW=139.83' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.07 cfs)

**Primary OutFlow** Max=0.14 cfs @ 12.23 hrs HW=141.15' TW=0.00' (Dynamic Tailwater)

↑ 3=Culvert (Passes 0.14 cfs of 1.31 cfs potential flow)

2=Sharp-Crested Rectangular Weir (Weir Controls 0.14 cfs @ 0.72 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Pond 29P: CB6**

Inflow Area = 7,005 sf, 0.00% Impervious, Inflow Depth > 1.89" for 10-Year event  
 Inflow = 0.35 cfs @ 12.09 hrs, Volume= 1,104 cf  
 Outflow = 0.35 cfs @ 12.09 hrs, Volume= 1,104 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.35 cfs @ 12.09 hrs, Volume= 1,104 cf  
 Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 150.43' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	150.10'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 150.10' / 150.00' S= 0.0250 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.35 cfs @ 12.09 hrs HW=150.43' TW=147.47' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.35 cfs @ 1.55 fps)

**Summary for Pond AD1: AD1**

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth > 3.09" for 10-Year event  
 Inflow = 0.06 cfs @ 12.09 hrs, Volume= 189 cf  
 Outflow = 0.06 cfs @ 12.09 hrs, Volume= 189 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.06 cfs @ 12.09 hrs, Volume= 189 cf  
 Routed to Pond DMH13 : DMH13

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 160.93' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.80'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.80' / 160.70' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.06 cfs @ 12.09 hrs HW=160.93' TW=160.83' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.06 cfs @ 1.46 fps)

**Summary for Pond AD2: AD2**

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth > 2.54" for 10-Year event  
 Inflow = 0.12 cfs @ 12.09 hrs, Volume= 384 cf  
 Outflow = 0.12 cfs @ 12.09 hrs, Volume= 384 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.12 cfs @ 12.09 hrs, Volume= 384 cf  
 Routed to Pond DMH6 : DMH6

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

Peak Elev= 160.19' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.00'	<b>12.0" Round Culvert</b> L= 12.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.00' / 159.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.12 cfs @ 12.09 hrs HW=160.19' TW=159.94' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.12 cfs @ 1.18 fps)

### Summary for Pond AD3: AD3

Inflow Area = 600 sf, 37.50% Impervious, Inflow Depth > 2.81" for 10-Year event  
 Inflow = 0.05 cfs @ 12.09 hrs, Volume= 141 cf  
 Outflow = 0.05 cfs @ 12.09 hrs, Volume= 141 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.05 cfs @ 12.09 hrs, Volume= 141 cf  
 Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 159.67' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.55'	<b>12.0" Round Culvert</b> L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.55' / 159.45' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.05 cfs @ 12.09 hrs HW=159.67' TW=159.58' (Dynamic Tailwater)  
 ↑ 1=Culvert (Outlet Controls 0.05 cfs @ 1.27 fps)

### Summary for Pond AD4: AD4

Inflow Area = 2,595 sf, 42.39% Impervious, Inflow Depth > 2.90" for 10-Year event  
 Inflow = 0.20 cfs @ 12.09 hrs, Volume= 628 cf  
 Outflow = 0.20 cfs @ 12.09 hrs, Volume= 628 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.20 cfs @ 12.09 hrs, Volume= 628 cf  
 Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 158.20' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	157.95'	<b>12.0" Round Culvert</b> L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.95' / 157.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.20 cfs @ 12.09 hrs HW=158.20' TW=148.44' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.20 cfs @ 1.34 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Pond AD5: AD5**

Inflow Area = 1,625 sf, 92.92% Impervious, Inflow Depth > 4.13" for 10-Year event  
 Inflow = 0.16 cfs @ 12.08 hrs, Volume= 560 cf  
 Outflow = 0.16 cfs @ 12.08 hrs, Volume= 560 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.16 cfs @ 12.08 hrs, Volume= 560 cf  
 Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 147.43' @ 12.08 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.20'	<b>12.0" Round Culvert</b> L= 11.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.20' / 147.10' S= 0.0091 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.16 cfs @ 12.08 hrs HW=147.42' TW=147.26' (Dynamic Tailwater)  
 ↑1=Culvert (Barrel Controls 0.16 cfs @ 1.88 fps)

**Summary for Pond CB1:**

Inflow Area = 10,045 sf, 54.75% Impervious, Inflow Depth > 3.19" for 10-Year event  
 Inflow = 0.85 cfs @ 12.09 hrs, Volume= 2,669 cf  
 Outflow = 0.85 cfs @ 12.09 hrs, Volume= 2,669 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.85 cfs @ 12.09 hrs, Volume= 2,669 cf  
 Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 147.29' @ 12.09 hrs  
 Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.85 cfs @ 12.09 hrs HW=147.29' TW=145.96' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.85 cfs @ 1.97 fps)

**Summary for Pond CB2:**

Inflow Area = 5,760 sf, 69.18% Impervious, Inflow Depth > 3.59" for 10-Year event  
 Inflow = 0.54 cfs @ 12.08 hrs, Volume= 1,724 cf  
 Outflow = 0.54 cfs @ 12.08 hrs, Volume= 1,724 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.54 cfs @ 12.08 hrs, Volume= 1,724 cf  
 Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

Peak Elev= 147.17' @ 12.08 hrs

Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.54 cfs @ 12.08 hrs HW=147.17' TW=145.96' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.54 cfs @ 1.73 fps)

**Summary for Pond CB3:**

Inflow Area = 13,605 sf, 72.80% Impervious, Inflow Depth &gt; 3.59" for 10-Year event

Inflow = 1.27 cfs @ 12.08 hrs, Volume= 4,072 cf

Outflow = 1.27 cfs @ 12.08 hrs, Volume= 4,072 cf, Atten= 0%, Lag= 0.0 min

Primary = 1.27 cfs @ 12.08 hrs, Volume= 4,072 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 144.55' @ 12.08 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=1.26 cfs @ 12.08 hrs HW=144.54' TW=142.39' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 1.26 cfs @ 3.62 fps)

**Summary for Pond CB4:**

Inflow Area = 9,380 sf, 82.78% Impervious, Inflow Depth &gt; 3.91" for 10-Year event

Inflow = 0.92 cfs @ 12.08 hrs, Volume= 3,057 cf

Outflow = 0.92 cfs @ 12.08 hrs, Volume= 3,057 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.92 cfs @ 12.08 hrs, Volume= 3,057 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 144.12' @ 12.08 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 6.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0167 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Primary OutFlow** Max=0.92 cfs @ 12.08 hrs HW=144.12' TW=142.39' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 0.92 cfs @ 2.64 fps)

### Summary for Pond CB5:

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 3.59" for 10-Year event  
 Inflow = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf  
 Outflow = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf  
 Routed to Pond DMH5 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 141.31' @ 12.22 hrs  
 Flood Elev= 143.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.60'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.60' / 140.50' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.42 cfs @ 12.08 hrs HW=141.28' TW=140.97' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 0.42 cfs @ 2.13 fps)

### Summary for Pond DCB1:

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 2.46" for 10-Year event  
 Inflow = 1.91 cfs @ 12.10 hrs, Volume= 6,046 cf  
 Outflow = 1.91 cfs @ 12.10 hrs, Volume= 6,046 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.91 cfs @ 12.10 hrs, Volume= 6,046 cf  
 Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 158.10' @ 12.10 hrs  
 Flood Elev= 173.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	157.20'	<b>12.0" Round Culvert</b> L= 131.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.20' / 150.00' S= 0.0550 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.91 cfs @ 12.10 hrs HW=158.10' TW=147.47' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 1.91 cfs @ 2.56 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Pond DCB2:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 2.12" for 10-Year event  
 Inflow = 2.45 cfs @ 12.12 hrs, Volume= 8,010 cf  
 Outflow = 2.45 cfs @ 12.12 hrs, Volume= 8,010 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.45 cfs @ 12.12 hrs, Volume= 8,010 cf  
 Routed to Pond DMH9 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 153.28' @ 12.12 hrs

Flood Elev= 172.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	152.10'	<b>12.0" Round Culvert</b> L= 78.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 152.10' / 148.60' S= 0.0449 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.45 cfs @ 12.12 hrs HW=153.27' TW=143.55' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 2.45 cfs @ 3.12 fps)

**Summary for Pond DMH1:**

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth > 3.34" for 10-Year event  
 Inflow = 1.39 cfs @ 12.09 hrs, Volume= 4,393 cf  
 Outflow = 1.39 cfs @ 12.09 hrs, Volume= 4,393 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.39 cfs @ 12.09 hrs, Volume= 4,393 cf  
 Routed to Pond 11P : P.UIS1

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 145.96' @ 12.09 hrs

Flood Elev= 150.55'

Device	Routing	Invert	Outlet Devices
#1	Primary	145.20'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 145.20' / 145.11' S= 0.0225 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.38 cfs @ 12.09 hrs HW=145.96' TW=145.05' (Dynamic Tailwater)

↑ 1=Culvert (Barrel Controls 1.38 cfs @ 3.00 fps)

**Summary for Pond DMH10:**

Inflow Area = 36,545 sf, 15.60% Impervious, Inflow Depth > 2.35" for 10-Year event  
 Inflow = 2.26 cfs @ 12.10 hrs, Volume= 7,150 cf  
 Outflow = 2.26 cfs @ 12.10 hrs, Volume= 7,150 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.26 cfs @ 12.10 hrs, Volume= 7,150 cf  
 Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

Peak Elev= 147.47' @ 12.10 hrs

Flood Elev= 154.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.40'	<b>12.0" Round Culvert</b> L= 43.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.40' / 145.80' S= 0.0140 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.26 cfs @ 12.10 hrs HW=147.47' TW=142.62' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 2.26 cfs @ 2.88 fps)

**Summary for Pond DMH11:**

Inflow Area = 52,350 sf, 29.01% Impervious, Inflow Depth &gt; 1.64" for 10-Year event

Inflow = 2.26 cfs @ 12.10 hrs, Volume= 7,150 cf

Outflow = 2.26 cfs @ 12.10 hrs, Volume= 7,150 cf, Atten= 0%, Lag= 0.0 min

Primary = 2.26 cfs @ 12.10 hrs, Volume= 7,150 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 142.62' @ 12.10 hrs

Flood Elev= 152.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.83'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.83' / 141.50' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=2.26 cfs @ 12.10 hrs HW=142.62' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 2.26 cfs @ 2.39 fps)

**Summary for Pond DMH12: DMH12**

Inflow Area = 2,360 sf, 79.87% Impervious, Inflow Depth &gt; 3.81" for 10-Year event

Inflow = 0.23 cfs @ 12.08 hrs, Volume= 749 cf

Outflow = 0.23 cfs @ 12.08 hrs, Volume= 749 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.23 cfs @ 12.08 hrs, Volume= 749 cf

Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.26' @ 12.08 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.00'	<b>12.0" Round Culvert</b> L= 208.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.00' / 142.35' S= 0.0224 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Primary OutFlow** Max=0.22 cfs @ 12.08 hrs HW=147.26' TW=143.11' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.22 cfs @ 1.37 fps)

### Summary for Pond DMH13: DMH13

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth > 3.09" for 10-Year event  
 Inflow = 0.06 cfs @ 12.09 hrs, Volume= 189 cf  
 Outflow = 0.06 cfs @ 12.09 hrs, Volume= 189 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.06 cfs @ 12.09 hrs, Volume= 189 cf  
 Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 160.83' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.70'	<b>12.0" Round Culvert</b> L= 100.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.70' / 147.10' S= 0.1360 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.06 cfs @ 12.09 hrs HW=160.83' TW=147.26' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.06 cfs @ 0.98 fps)

### Summary for Pond DMH2:

Inflow Area = 22,495 sf, 83.93% Impervious, Inflow Depth > 3.95" for 10-Year event  
 Inflow = 2.16 cfs @ 12.08 hrs, Volume= 7,399 cf  
 Outflow = 2.16 cfs @ 12.08 hrs, Volume= 7,399 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.16 cfs @ 12.08 hrs, Volume= 7,399 cf  
 Routed to Pond 12P : P.UIS2

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 143.69' @ 12.34 hrs  
 Flood Elev= 150.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.45'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.45' / 141.36' S= 0.0180 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.99 cfs @ 12.08 hrs HW=143.11' TW=142.66' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 1.99 cfs @ 2.54 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Pond DMH3:**

Inflow Area = 90,755 sf, 42.01% Impervious, Inflow Depth > 1.27" for 10-Year event  
 Inflow = 2.45 cfs @ 12.12 hrs, Volume= 9,606 cf  
 Outflow = 2.45 cfs @ 12.12 hrs, Volume= 9,606 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.45 cfs @ 12.12 hrs, Volume= 9,606 cf  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 139.83' @ 12.12 hrs

Flood Elev= 149.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	139.00'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.00' / 138.50' S= 0.0152 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=2.45 cfs @ 12.12 hrs HW=139.83' TW=0.00' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 2.45 cfs @ 2.45 fps)

**Summary for Pond DMH4:**

Inflow Area = 22,985 sf, 76.88% Impervious, Inflow Depth > 3.72" for 10-Year event  
 Inflow = 2.19 cfs @ 12.08 hrs, Volume= 7,128 cf  
 Outflow = 2.19 cfs @ 12.08 hrs, Volume= 7,128 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.19 cfs @ 12.08 hrs, Volume= 7,128 cf  
 Routed to Pond 13P : P.UIS3

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 143.05' @ 14.40 hrs

Flood Elev= 146.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.35'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.35' / 141.25' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.19 cfs @ 12.08 hrs HW=142.39' TW=141.83' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 2.19 cfs @ 2.78 fps)

**Summary for Pond DMH5:**

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 3.59" for 10-Year event  
 Inflow = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf  
 Outflow = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.42 cfs @ 12.08 hrs, Volume= 1,354 cf  
 Routed to Pond 14P : P.UIS4

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

Peak Elev= 141.23' @ 12.22 hrs

Flood Elev= 143.90'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.40'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.40' / 140.30' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.41 cfs @ 12.08 hrs HW=140.97' TW=140.67' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.41 cfs @ 2.07 fps)

### Summary for Pond DMH6: DMH6

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth > 2.54" for 10-Year event  
 Inflow = 0.12 cfs @ 12.09 hrs, Volume= 384 cf  
 Outflow = 0.12 cfs @ 12.09 hrs, Volume= 384 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.12 cfs @ 12.09 hrs, Volume= 384 cf  
 Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 159.94' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.75'	<b>12.0" Round Culvert</b> L= 29.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.75' / 159.45' S= 0.0103 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.12 cfs @ 12.09 hrs HW=159.94' TW=159.58' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.12 cfs @ 1.18 fps)

### Summary for Pond DMH7: DMH7

Inflow Area = 2,410 sf, 31.74% Impervious, Inflow Depth > 2.61" for 10-Year event  
 Inflow = 0.17 cfs @ 12.09 hrs, Volume= 524 cf  
 Outflow = 0.17 cfs @ 12.09 hrs, Volume= 524 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.17 cfs @ 12.09 hrs, Volume= 524 cf  
 Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 159.58' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.35'	<b>12.0" Round Culvert</b> L= 147.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.35' / 157.85' S= 0.0102 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.17 cfs @ 12.09 hrs HW=159.58' TW=148.44' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.17 cfs @ 1.28 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=4.60"

Printed 10/14/2025

**Summary for Pond DMH8: DMH8**

Inflow Area = 5,005 sf, 37.26% Impervious, Inflow Depth > 2.76" for 10-Year event  
 Inflow = 0.37 cfs @ 12.09 hrs, Volume= 1,152 cf  
 Outflow = 0.37 cfs @ 12.09 hrs, Volume= 1,152 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.37 cfs @ 12.09 hrs, Volume= 1,152 cf  
 Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 148.44' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	148.10'	<b>12.0" Round Culvert</b> L= 72.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 148.10' / 142.35' S= 0.0799 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.37 cfs @ 12.09 hrs HW=148.44' TW=143.13' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.37 cfs @ 1.57 fps)

**Summary for Pond DMH9:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 2.12" for 10-Year event  
 Inflow = 2.45 cfs @ 12.12 hrs, Volume= 8,010 cf  
 Outflow = 2.45 cfs @ 12.12 hrs, Volume= 8,010 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.45 cfs @ 12.12 hrs, Volume= 8,010 cf  
 Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 143.56' @ 12.12 hrs  
 Flood Elev= 154.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	142.38'	<b>12.0" Round Culvert</b> L= 55.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 142.38' / 139.90' S= 0.0451 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.45 cfs @ 12.12 hrs HW=143.55' TW=139.83' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 2.45 cfs @ 3.12 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Subcatchment 10S: Overland to Wetlands**

Runoff = 1.83 cfs @ 12.09 hrs, Volume= 5,691 cf, Depth> 2.76"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
17,430	70	Woods, Good, HSG C
6,325	74	>75% Grass cover, Good, HSG C
1,000	61	>75% Grass cover, Good, HSG B
24,755	71	Weighted Average
24,755		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	50	0.1700	0.16		<b>Sheet Flow, Sheet Flow</b> Woods: Light underbrush n= 0.400 P2= 3.15"
0.2	20	0.1400	1.87		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
0.5	45	0.0560	1.66		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.0	115				Total

**Summary for Subcatchment 11S: Overland to CB1**

Runoff = 1.15 cfs @ 12.09 hrs, Volume= 3,642 cf, Depth> 4.35"  
 Routed to Pond CB1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
5,500	98	Paved parking, HSG C
4,545	74	>75% Grass cover, Good, HSG C
10,045	87	Weighted Average
4,545		45.25% Pervious Area
5,500		54.75% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Subcatchment 12S: Overland to CB2**

Runoff = 0.70 cfs @ 12.08 hrs, Volume= 2,298 cf, Depth> 4.79"  
 Routed to Pond CB2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
*	3,545	Paved parking, HSG C
	440	Retaining Wall, HSG C
	1,775	>75% Grass cover, Good, HSG C
5,760	91	Weighted Average
1,775		30.82% Pervious Area
3,985		69.18% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		Direct Entry,

**Summary for Subcatchment 13S: Overland to CB3**

Runoff = 1.66 cfs @ 12.08 hrs, Volume= 5,427 cf, Depth> 4.79"  
 Routed to Pond CB3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
*	9,580	Paved parking, HSG C
	325	Retaining Wall, HSG C
	3,700	>75% Grass cover, Good, HSG C
13,605	91	Weighted Average
3,700		27.20% Pervious Area
9,905		72.80% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		Direct Entry,

**Summary for Subcatchment 14S: Overland to CB4**

Runoff = 1.19 cfs @ 12.08 hrs, Volume= 4,005 cf, Depth> 5.12"  
 Routed to Pond CB4 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Area (sf)	CN	Description			
7,175	98	Paved parking, HSG C			
*	590	Retaining Wall, HSG C			
1,615	74	>75% Grass cover, Good, HSG C			
9,380	94	Weighted Average			
1,615		17.22% Pervious Area			
7,765		82.78% Impervious Area			
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 15S: Overland to CB5**

Runoff = 0.55 cfs @ 12.08 hrs, Volume= 1,805 cf, Depth> 4.79"  
 Routed to Pond CB5 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description			
2,985	98	Paved parking, HSG C			
*	225	Retaining Wall, HSG C			
1,315	74	>75% Grass cover, Good, HSG C			
4,525	91	Weighted Average			
1,315		29.06% Pervious Area			
3,210		70.94% Impervious Area			
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 17S: Overland to Street Drainage**

Runoff = 0.08 cfs @ 12.08 hrs, Volume= 270 cf, Depth> 5.59"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description			
580	98	Paved parking, HSG C			
580		100.00% Impervious Area			
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Subcatchment 18S: Overland to Drainage Swale**

Runoff = 1.90 cfs @ 12.00 hrs, Volume= 4,801 cf, Depth> 2.95"  
 Routed to Reach 19R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
4,935	70	Woods, Good, HSG C
14,605	74	>75% Grass cover, Good, HSG C
19,540	73	Weighted Average
19,540		100.00% Pervious Area

**Summary for Subcatchment 20S: Roof**

Runoff = 1.98 cfs @ 12.08 hrs, Volume= 7,045 cf, Depth> 5.59"  
 Routed to Pond DMH2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
15,130	98	Roofs, HSG C
15,130		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 21S: Overland to Rear of Building**

Runoff = 3.68 cfs @ 12.10 hrs, Volume= 11,822 cf, Depth> 3.13"  
 Routed to Reach 13R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
40,790	74	>75% Grass cover, Good, HSG C
2,910	70	Woods, Good, HSG C
1,575	98	Roofs, HSG C
45,275	75	Weighted Average
43,700		96.52% Pervious Area
1,575		3.48% Impervious Area

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
7.1	380	Total			

**Summary for Subcatchment 22S: Overland to Rear of Building**

Runoff = 2.74 cfs @ 12.10 hrs, Volume= 8,675 cf, Depth> 3.52"  
Routed to Reach 14R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
23,415	74	>75% Grass cover, Good, HSG C
425	70	Woods, Good, HSG C
2,380	98	Roofs, HSG C
3,320	98	Paved parking, HSG C
29,540	79	Weighted Average
23,840		80.70% Pervious Area
5,700		19.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
1.9	180	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.0200	2.87		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Paved Kv= 20.3 fps
0.8	110	0.1000	2.21		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.6	370	Total			

**Summary for Subcatchment 23S: Overland to AD5**

Runoff = 0.21 cfs @ 12.08 hrs, Volume= 725 cf, Depth> 5.35"  
Routed to Pond AD5 : AD5

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 25-Year Rainfall=5.83"

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Area (sf)	CN	Description
1,335	98	Paved parking, HSG C
*		
175	98	Unconnected pavement, HSG C- ret. walls
115	74	>75% Grass cover, Good, HSG C
1,625	96	Weighted Average
115		7.08% Pervious Area
1,510		92.92% Impervious Area
175		11.59% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(cfs)	

6.0 **Direct Entry,****Summary for Subcatchment 24S: Overland to AD1**

Runoff = 0.08 cfs @ 12.09 hrs, Volume= 260 cf, Depth> 4.24"  
 Routed to Pond AD1 : AD1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
260	98	Paved parking, HSG C
*		
115	98	Unconnected pavement, HSG C-ret walls
360	74	>75% Grass cover, Good, HSG C
735	86	Weighted Average
360		48.98% Pervious Area
375		51.02% Impervious Area
115		30.67% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(cfs)	

6.0 **Direct Entry,****Summary for Subcatchment 25S: Overland to AD2**

Runoff = 0.18 cfs @ 12.09 hrs, Volume= 547 cf, Depth> 3.62"  
 Routed to Pond AD2 : AD2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Adj	Description
360	98		Paved parking, HSG C
180	98		Unconnected pavement, HSG C
1,270	74		>75% Grass cover, Good, HSG C
1,810	81	80	Weighted Average, UI Adjusted
1,270			70.17% Pervious Area
540			29.83% Impervious Area
180			33.33% Unconnected

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 26S: Overland to AD3**

Runoff = 0.06 cfs @ 12.09 hrs, Volume= 196 cf, Depth> 3.93"  
 Routed to Pond AD3 : AD3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
185	98	Paved parking, HSG C
*	40	Unconnected pavement, HSG C-ret. walls
	375	>75% Grass cover, Good, HSG C
	600	Weighted Average
375		62.50% Pervious Area
225		37.50% Impervious Area
40		17.78% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 27S: Overland to AD4**

Runoff = 0.28 cfs @ 12.09 hrs, Volume= 872 cf, Depth> 4.03"  
 Routed to Pond AD4 : AD4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
775	98	Paved parking, HSG C
*	325	Unconnected pavement, HSG C-ret. walls
	1,495	>75% Grass cover, Good, HSG C
	2,595	Weighted Average
1,495		57.61% Pervious Area
1,100		42.39% Impervious Area
325		29.55% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Subcatchment 28S: Overland to CB6**

Runoff = 0.54 cfs @ 12.09 hrs, Volume= 1,664 cf, Depth> 2.85"  
 Routed to Pond 29P : CB6

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 25-Year Rainfall=5.83"

Area (sf)	CN	Description
2,630	70	Woods, Good, HSG C
4,375	74	>75% Grass cover, Good, HSG C
7,005	72	Weighted Average
7,005		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Reach 10R: Wetlands System - Peppermint Brook**

Inflow Area = 192,505 sf, 29.66% Impervious, Inflow Depth > 2.34" for 25-Year event  
 Inflow = 10.95 cfs @ 12.11 hrs, Volume= 37,505 cf  
 Outflow = 10.95 cfs @ 12.11 hrs, Volume= 37,505 cf, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**Summary for Reach 13R: Drainage Swale**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 3.13" for 25-Year event  
 Inflow = 3.68 cfs @ 12.10 hrs, Volume= 11,822 cf  
 Outflow = 3.65 cfs @ 12.12 hrs, Volume= 11,809 cf, Atten= 1%, Lag= 0.7 min  
 Routed to Pond DCB2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Max. Velocity= 2.42 fps, Min. Travel Time= 1.0 min  
 Avg. Velocity = 0.75 fps, Avg. Travel Time= 3.2 min

Peak Storage= 219 cf @ 12.12 hrs  
 Average Depth at Peak Storage= 0.37' , Surface Width= 5.20'  
 Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 25.08 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight  
 Side Slope Z-value= 3.0 '/' Top Width= 9.00'  
 Length= 145.0' Slope= 0.0069 '/'  
 Inlet Invert= 172.00', Outlet Invert= 171.00'

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025



### **Summary for Reach 14R: Drainage Swale**

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 3.52" for 25-Year event  
Inflow = 2.74 cfs @ 12.10 hrs, Volume= 8,675 cf  
Outflow = 2.74 cfs @ 12.10 hrs, Volume= 8,670 cf, Atten= 0%, Lag= 0.4 min  
Routed to Pond DCB1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Max. Velocity= 2.30 fps, Min. Travel Time= 0.5 min  
Avg. Velocity = 0.68 fps, Avg. Travel Time= 1.6 min

Peak Storage= 77 cf @ 12.10 hrs  
Average Depth at Peak Storage= 0.30' , Surface Width= 4.83'  
Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 26.49 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight  
Side Slope Z-value= 3.0 '/' Top Width= 9.00'  
Length= 65.0' Slope= 0.0077 '/'  
Inlet Invert= 174.00', Outlet Invert= 173.50'



### **Summary for Reach 19R: Drainage Swale**

Inflow Area = 19,540 sf, 0.00% Impervious, Inflow Depth > 2.95" for 25-Year event  
Inflow = 1.90 cfs @ 12.00 hrs, Volume= 4,801 cf  
Outflow = 1.80 cfs @ 12.01 hrs, Volume= 4,794 cf, Atten= 5%, Lag= 0.8 min  
Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Max. Velocity= 4.78 fps, Min. Travel Time= 1.2 min  
Avg. Velocity = 1.41 fps, Avg. Travel Time= 4.0 min

Peak Storage= 128 cf @ 12.01 hrs  
Average Depth at Peak Storage= 0.18' , Surface Width= 2.60'  
Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.44 cfs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

1.50' x 0.50' deep channel, n= 0.025 Earth, clean & winding  
 Side Slope Z-value= 3.0 '/' Top Width= 4.50'  
 Length= 340.0' Slope= 0.0882 '/'  
 Inlet Invert= 172.00', Outlet Invert= 142.00'



‡

### Summary for Pond 11P: P.UIS1

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth > 4.51" for 25-Year event  
 Inflow = 1.85 cfs @ 12.09 hrs, Volume= 5,939 cf  
 Outflow = 0.27 cfs @ 11.74 hrs, Volume= 5,939 cf, Atten= 85%, Lag= 0.0 min  
 Discarded = 0.27 cfs @ 11.74 hrs, Volume= 5,939 cf  
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf  
 Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 146.12' @ 12.58 hrs Surf.Area= 1,435 sf Storage= 1,744 cf

Plug-Flow detention time= 39.1 min calculated for 5,939 cf (100% of inflow)  
 Center-of-Mass det. time= 39.0 min ( 828.8 - 789.7 )

Volume	Invert	Avail.Storage	Storage Description
#1A	144.25'	2,065 cf	<b>22.75'W x 63.06'L x 5.50'H Field A</b> 7,890 cf Overall - 2,728 cf Embedded = 5,162 cf x 40.0% Voids
#2A	145.00'	2,728 cf	<b>ADS_StormTech MC-3500 d +Cap x 24 Inside #1</b> Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 24 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,793 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	144.25'	<b>8.270 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	148.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	146.00'	<b>12.0" Round Culvert</b> L= 13.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.00' / 145.80' S= 0.0154 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	146.25'	<b>12.0" Vert. Orifice/Grate</b>	C= 0.600 Limited to weir flow at low heads

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Discarded OutFlow** Max=0.27 cfs @ 11.74 hrs HW=144.31' (Free Discharge)

1=Exfiltration (Exfiltration Controls 0.27 cfs)

**Primary OutFlow** Max=0.00 cfs @ 0.00 hrs HW=144.25' TW=141.83' (Dynamic Tailwater)

3=Culvert (Controls 0.00 cfs)

2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

4=Orifice/Grate (Controls 0.00 cfs)

**Summary for Pond 12P: P.UIS2**

Inflow Area = 22,495 sf, 83.93% Impervious, Inflow Depth > 5.15" for 25-Year event  
 Inflow = 2.79 cfs @ 12.08 hrs, Volume= 9,645 cf  
 Outflow = 1.45 cfs @ 12.22 hrs, Volume= 8,041 cf, Atten= 48%, Lag= 8.0 min  
 Discarded = 0.07 cfs @ 9.13 hrs, Volume= 4,703 cf  
 Primary = 1.38 cfs @ 12.22 hrs, Volume= 3,338 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 144.03' @ 12.22 hrs Surf.Area= 1,271 sf Storage= 3,084 cf

Plug-Flow detention time= 145.1 min calculated for 8,041 cf (83% of inflow)  
 Center-of-Mass det. time= 75.9 min ( 833.9 - 758.0 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	1,838 cf	<b>22.75'W x 55.89'L x 5.50'H Field A</b> 6,993 cf Overall - 2,398 cf Embedded = 4,595 cf x 40.0% Voids
#2A	141.25'	2,398 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 21 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 21 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,236 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	139.50'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.50' / 139.40' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	143.25'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads	

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Discarded OutFlow** Max=0.07 cfs @ 9.13 hrs HW=140.56' (Free Discharge)↑  
1=Exfiltration (Exfiltration Controls 0.07 cfs)**Primary OutFlow** Max=1.38 cfs @ 12.22 hrs HW=144.03' TW=140.09' (Dynamic Tailwater)↑  
3=Culvert (Passes 1.38 cfs of 5.93 cfs potential flow)  
└─2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)  
└─4=Orifice/Grate (Orifice Controls 1.38 cfs @ 3.51 fps)

### Summary for Pond 13P: P.UIS3

Inflow Area =	22,985 sf, 76.88% Impervious, Inflow Depth > 4.92"	for 25-Year event
Inflow =	2.85 cfs @ 12.08 hrs, Volume=	9,432 cf
Outflow =	0.33 cfs @ 12.70 hrs, Volume=	7,296 cf, Atten= 88%, Lag= 37.1 min
Discarded =	0.11 cfs @ 10.51 hrs, Volume=	6,320 cf
Primary =	0.22 cfs @ 12.70 hrs, Volume=	976 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 143.65' @ 12.70 hrs Surf.Area= 1,924 sf Storage= 4,217 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 148.8 min ( 924.8 - 776.0 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	2,746 cf	<b>22.75'W x 84.57'L x 5.50'H Field A</b> 10,582 cf Overall - 3,718 cf Embedded = 6,864 cf x 40.0% Voids
#2A	141.25'	3,718 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 33 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 33 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
6,463 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	141.00'	<b>12.0" Round Culvert</b> L= 31.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.00' / 139.90' S= 0.0355 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#4	Device 3	143.45'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Discarded OutFlow** Max=0.11 cfs @ 10.51 hrs HW=140.56' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.11 cfs)

**Primary OutFlow** Max=0.22 cfs @ 12.70 hrs HW=143.65' TW=139.54' (Dynamic Tailwater)

↑ 3=Culvert (Passes 0.22 cfs of 4.38 cfs potential flow)

2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

4=Orifice/Grate (Orifice Controls 0.22 cfs @ 1.52 fps)

**Summary for Pond 14P: P.UIS4**

Inflow Area =	4,525 sf, 70.94% Impervious, Inflow Depth > 4.79"	for 25-Year event
Inflow =	0.55 cfs @ 12.08 hrs, Volume=	1,805 cf
Outflow =	0.49 cfs @ 12.13 hrs, Volume=	1,805 cf, Atten= 11%, Lag= 2.6 min
Discarded =	0.07 cfs @ 11.66 hrs, Volume=	1,513 cf
Primary =	0.42 cfs @ 12.13 hrs, Volume=	291 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 141.20' @ 12.13 hrs Surf.Area= 364 sf Storage= 297 cf

Plug-Flow detention time= 18.9 min calculated for 1,804 cf (100% of inflow)

Center-of-Mass det. time= 18.9 min ( 800.2 - 781.3 )

Volume	Invert	Avail.Storage	Storage Description
#1A	139.80'	269 cf	<b>14.83'W x 24.56'L x 2.33'H Field A</b> 850 cf Overall - 177 cf Embedded = 673 cf x 40.0% Voids
#2A	140.30'	177 cf	<b>ADS_StormTech SC-310 +Cap</b> x 12 Inside #1 Effective Size= 28.9"W x 16.0"H => 2.07 sf x 7.12'L = 14.7 cf Overall Size= 34.0"W x 16.0"H x 7.56'L with 0.44' Overlap 12 Chambers in 4 Rows
446 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	139.80'	<b>8.270 in/hr Exfiltration over Surface area</b> Phase-In= 0.01'
#2	Device 3	141.10'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	140.45'	<b>12.0" Round Culvert</b> L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.45' / 140.20' S= 0.0147 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Discarded OutFlow** Max=0.07 cfs @ 11.66 hrs HW=139.83' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.07 cfs)

**Primary OutFlow** Max=0.42 cfs @ 12.13 hrs HW=141.20' TW=0.00' (Dynamic Tailwater)

↑ 3=Culvert (Passes 0.42 cfs of 1.47 cfs potential flow)

2=Sharp-Crested Rectangular Weir (Weir Controls 0.42 cfs @ 1.04 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Pond 29P: CB6**

Inflow Area = 7,005 sf, 0.00% Impervious, Inflow Depth > 2.85" for 25-Year event  
 Inflow = 0.54 cfs @ 12.09 hrs, Volume= 1,664 cf  
 Outflow = 0.54 cfs @ 12.09 hrs, Volume= 1,664 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.54 cfs @ 12.09 hrs, Volume= 1,664 cf  
 Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 150.52' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	150.10'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 150.10' / 150.00' S= 0.0250 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.54 cfs @ 12.09 hrs HW=150.52' TW=148.09' (Dynamic Tailwater)  
 ↑1=Culvert (Barrel Controls 0.54 cfs @ 2.53 fps)

**Summary for Pond AD1: AD1**

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth > 4.24" for 25-Year event  
 Inflow = 0.08 cfs @ 12.09 hrs, Volume= 260 cf  
 Outflow = 0.08 cfs @ 12.09 hrs, Volume= 260 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.08 cfs @ 12.09 hrs, Volume= 260 cf  
 Routed to Pond DMH13 : DMH13

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 160.96' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.80'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.80' / 160.70' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.08 cfs @ 12.09 hrs HW=160.96' TW=160.86' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.08 cfs @ 1.54 fps)

**Summary for Pond AD2: AD2**

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth > 3.62" for 25-Year event  
 Inflow = 0.18 cfs @ 12.09 hrs, Volume= 547 cf  
 Outflow = 0.18 cfs @ 12.09 hrs, Volume= 547 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.18 cfs @ 12.09 hrs, Volume= 547 cf  
 Routed to Pond DMH6 : DMH6

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Peak Elev= 160.23' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.00'	<b>12.0" Round Culvert</b> L= 12.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.00' / 159.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.18 cfs @ 12.09 hrs HW=160.23' TW=159.98' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.18 cfs @ 1.29 fps)

### Summary for Pond AD3: AD3

Inflow Area = 600 sf, 37.50% Impervious, Inflow Depth > 3.93" for 25-Year event  
 Inflow = 0.06 cfs @ 12.09 hrs, Volume= 196 cf  
 Outflow = 0.06 cfs @ 12.09 hrs, Volume= 196 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.06 cfs @ 12.09 hrs, Volume= 196 cf  
 Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 159.70' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.55'	<b>12.0" Round Culvert</b> L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.55' / 159.45' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.06 cfs @ 12.09 hrs HW=159.70' TW=159.62' (Dynamic Tailwater)  
 ↑ 1=Culvert (Outlet Controls 0.06 cfs @ 1.26 fps)

### Summary for Pond AD4: AD4

Inflow Area = 2,595 sf, 42.39% Impervious, Inflow Depth > 4.03" for 25-Year event  
 Inflow = 0.28 cfs @ 12.09 hrs, Volume= 872 cf  
 Outflow = 0.28 cfs @ 12.09 hrs, Volume= 872 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.28 cfs @ 12.09 hrs, Volume= 872 cf  
 Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 158.24' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	157.95'	<b>12.0" Round Culvert</b> L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.95' / 157.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.28 cfs @ 12.09 hrs HW=158.24' TW=148.51' (Dynamic Tailwater)  
 ↑ 1=Culvert (Barrel Controls 0.28 cfs @ 2.16 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Pond AD5: AD5**

Inflow Area = 1,625 sf, 92.92% Impervious, Inflow Depth > 5.35" for 25-Year event  
 Inflow = 0.21 cfs @ 12.08 hrs, Volume= 725 cf  
 Outflow = 0.21 cfs @ 12.08 hrs, Volume= 725 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.21 cfs @ 12.08 hrs, Volume= 725 cf  
 Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 147.46' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.20'	<b>12.0" Round Culvert</b> L= 11.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.20' / 147.10' S= 0.0091 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.21 cfs @ 12.08 hrs HW=147.46' TW=147.30' (Dynamic Tailwater)  
 ↑1=Culvert (Outlet Controls 0.21 cfs @ 1.95 fps)

**Summary for Pond CB1:**

Inflow Area = 10,045 sf, 54.75% Impervious, Inflow Depth > 4.35" for 25-Year event  
 Inflow = 1.15 cfs @ 12.09 hrs, Volume= 3,642 cf  
 Outflow = 1.15 cfs @ 12.09 hrs, Volume= 3,642 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.15 cfs @ 12.09 hrs, Volume= 3,642 cf  
 Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 147.39' @ 12.09 hrs  
 Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.14 cfs @ 12.09 hrs HW=147.39' TW=146.11' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 1.14 cfs @ 2.15 fps)

**Summary for Pond CB2:**

Inflow Area = 5,760 sf, 69.18% Impervious, Inflow Depth > 4.79" for 25-Year event  
 Inflow = 0.70 cfs @ 12.08 hrs, Volume= 2,298 cf  
 Outflow = 0.70 cfs @ 12.08 hrs, Volume= 2,298 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.70 cfs @ 12.08 hrs, Volume= 2,298 cf  
 Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Peak Elev= 147.23' @ 12.08 hrs

Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.70 cfs @ 12.08 hrs HW=147.23' TW=146.11' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.70 cfs @ 1.87 fps)

**Summary for Pond CB3:**

Inflow Area = 13,605 sf, 72.80% Impervious, Inflow Depth &gt; 4.79" for 25-Year event

Inflow = 1.66 cfs @ 12.08 hrs, Volume= 5,427 cf

Outflow = 1.66 cfs @ 12.08 hrs, Volume= 5,427 cf, Atten= 0%, Lag= 0.0 min

Primary = 1.66 cfs @ 12.08 hrs, Volume= 5,427 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 145.20' @ 12.08 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=1.66 cfs @ 12.08 hrs HW=145.20' TW=143.15' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 1.66 cfs @ 4.75 fps)

**Summary for Pond CB4:**

Inflow Area = 9,380 sf, 82.78% Impervious, Inflow Depth &gt; 5.12" for 25-Year event

Inflow = 1.19 cfs @ 12.08 hrs, Volume= 4,005 cf

Outflow = 1.19 cfs @ 12.08 hrs, Volume= 4,005 cf, Atten= 0%, Lag= 0.0 min

Primary = 1.19 cfs @ 12.08 hrs, Volume= 4,005 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 144.44' @ 12.08 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 6.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0167 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Primary OutFlow** Max=1.19 cfs @ 12.08 hrs HW=144.44' TW=143.15' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 1.19 cfs @ 3.41 fps)

### Summary for Pond CB5:

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 4.79" for 25-Year event  
 Inflow = 0.55 cfs @ 12.08 hrs, Volume= 1,805 cf  
 Outflow = 0.55 cfs @ 12.08 hrs, Volume= 1,805 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.55 cfs @ 12.08 hrs, Volume= 1,805 cf  
 Routed to Pond DMH5 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 142.12' @ 12.11 hrs  
 Flood Elev= 143.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.60'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.60' / 140.50' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.51 cfs @ 12.08 hrs HW=141.99' TW=141.52' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 0.51 cfs @ 2.60 fps)

### Summary for Pond DCB1:

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 3.52" for 25-Year event  
 Inflow = 2.74 cfs @ 12.10 hrs, Volume= 8,670 cf  
 Outflow = 2.74 cfs @ 12.10 hrs, Volume= 8,670 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.74 cfs @ 12.10 hrs, Volume= 8,670 cf  
 Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 158.54' @ 12.10 hrs  
 Flood Elev= 173.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	157.20'	<b>12.0" Round Culvert</b> L= 131.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.20' / 150.00' S= 0.0550 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.74 cfs @ 12.10 hrs HW=158.54' TW=148.10' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 2.74 cfs @ 3.48 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Pond DCB2:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 3.13" for 25-Year event  
 Inflow = 3.65 cfs @ 12.12 hrs, Volume= 11,809 cf  
 Outflow = 3.65 cfs @ 12.12 hrs, Volume= 11,809 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 3.65 cfs @ 12.12 hrs, Volume= 11,809 cf  
 Routed to Pond DMH9 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 154.09' @ 12.12 hrs

Flood Elev= 172.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	152.10'	<b>12.0" Round Culvert</b> L= 78.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 152.10' / 148.60' S= 0.0449 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=3.64 cfs @ 12.12 hrs HW=154.09' TW=144.37' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 3.64 cfs @ 4.64 fps)

**Summary for Pond DMH1:**

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth > 4.51" for 25-Year event  
 Inflow = 1.85 cfs @ 12.09 hrs, Volume= 5,939 cf  
 Outflow = 1.85 cfs @ 12.09 hrs, Volume= 5,939 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 1.85 cfs @ 12.09 hrs, Volume= 5,939 cf  
 Routed to Pond 11P : P.UIS1

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 146.13' @ 12.57 hrs

Flood Elev= 150.55'

Device	Routing	Invert	Outlet Devices
#1	Primary	145.20'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 145.20' / 145.11' S= 0.0225 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.85 cfs @ 12.09 hrs HW=146.11' TW=145.31' (Dynamic Tailwater)  
 ↑ 1=Culvert (Barrel Controls 1.85 cfs @ 3.21 fps)

**Summary for Pond DMH10:**

Inflow Area = 36,545 sf, 15.60% Impervious, Inflow Depth > 3.39" for 25-Year event  
 Inflow = 3.27 cfs @ 12.10 hrs, Volume= 10,335 cf  
 Outflow = 3.27 cfs @ 12.10 hrs, Volume= 10,335 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 3.27 cfs @ 12.10 hrs, Volume= 10,335 cf  
 Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Peak Elev= 148.10' @ 12.10 hrs

Flood Elev= 154.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.40'	<b>12.0" Round Culvert</b> L= 43.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.40' / 145.80' S= 0.0140 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=3.27 cfs @ 12.10 hrs HW=148.10' TW=142.81' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 3.27 cfs @ 4.16 fps)

**Summary for Pond DMH11:**

Inflow Area = 52,350 sf, 29.01% Impervious, Inflow Depth &gt; 2.37" for 25-Year event

Inflow = 3.27 cfs @ 12.10 hrs, Volume= 10,335 cf

Outflow = 3.27 cfs @ 12.10 hrs, Volume= 10,335 cf, Atten= 0%, Lag= 0.0 min

Primary = 3.27 cfs @ 12.10 hrs, Volume= 10,335 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 142.81' @ 12.10 hrs

Flood Elev= 152.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.83'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.83' / 141.50' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=3.27 cfs @ 12.10 hrs HW=142.81' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 3.27 cfs @ 2.66 fps)

**Summary for Pond DMH12: DMH12**

Inflow Area = 2,360 sf, 79.87% Impervious, Inflow Depth &gt; 5.01" for 25-Year event

Inflow = 0.29 cfs @ 12.08 hrs, Volume= 985 cf

Outflow = 0.29 cfs @ 12.08 hrs, Volume= 985 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.29 cfs @ 12.08 hrs, Volume= 985 cf

Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.30' @ 12.08 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.00'	<b>12.0" Round Culvert</b> L= 208.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.00' / 142.35' S= 0.0224 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Primary OutFlow** Max=0.29 cfs @ 12.08 hrs HW=147.30' TW=144.29' (Dynamic Tailwater)  
↑ 1=Culvert (Inlet Controls 0.29 cfs @ 1.47 fps)

### Summary for Pond DMH13: DMH13

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth > 4.24" for 25-Year event  
Inflow = 0.08 cfs @ 12.09 hrs, Volume= 260 cf  
Outflow = 0.08 cfs @ 12.09 hrs, Volume= 260 cf, Atten= 0%, Lag= 0.0 min  
Primary = 0.08 cfs @ 12.09 hrs, Volume= 260 cf  
Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Peak Elev= 160.86' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.70'	<b>12.0" Round Culvert</b> L= 100.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.70' / 147.10' S= 0.1360 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.08 cfs @ 12.09 hrs HW=160.86' TW=147.30' (Dynamic Tailwater)  
↑ 1=Culvert (Inlet Controls 0.08 cfs @ 1.06 fps)

### Summary for Pond DMH2:

Inflow Area = 22,495 sf, 83.93% Impervious, Inflow Depth > 5.15" for 25-Year event  
Inflow = 2.79 cfs @ 12.08 hrs, Volume= 9,645 cf  
Outflow = 2.79 cfs @ 12.08 hrs, Volume= 9,645 cf, Atten= 0%, Lag= 0.0 min  
Primary = 2.79 cfs @ 12.08 hrs, Volume= 9,645 cf  
Routed to Pond 12P : P.UIS2

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Peak Elev= 144.46' @ 12.12 hrs  
Flood Elev= 150.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.45'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.45' / 141.36' S= 0.0180 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.63 cfs @ 12.08 hrs HW=144.29' TW=143.51' (Dynamic Tailwater)  
↑ 1=Culvert (Inlet Controls 2.63 cfs @ 3.35 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Pond DMH3:**

Inflow Area = 90,755 sf, 42.01% Impervious, Inflow Depth > 2.13" for 25-Year event  
 Inflow = 4.72 cfs @ 12.13 hrs, Volume= 16,123 cf  
 Outflow = 4.72 cfs @ 12.13 hrs, Volume= 16,123 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 4.72 cfs @ 12.13 hrs, Volume= 16,123 cf  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 140.25' @ 12.13 hrs

Flood Elev= 149.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	139.00'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.00' / 138.50' S= 0.0152 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=4.71 cfs @ 12.13 hrs HW=140.25' TW=0.00' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 4.71 cfs @ 3.00 fps)

**Summary for Pond DMH4:**

Inflow Area = 22,985 sf, 76.88% Impervious, Inflow Depth > 4.92" for 25-Year event  
 Inflow = 2.85 cfs @ 12.08 hrs, Volume= 9,432 cf  
 Outflow = 2.85 cfs @ 12.08 hrs, Volume= 9,432 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 2.85 cfs @ 12.08 hrs, Volume= 9,432 cf  
 Routed to Pond 13P : P.UIS3

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 143.66' @ 12.69 hrs

Flood Elev= 146.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.35'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.35' / 141.25' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.75 cfs @ 12.08 hrs HW=143.15' TW=142.30' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 2.75 cfs @ 3.50 fps)

**Summary for Pond DMH5:**

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 4.79" for 25-Year event  
 Inflow = 0.55 cfs @ 12.08 hrs, Volume= 1,805 cf  
 Outflow = 0.55 cfs @ 12.08 hrs, Volume= 1,805 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.55 cfs @ 12.08 hrs, Volume= 1,805 cf  
 Routed to Pond 14P : P.UIS4

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

Peak Elev= 141.66' @ 12.11 hrs

Flood Elev= 143.90'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.40'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.40' / 140.30' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.51 cfs @ 12.08 hrs HW=141.52' TW=141.05' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 0.51 cfs @ 2.61 fps)

**Summary for Pond DMH6: DMH6**

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth &gt; 3.62" for 25-Year event

Inflow = 0.18 cfs @ 12.09 hrs, Volume= 547 cf

Outflow = 0.18 cfs @ 12.09 hrs, Volume= 547 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.18 cfs @ 12.09 hrs, Volume= 547 cf

Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 159.98' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.75'	<b>12.0" Round Culvert</b> L= 29.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.75' / 159.45' S= 0.0103 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.18 cfs @ 12.09 hrs HW=159.98' TW=159.62' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 0.18 cfs @ 1.29 fps)

**Summary for Pond DMH7: DMH7**

Inflow Area = 2,410 sf, 31.74% Impervious, Inflow Depth &gt; 3.70" for 25-Year event

Inflow = 0.24 cfs @ 12.09 hrs, Volume= 743 cf

Outflow = 0.24 cfs @ 12.09 hrs, Volume= 743 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.24 cfs @ 12.09 hrs, Volume= 743 cf

Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 159.62' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.35'	<b>12.0" Round Culvert</b> L= 147.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.35' / 157.85' S= 0.0102 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.24 cfs @ 12.09 hrs HW=159.62' TW=148.51' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 0.24 cfs @ 1.40 fps)

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=5.83"

Printed 10/14/2025

**Summary for Pond DMH8: DMH8**

Inflow Area = 5,005 sf, 37.26% Impervious, Inflow Depth > 3.87" for 25-Year event  
 Inflow = 0.52 cfs @ 12.09 hrs, Volume= 1,615 cf  
 Outflow = 0.52 cfs @ 12.09 hrs, Volume= 1,615 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.52 cfs @ 12.09 hrs, Volume= 1,615 cf  
 Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 148.51' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	148.10'	<b>12.0" Round Culvert</b> L= 72.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 148.10' / 142.35' S= 0.0799 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.52 cfs @ 12.09 hrs HW=148.51' TW=144.32' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 0.52 cfs @ 1.72 fps)

**Summary for Pond DMH9:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 3.13" for 25-Year event  
 Inflow = 3.65 cfs @ 12.12 hrs, Volume= 11,809 cf  
 Outflow = 3.65 cfs @ 12.12 hrs, Volume= 11,809 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 3.65 cfs @ 12.12 hrs, Volume= 11,809 cf  
 Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 144.37' @ 12.12 hrs  
 Flood Elev= 154.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	142.38'	<b>12.0" Round Culvert</b> L= 55.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 142.38' / 139.90' S= 0.0451 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=3.64 cfs @ 12.12 hrs HW=144.37' TW=140.23' (Dynamic Tailwater)  
 ↑1=Culvert (Inlet Controls 3.64 cfs @ 4.64 fps)

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Subcatchment 10S: Overland to Wetlands**

Runoff = 3.27 cfs @ 12.09 hrs, Volume= 10,101 cf, Depth> 4.90"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
17,430	70	Woods, Good, HSG C
6,325	74	>75% Grass cover, Good, HSG C
1,000	61	>75% Grass cover, Good, HSG B
24,755	71	Weighted Average
24,755		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.3	50	0.1700	0.16		<b>Sheet Flow, Sheet Flow</b> Woods: Light underbrush n= 0.400 P2= 3.15"
0.2	20	0.1400	1.87		<b>Shallow Concentrated Flow, Shallow Flow</b> Woodland Kv= 5.0 fps
0.5	45	0.0560	1.66		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.0	115				Total

**Summary for Subcatchment 11S: Overland to CB1**

Runoff = 1.75 cfs @ 12.08 hrs, Volume= 5,696 cf, Depth> 6.80"  
 Routed to Pond CB1 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
5,500	98	Paved parking, HSG C
4,545	74	>75% Grass cover, Good, HSG C
10,045	87	Weighted Average
4,545		45.25% Pervious Area
5,500		54.75% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.37"

Printed 10/14/2025

**Summary for Subcatchment 12S: Overland to CB2**

Runoff = 1.05 cfs @ 12.08 hrs, Volume= 3,496 cf, Depth> 7.28"  
 Routed to Pond CB2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
3,545	98	Paved parking, HSG C
440	98	Retaining Wall, HSG C
1,775	74	>75% Grass cover, Good, HSG C
5,760	91	Weighted Average
1,775		30.82% Pervious Area
3,985		69.18% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 13S: Overland to CB3**

Runoff = 2.47 cfs @ 12.08 hrs, Volume= 8,258 cf, Depth> 7.28"  
 Routed to Pond CB3 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
9,580	98	Paved parking, HSG C
325	98	Retaining Wall, HSG C
3,700	74	>75% Grass cover, Good, HSG C
13,605	91	Weighted Average
3,700		27.20% Pervious Area
9,905		72.80% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 14S: Overland to CB4**

Runoff = 1.74 cfs @ 12.08 hrs, Volume= 5,975 cf, Depth> 7.64"  
 Routed to Pond CB4 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

**27164-2****Type III 24-hr 100-Year Rainfall=8.37"**

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Area (sf)	CN	Description
7,175	98	Paved parking, HSG C
*	590	Retaining Wall, HSG C
1,615	74	>75% Grass cover, Good, HSG C
9,380	94	Weighted Average
1,615		17.22% Pervious Area
7,765		82.78% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**Summary for Subcatchment 15S: Overland to CB5**

Runoff = 0.82 cfs @ 12.08 hrs, Volume= 2,747 cf, Depth> 7.28"  
 Routed to Pond CB5 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
2,985	98	Paved parking, HSG C
*	225	Retaining Wall, HSG C
1,315	74	>75% Grass cover, Good, HSG C
4,525	91	Weighted Average
1,315		29.06% Pervious Area
3,210		70.94% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**Summary for Subcatchment 17S: Overland to Street Drainage**

Runoff = 0.11 cfs @ 12.08 hrs, Volume= 393 cf, Depth> 8.12"  
 Routed to Reach 10R : Wetlands System - Peppermint Brook

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
580	98	Paved parking, HSG C
580		100.00% Impervious Area
Tc (min)	Length (feet)	Slope (ft/ft) Velocity (ft/sec) Capacity (cfs)
6.0		<b>Direct Entry,</b>

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.37"

Printed 10/14/2025

**Summary for Subcatchment 18S: Overland to Drainage Swale**

Runoff = 3.30 cfs @ 12.00 hrs, Volume= 8,368 cf, Depth> 5.14"  
 Routed to Reach 19R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
4,935	70	Woods, Good, HSG C
14,605	74	>75% Grass cover, Good, HSG C
19,540	73	Weighted Average
19,540		100.00% Pervious Area

**Summary for Subcatchment 20S: Roof**

Runoff = 2.85 cfs @ 12.08 hrs, Volume= 10,243 cf, Depth> 8.12"  
 Routed to Pond DMH2 :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
15,130	98	Roofs, HSG C
15,130		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 21S: Overland to Rear of Building**

Runoff = 6.27 cfs @ 12.10 hrs, Volume= 20,260 cf, Depth> 5.37"  
 Routed to Reach 13R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
40,790	74	>75% Grass cover, Good, HSG C
2,910	70	Woods, Good, HSG C
1,575	98	Roofs, HSG C
45,275	75	Weighted Average
43,700		96.52% Pervious Area
1,575		3.48% Impervious Area

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
3.2	300	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.2400	2.45		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Woodland Kv= 5.0 fps
7.1	380	Total			

### Summary for Subcatchment 22S: Overland to Rear of Building

Runoff = 4.49 cfs @ 12.09 hrs, Volume= 14,393 cf, Depth> 5.85"  
Routed to Reach 14R : Drainage Swale

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
23,415	74	>75% Grass cover, Good, HSG C
425	70	Woods, Good, HSG C
2,380	98	Roofs, HSG C
3,320	98	Paved parking, HSG C
29,540	79	Weighted Average
23,840		80.70% Pervious Area
5,700		19.30% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	50	0.0600	0.23		<b>Sheet Flow, Sheet Flow</b> Grass: Short n= 0.150 P2= 3.15"
1.9	180	0.0500	1.57		<b>Shallow Concentrated Flow, Shallow Flow</b> Short Grass Pasture Kv= 7.0 fps
0.2	30	0.0200	2.87		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Paved Kv= 20.3 fps
0.8	110	0.1000	2.21		<b>Shallow Concentrated Flow, Shallow Flow - Slope &amp; Cover Change</b> Short Grass Pasture Kv= 7.0 fps
6.6	370	Total			

### Summary for Subcatchment 23S: Overland to AD5

Runoff = 0.30 cfs @ 12.08 hrs, Volume= 1,068 cf, Depth> 7.88"  
Routed to Pond AD5 : AD5

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Type III 24-hr 100-Year Rainfall=8.37"

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Area (sf)	CN	Description
1,335	98	Paved parking, HSG C
*		
175	98	Unconnected pavement, HSG C- ret. walls
115	74	>75% Grass cover, Good, HSG C
1,625	96	Weighted Average
115		7.08% Pervious Area
1,510		92.92% Impervious Area
175		11.59% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(cfs)	

6.0 **Direct Entry,****Summary for Subcatchment 24S: Overland to AD1**

Runoff = 0.13 cfs @ 12.08 hrs, Volume= 409 cf, Depth> 6.68"  
 Routed to Pond AD1 : AD1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
260	98	Paved parking, HSG C
*		
115	98	Unconnected pavement, HSG C-ret walls
360	74	>75% Grass cover, Good, HSG C
735	86	Weighted Average
360		48.98% Pervious Area
375		51.02% Impervious Area
115		30.67% Unconnected
Tc	Length	Slope
(min)	(feet)	(ft/ft)
Velocity	Capacity	Description
	(cfs)	

6.0 **Direct Entry,****Summary for Subcatchment 25S: Overland to AD2**

Runoff = 0.29 cfs @ 12.09 hrs, Volume= 900 cf, Depth> 5.97"  
 Routed to Pond AD2 : AD2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Adj	Description
360	98		Paved parking, HSG C
180	98		Unconnected pavement, HSG C
1,270	74		>75% Grass cover, Good, HSG C
1,810	81	80	Weighted Average, UI Adjusted
1,270			70.17% Pervious Area
540			29.83% Impervious Area
180			33.33% Unconnected

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 26S: Overland to AD3**

Runoff = 0.10 cfs @ 12.09 hrs, Volume= 316 cf, Depth> 6.33"  
 Routed to Pond AD3 : AD3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
185	98	Paved parking, HSG C
*	40	Unconnected pavement, HSG C-ret. walls
	375	>75% Grass cover, Good, HSG C
	600	Weighted Average
*	375	62.50% Pervious Area
	225	37.50% Impervious Area
	40	17.78% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Subcatchment 27S: Overland to AD4**

Runoff = 0.44 cfs @ 12.09 hrs, Volume= 1,394 cf, Depth> 6.44"  
 Routed to Pond AD4 : AD4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description
775	98	Paved parking, HSG C
*	325	Unconnected pavement, HSG C-ret. walls
	1,495	>75% Grass cover, Good, HSG C
	2,595	Weighted Average
*	1,495	57.61% Pervious Area
	1,100	42.39% Impervious Area
	325	29.55% Unconnected

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.37"

Printed 10/14/2025

**Summary for Subcatchment 28S: Overland to CB6**

Runoff = 0.95 cfs @ 12.09 hrs, Volume= 2,928 cf, Depth> 5.02"  
 Routed to Pond 29P : CB6

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Type III 24-hr 100-Year Rainfall=8.37"

Area (sf)	CN	Description			
2,630	70	Woods, Good, HSG C			
4,375	74	>75% Grass cover, Good, HSG C			
7,005	72	Weighted Average			
7,005		100.00% Pervious Area			
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Summary for Reach 10R: Wetlands System - Peppermint Brook**

Inflow Area = 192,505 sf, 29.66% Impervious, Inflow Depth > 4.38" for 100-Year event  
 Inflow = 19.90 cfs @ 12.11 hrs, Volume= 70,206 cf  
 Outflow = 19.90 cfs @ 12.11 hrs, Volume= 70,206 cf, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**Summary for Reach 13R: Drainage Swale**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth > 5.37" for 100-Year event  
 Inflow = 6.27 cfs @ 12.10 hrs, Volume= 20,260 cf  
 Outflow = 6.23 cfs @ 12.11 hrs, Volume= 20,244 cf, Atten= 1%, Lag= 0.6 min  
 Routed to Pond DCB2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Max. Velocity= 2.84 fps, Min. Travel Time= 0.9 min  
 Avg. Velocity = 0.87 fps, Avg. Travel Time= 2.8 min

Peak Storage= 318 cf @ 12.11 hrs  
 Average Depth at Peak Storage= 0.49', Surface Width= 5.95'  
 Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 25.08 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight  
 Side Slope Z-value= 3.0 '/' Top Width= 9.00'  
 Length= 145.0' Slope= 0.0069 '/'  
 Inlet Invert= 172.00', Outlet Invert= 171.00'

**27164-2**

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.37"

Printed 10/14/2025

‡

### **Summary for Reach 14R: Drainage Swale**

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 5.85" for 100-Year event

Inflow = 4.49 cfs @ 12.09 hrs, Volume= 14,393 cf

Outflow = 4.48 cfs @ 12.10 hrs, Volume= 14,387 cf, Atten= 0%, Lag= 0.3 min  
Routed to Pond DCB1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Max. Velocity= 2.67 fps, Min. Travel Time= 0.4 min

Avg. Velocity = 0.78 fps, Avg. Travel Time= 1.4 min

Peak Storage= 109 cf @ 12.10 hrs

Average Depth at Peak Storage= 0.40', Surface Width= 5.40'

Bank-Full Depth= 1.00' Flow Area= 6.0 sf, Capacity= 26.49 cfs

3.00' x 1.00' deep channel, n= 0.022 Earth, clean & straight

Side Slope Z-value= 3.0 '/' Top Width= 9.00'

Length= 65.0' Slope= 0.0077 '/'

Inlet Invert= 174.00', Outlet Invert= 173.50'

‡

### **Summary for Reach 19R: Drainage Swale**

Inflow Area = 19,540 sf, 0.00% Impervious, Inflow Depth > 5.14" for 100-Year event

Inflow = 3.30 cfs @ 12.00 hrs, Volume= 8,368 cf

Outflow = 3.16 cfs @ 12.01 hrs, Volume= 8,360 cf, Atten= 4%, Lag= 0.7 min  
Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Max. Velocity= 5.66 fps, Min. Travel Time= 1.0 min

Avg. Velocity = 1.64 fps, Avg. Travel Time= 3.5 min

Peak Storage= 190 cf @ 12.01 hrs

Average Depth at Peak Storage= 0.25', Surface Width= 2.99'

Bank-Full Depth= 0.50' Flow Area= 1.5 sf, Capacity= 12.44 cfs

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

1.50' x 0.50' deep channel, n= 0.025 Earth, clean & winding  
 Side Slope Z-value= 3.0 '/' Top Width= 4.50'  
 Length= 340.0' Slope= 0.0882 '/'  
 Inlet Invert= 172.00', Outlet Invert= 142.00'



‡

### Summary for Pond 11P: P.UIS1

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth > 6.98" for 100-Year event  
 Inflow = 2.80 cfs @ 12.08 hrs, Volume= 9,192 cf  
 Outflow = 1.06 cfs @ 12.32 hrs, Volume= 9,191 cf, Atten= 62%, Lag= 14.1 min  
 Discarded = 0.27 cfs @ 11.63 hrs, Volume= 7,988 cf  
 Primary = 0.79 cfs @ 12.32 hrs, Volume= 1,204 cf  
 Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 146.70' @ 12.32 hrs Surf.Area= 1,435 sf Storage= 2,394 cf

Plug-Flow detention time= 43.1 min calculated for 9,187 cf (100% of inflow)  
 Center-of-Mass det. time= 43.0 min ( 821.3 - 778.3 )

Volume	Invert	Avail.Storage	Storage Description
#1A	144.25'	2,065 cf	<b>22.75'W x 63.06'L x 5.50'H Field A</b> 7,890 cf Overall - 2,728 cf Embedded = 5,162 cf x 40.0% Voids
#2A	145.00'	2,728 cf	<b>ADS_StormTech MC-3500 d +Cap x 24 Inside #1</b> Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 24 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,793 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	144.25'	<b>8.270 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	148.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	146.00'	<b>12.0" Round Culvert</b> L= 13.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.00' / 145.80' S= 0.0154 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	146.25'	<b>12.0" Vert. Orifice/Grate</b>	C= 0.600 Limited to weir flow at low heads

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Discarded OutFlow** Max=0.27 cfs @ 11.63 hrs HW=144.31' (Free Discharge)↑  
1=Exfiltration (Exfiltration Controls 0.27 cfs)**Primary OutFlow** Max=0.79 cfs @ 12.32 hrs HW=146.70' TW=142.78' (Dynamic Tailwater)↑  
3=Culvert (Passes 0.79 cfs of 1.33 cfs potential flow)  
└─2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)  
└─4=Orifice/Grate (Orifice Controls 0.79 cfs @ 2.29 fps)

### Summary for Pond 12P: P.UIS2

Inflow Area =	22,495 sf, 83.93% Impervious, Inflow Depth > 7.64"	for 100-Year event
Inflow =	4.11 cfs @ 12.08 hrs, Volume=	14,330 cf
Outflow =	2.83 cfs @ 12.17 hrs, Volume=	12,316 cf, Atten= 31%, Lag= 4.9 min
Discarded =	0.07 cfs @ 7.90 hrs, Volume=	5,099 cf
Primary =	2.76 cfs @ 12.17 hrs, Volume=	7,218 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 145.31' @ 12.17 hrs Surf.Area= 1,271 sf Storage= 3,888 cf

Plug-Flow detention time= 107.3 min calculated for 12,316 cf (86% of inflow)  
 Center-of-Mass det. time= 44.8 min ( 797.0 - 752.1 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	1,838 cf	<b>22.75'W x 55.89'L x 5.50'H Field A</b> 6,993 cf Overall - 2,398 cf Embedded = 4,595 cf x 40.0% Voids
#2A	141.25'	2,398 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 21 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 21 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
4,236 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices	
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>	Phase-In= 0.01'
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b>	2 End Contraction(s)
#3	Primary	139.50'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.50' / 139.40' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf	
#4	Device 3	143.25'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads	

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Discarded OutFlow** Max=0.07 cfs @ 7.90 hrs HW=140.56' (Free Discharge)↑  
1=Exfiltration (Exfiltration Controls 0.07 cfs)**Primary OutFlow** Max=2.75 cfs @ 12.17 hrs HW=145.31' TW=141.67' (Dynamic Tailwater)↑  
3=Culvert (Passes 2.75 cfs of 5.70 cfs potential flow)

2=Sharp-Crested Rectangular Weir (Weir Controls 0.21 cfs @ 0.82 fps)

4=Orifice/Grate (Orifice Controls 2.55 cfs @ 6.48 fps)

### Summary for Pond 13P: P.UIS3

Inflow Area =	22,985 sf, 76.88% Impervious, Inflow Depth > 7.43"	for 100-Year event
Inflow =	4.21 cfs @ 12.08 hrs, Volume=	14,233 cf
Outflow =	1.65 cfs @ 12.30 hrs, Volume=	11,506 cf, Atten= 61%, Lag= 13.2 min
Discarded =	0.11 cfs @ 9.26 hrs, Volume=	6,865 cf
Primary =	1.54 cfs @ 12.30 hrs, Volume=	4,641 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 144.37' @ 12.30 hrs Surf.Area= 1,924 sf Storage= 5,109 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 84.9 min ( 851.1 - 766.1 )

Volume	Invert	Avail.Storage	Storage Description
#1A	140.50'	2,746 cf	<b>22.75'W x 84.57'L x 5.50'H Field A</b> 10,582 cf Overall - 3,718 cf Embedded = 6,864 cf x 40.0% Voids
#2A	141.25'	3,718 cf	<b>ADS_StormTech MC-3500 d +Cap</b> x 33 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 33 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
			6,463 cf Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	140.50'	<b>2.410 in/hr Exfiltration over Surface area</b>
#2	Device 3	145.25'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	141.00'	<b>12.0" Round Culvert</b> L= 31.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.00' / 139.90' S= 0.0355 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#4	Device 3	143.45'	<b>6.0" Vert. Orifice/Grate X 2.00</b> C= 0.600 Limited to weir flow at low heads

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Discarded OutFlow** Max=0.11 cfs @ 9.26 hrs HW=140.56' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.11 cfs)

**Primary OutFlow** Max=1.54 cfs @ 12.30 hrs HW=144.37' TW=140.75' (Dynamic Tailwater)

↑ 3=Culvert (Passes 1.54 cfs of 5.05 cfs potential flow)

2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

4=Orifice/Grate (Orifice Controls 1.54 cfs @ 3.93 fps)

**Summary for Pond 14P: P.UIS4**

Inflow Area =	4,525 sf, 70.94% Impervious, Inflow Depth > 7.28"	for 100-Year event
Inflow =	0.82 cfs @ 12.08 hrs, Volume=	2,747 cf
Outflow =	0.82 cfs @ 12.09 hrs, Volume=	2,746 cf, Atten= 0%, Lag= 0.5 min
Discarded =	0.07 cfs @ 11.39 hrs, Volume=	2,015 cf
Primary =	0.75 cfs @ 12.09 hrs, Volume=	731 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 141.25' @ 12.09 hrs Surf.Area= 364 sf Storage= 307 cf

Plug-Flow detention time= 17.5 min calculated for 2,745 cf (100% of inflow)

Center-of-Mass det. time= 17.5 min ( 788.2 - 770.8 )

Volume	Invert	Avail.Storage	Storage Description
#1A	139.80'	269 cf	<b>14.83'W x 24.56'L x 2.33'H Field A</b> 850 cf Overall - 177 cf Embedded = 673 cf x 40.0% Voids
#2A	140.30'	177 cf	<b>ADS_StormTech SC-310 +Cap</b> x 12 Inside #1 Effective Size= 28.9"W x 16.0"H => 2.07 sf x 7.12'L = 14.7 cf Overall Size= 34.0"W x 16.0"H x 7.56'L with 0.44' Overlap 12 Chambers in 4 Rows
446 cf			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	139.80'	<b>8.270 in/hr Exfiltration over Surface area</b> Phase-In= 0.01'
#2	Device 3	141.10'	<b>4.0' long Sharp-Crested Rectangular Weir</b> 2 End Contraction(s)
#3	Primary	140.45'	<b>12.0" Round Culvert</b> L= 17.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.45' / 140.20' S= 0.0147 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Discarded OutFlow** Max=0.07 cfs @ 11.39 hrs HW=139.82' (Free Discharge)

↑ 1=Exfiltration (Exfiltration Controls 0.07 cfs)

**Primary OutFlow** Max=0.75 cfs @ 12.09 hrs HW=141.25' TW=0.00' (Dynamic Tailwater)

↑ 3=Culvert (Passes 0.75 cfs of 1.62 cfs potential flow)

2=Sharp-Crested Rectangular Weir (Weir Controls 0.75 cfs @ 1.26 fps)

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond 29P: CB6**

Inflow Area = 7,005 sf, 0.00% Impervious, Inflow Depth &gt; 5.02" for 100-Year event

Inflow = 0.95 cfs @ 12.09 hrs, Volume= 2,928 cf

Outflow = 0.95 cfs @ 12.09 hrs, Volume= 2,928 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.95 cfs @ 12.09 hrs, Volume= 2,928 cf

Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 150.69' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	150.10'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 150.10' / 150.00' S= 0.0250 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.94 cfs @ 12.09 hrs HW=150.69' TW=150.15' (Dynamic Tailwater)

↑1=Culvert (Barrel Controls 0.94 cfs @ 2.81 fps)

**Summary for Pond AD1: AD1**

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth &gt; 6.68" for 100-Year event

Inflow = 0.13 cfs @ 12.08 hrs, Volume= 409 cf

Outflow = 0.13 cfs @ 12.08 hrs, Volume= 409 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.13 cfs @ 12.08 hrs, Volume= 409 cf

Routed to Pond DMH13 : DMH13

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 161.00' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.80'	<b>12.0" Round Culvert</b> L= 7.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.80' / 160.70' S= 0.0143 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.13 cfs @ 12.08 hrs HW=161.00' TW=160.89' (Dynamic Tailwater)

↑1=Culvert (Outlet Controls 0.13 cfs @ 1.66 fps)

**Summary for Pond AD2: AD2**

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth &gt; 5.97" for 100-Year event

Inflow = 0.29 cfs @ 12.09 hrs, Volume= 900 cf

Outflow = 0.29 cfs @ 12.09 hrs, Volume= 900 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.29 cfs @ 12.09 hrs, Volume= 900 cf

Routed to Pond DMH6 : DMH6

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 160.30' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.00'	<b>12.0" Round Culvert</b> L= 12.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.00' / 159.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.29 cfs @ 12.09 hrs HW=160.30' TW=160.05' (Dynamic Tailwater)  
 ↑ 1=Culvert (Inlet Controls 0.29 cfs @ 1.46 fps)

### Summary for Pond AD3: AD3

Inflow Area = 600 sf, 37.50% Impervious, Inflow Depth > 6.33" for 100-Year event  
 Inflow = 0.10 cfs @ 12.09 hrs, Volume= 316 cf  
 Outflow = 0.10 cfs @ 12.09 hrs, Volume= 316 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.10 cfs @ 12.09 hrs, Volume= 316 cf  
 Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 159.76' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.55'	<b>12.0" Round Culvert</b> L= 10.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.55' / 159.45' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.10 cfs @ 12.09 hrs HW=159.76' TW=159.70' (Dynamic Tailwater)  
 ↑ 1=Culvert (Outlet Controls 0.10 cfs @ 1.22 fps)

### Summary for Pond AD4: AD4

Inflow Area = 2,595 sf, 42.39% Impervious, Inflow Depth > 6.44" for 100-Year event  
 Inflow = 0.44 cfs @ 12.09 hrs, Volume= 1,394 cf  
 Outflow = 0.44 cfs @ 12.09 hrs, Volume= 1,394 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.44 cfs @ 12.09 hrs, Volume= 1,394 cf  
 Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 158.33' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	157.95'	<b>12.0" Round Culvert</b> L= 8.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.95' / 157.85' S= 0.0125 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.43 cfs @ 12.09 hrs HW=158.33' TW=148.63' (Dynamic Tailwater)  
 ↑ 1=Culvert (Barrel Controls 0.43 cfs @ 2.35 fps)

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond AD5: AD5**

Inflow Area = 1,625 sf, 92.92% Impervious, Inflow Depth &gt; 7.88" for 100-Year event

Inflow = 0.30 cfs @ 12.08 hrs, Volume= 1,068 cf

Outflow = 0.30 cfs @ 12.08 hrs, Volume= 1,068 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.30 cfs @ 12.08 hrs, Volume= 1,068 cf

Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.53' @ 12.10 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.20'	<b>12.0" Round Culvert</b> L= 11.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.20' / 147.10' S= 0.0091 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.30 cfs @ 12.08 hrs HW=147.53' TW=147.37' (Dynamic Tailwater)

↑1=Culvert (Outlet Controls 0.30 cfs @ 1.98 fps)

**Summary for Pond CB1:**

Inflow Area = 10,045 sf, 54.75% Impervious, Inflow Depth &gt; 6.80" for 100-Year event

Inflow = 1.75 cfs @ 12.08 hrs, Volume= 5,696 cf

Outflow = 1.75 cfs @ 12.08 hrs, Volume= 5,696 cf, Atten= 0%, Lag= 0.0 min

Primary = 1.75 cfs @ 12.08 hrs, Volume= 5,696 cf

Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.60' @ 12.08 hrs

Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.75 cfs @ 12.08 hrs HW=147.59' TW=146.69' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 1.75 cfs @ 2.47 fps)

**Summary for Pond CB2:**

Inflow Area = 5,760 sf, 69.18% Impervious, Inflow Depth &gt; 7.28" for 100-Year event

Inflow = 1.05 cfs @ 12.08 hrs, Volume= 3,496 cf

Outflow = 1.05 cfs @ 12.08 hrs, Volume= 3,496 cf, Atten= 0%, Lag= 0.0 min

Primary = 1.05 cfs @ 12.08 hrs, Volume= 3,496 cf

Routed to Pond DMH1 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 147.36' @ 12.08 hrs

Flood Elev= 150.35'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.75'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.75' / 146.50' S= 0.0500 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=1.04 cfs @ 12.08 hrs HW=147.36' TW=146.69' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 1.04 cfs @ 2.09 fps)

**Summary for Pond CB3:**

Inflow Area = 13,605 sf, 72.80% Impervious, Inflow Depth &gt; 7.28" for 100-Year event

Inflow = 2.47 cfs @ 12.08 hrs, Volume= 8,258 cf

Outflow = 2.47 cfs @ 12.08 hrs, Volume= 8,258 cf, Atten= 0%, Lag= 0.0 min

Primary = 2.47 cfs @ 12.08 hrs, Volume= 8,258 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 148.79' @ 12.09 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=2.42 cfs @ 12.08 hrs HW=148.69' TW=145.37' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 2.42 cfs @ 6.93 fps)

**Summary for Pond CB4:**

Inflow Area = 9,380 sf, 82.78% Impervious, Inflow Depth &gt; 7.64" for 100-Year event

Inflow = 1.74 cfs @ 12.08 hrs, Volume= 5,975 cf

Outflow = 1.74 cfs @ 12.08 hrs, Volume= 5,975 cf, Atten= 0%, Lag= 0.0 min

Primary = 1.74 cfs @ 12.08 hrs, Volume= 5,975 cf

Routed to Pond DMH4 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.08' @ 12.10 hrs

Flood Elev= 146.70'

Device	Routing	Invert	Outlet Devices
#1	Primary	143.30'	<b>8.0" Round Culvert</b> L= 6.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 143.30' / 143.20' S= 0.0167 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.35 sf

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Primary OutFlow** Max=1.67 cfs @ 12.08 hrs HW=146.95' TW=145.36' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 1.67 cfs @ 4.78 fps)

### Summary for Pond CB5:

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth > 7.28" for 100-Year event  
 Inflow = 0.82 cfs @ 12.08 hrs, Volume= 2,747 cf  
 Outflow = 0.82 cfs @ 12.08 hrs, Volume= 2,747 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 0.82 cfs @ 12.08 hrs, Volume= 2,747 cf  
 Routed to Pond DMH5 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 143.66' @ 12.09 hrs  
 Flood Elev= 143.80'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.60'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.60' / 140.50' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.81 cfs @ 12.08 hrs HW=143.64' TW=142.45' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 0.81 cfs @ 4.14 fps)

### Summary for Pond DCB1:

Inflow Area = 29,540 sf, 19.30% Impervious, Inflow Depth > 5.84" for 100-Year event  
 Inflow = 4.48 cfs @ 12.10 hrs, Volume= 14,387 cf  
 Outflow = 4.48 cfs @ 12.10 hrs, Volume= 14,387 cf, Atten= 0%, Lag= 0.0 min  
 Primary = 4.48 cfs @ 12.10 hrs, Volume= 14,387 cf  
 Routed to Pond DMH10 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
 Peak Elev= 159.95' @ 12.10 hrs  
 Flood Elev= 173.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	157.20'	<b>12.0" Round Culvert</b> L= 131.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 157.20' / 150.00' S= 0.0550 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=4.48 cfs @ 12.10 hrs HW=159.95' TW=150.19' (Dynamic Tailwater)  
 ↗ 1=Culvert (Inlet Controls 4.48 cfs @ 5.70 fps)

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond DCB2:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth &gt; 5.37" for 100-Year event

Inflow = 6.23 cfs @ 12.11 hrs, Volume= 20,244 cf

Outflow = 6.23 cfs @ 12.11 hrs, Volume= 20,244 cf, Atten= 0%, Lag= 0.0 min

Primary = 6.23 cfs @ 12.11 hrs, Volume= 20,244 cf

Routed to Pond DMH9 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 156.95' @ 12.11 hrs

Flood Elev= 172.00'

Device	Routing	Invert	Outlet Devices
#1	Primary	152.10'	<b>12.0" Round Culvert</b> L= 78.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 152.10' / 148.60' S= 0.0449 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=6.22 cfs @ 12.11 hrs HW=156.95' TW=147.23' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 6.22 cfs @ 7.92 fps)

**Summary for Pond DMH1:**

Inflow Area = 15,805 sf, 60.01% Impervious, Inflow Depth &gt; 6.98" for 100-Year event

Inflow = 2.80 cfs @ 12.08 hrs, Volume= 9,192 cf

Outflow = 2.80 cfs @ 12.08 hrs, Volume= 9,192 cf, Atten= 0%, Lag= 0.0 min

Primary = 2.80 cfs @ 12.08 hrs, Volume= 9,192 cf

Routed to Pond 11P : P.UIS1

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 146.85' @ 12.26 hrs

Flood Elev= 150.55'

Device	Routing	Invert	Outlet Devices
#1	Primary	145.20'	<b>12.0" Round Culvert</b> L= 4.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 145.20' / 145.11' S= 0.0225 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=2.66 cfs @ 12.08 hrs HW=146.69' TW=145.90' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 2.66 cfs @ 3.39 fps)

**Summary for Pond DMH10:**

Inflow Area = 36,545 sf, 15.60% Impervious, Inflow Depth &gt; 5.69" for 100-Year event

Inflow = 5.42 cfs @ 12.10 hrs, Volume= 17,315 cf

Outflow = 5.42 cfs @ 12.10 hrs, Volume= 17,315 cf, Atten= 0%, Lag= 0.0 min

Primary = 5.42 cfs @ 12.10 hrs, Volume= 17,315 cf

Routed to Pond DMH11 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 150.20' @ 12.10 hrs

Flood Elev= 154.60'

Device	Routing	Invert	Outlet Devices
#1	Primary	146.40'	<b>12.0" Round Culvert</b> L= 43.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 146.40' / 145.80' S= 0.0140 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=5.41 cfs @ 12.10 hrs HW=150.19' TW=143.22' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 5.41 cfs @ 6.89 fps)

**Summary for Pond DMH11:**

Inflow Area = 52,350 sf, 29.01% Impervious, Inflow Depth &gt; 4.24" for 100-Year event

Inflow = 5.42 cfs @ 12.10 hrs, Volume= 18,519 cf

Outflow = 5.42 cfs @ 12.10 hrs, Volume= 18,519 cf, Atten= 0%, Lag= 0.0 min

Primary = 5.42 cfs @ 12.10 hrs, Volume= 18,519 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 143.22' @ 12.10 hrs

Flood Elev= 152.75'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.83'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.83' / 141.50' S= 0.0100 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=5.41 cfs @ 12.10 hrs HW=143.22' TW=0.00' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 5.41 cfs @ 3.17 fps)

**Summary for Pond DMH12: DMH12**

Inflow Area = 2,360 sf, 79.87% Impervious, Inflow Depth &gt; 7.51" for 100-Year event

Inflow = 0.43 cfs @ 12.08 hrs, Volume= 1,477 cf

Outflow = 0.43 cfs @ 12.08 hrs, Volume= 1,477 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.43 cfs @ 12.08 hrs, Volume= 1,477 cf

Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.39' @ 12.11 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	147.00'	<b>12.0" Round Culvert</b> L= 208.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 147.00' / 142.35' S= 0.0224 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Primary OutFlow** Max=0.40 cfs @ 12.08 hrs HW=147.37' TW=146.47' (Dynamic Tailwater)  
↑  
1=Culvert (Outlet Controls 0.40 cfs @ 2.22 fps)

### Summary for Pond DMH13: DMH13

Inflow Area = 735 sf, 51.02% Impervious, Inflow Depth > 6.68" for 100-Year event  
Inflow = 0.13 cfs @ 12.08 hrs, Volume= 409 cf  
Outflow = 0.13 cfs @ 12.08 hrs, Volume= 409 cf, Atten= 0%, Lag= 0.0 min  
Primary = 0.13 cfs @ 12.08 hrs, Volume= 409 cf  
Routed to Pond DMH12 : DMH12

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Peak Elev= 160.89' @ 12.08 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	160.70'	<b>12.0" Round Culvert</b> L= 100.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 160.70' / 147.10' S= 0.1360 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.13 cfs @ 12.08 hrs HW=160.89' TW=147.38' (Dynamic Tailwater)  
↑  
1=Culvert (Inlet Controls 0.13 cfs @ 1.18 fps)

### Summary for Pond DMH2:

Inflow Area = 22,495 sf, 83.93% Impervious, Inflow Depth > 7.64" for 100-Year event  
Inflow = 4.11 cfs @ 12.08 hrs, Volume= 14,330 cf  
Outflow = 4.11 cfs @ 12.08 hrs, Volume= 14,330 cf, Atten= 0%, Lag= 0.0 min  
Primary = 4.11 cfs @ 12.08 hrs, Volume= 14,330 cf  
Routed to Pond 12P : P.UIS2

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs  
Peak Elev= 146.61' @ 12.11 hrs  
Flood Elev= 150.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.45'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.45' / 141.36' S= 0.0180 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=3.97 cfs @ 12.08 hrs HW=146.47' TW=144.71' (Dynamic Tailwater)  
↑  
1=Culvert (Inlet Controls 3.97 cfs @ 5.05 fps)

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond DMH3:**

Inflow Area = 90,755 sf, 42.01% Impervious, Inflow Depth &gt; 4.24" for 100-Year event

Inflow = 9.50 cfs @ 12.15 hrs, Volume= 32,102 cf

Outflow = 9.50 cfs @ 12.15 hrs, Volume= 32,102 cf, Atten= 0%, Lag= 0.0 min

Primary = 9.50 cfs @ 12.15 hrs, Volume= 32,102 cf

Routed to Reach 10R : Wetlands System - Peppermint Brook

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 141.75' @ 12.15 hrs

Flood Elev= 149.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	139.00'	<b>18.0" Round Culvert</b> L= 33.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 139.00' / 138.50' S= 0.0152 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 1.77 sf

**Primary OutFlow** Max=9.49 cfs @ 12.15 hrs HW=141.75' TW=0.00' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 9.49 cfs @ 5.37 fps)

**Summary for Pond DMH4:**

Inflow Area = 22,985 sf, 76.88% Impervious, Inflow Depth &gt; 7.43" for 100-Year event

Inflow = 4.21 cfs @ 12.08 hrs, Volume= 14,233 cf

Outflow = 4.21 cfs @ 12.08 hrs, Volume= 14,233 cf, Atten= 0%, Lag= 0.0 min

Primary = 4.21 cfs @ 12.08 hrs, Volume= 14,233 cf

Routed to Pond 13P : P.UIS3

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 145.47' @ 12.10 hrs

Flood Elev= 146.85'

Device	Routing	Invert	Outlet Devices
#1	Primary	141.35'	<b>12.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 141.35' / 141.25' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=4.09 cfs @ 12.08 hrs HW=145.37' TW=143.49' (Dynamic Tailwater)

↑ 1=Culvert (Inlet Controls 4.09 cfs @ 5.21 fps)

**Summary for Pond DMH5:**

Inflow Area = 4,525 sf, 70.94% Impervious, Inflow Depth &gt; 7.28" for 100-Year event

Inflow = 0.82 cfs @ 12.08 hrs, Volume= 2,747 cf

Outflow = 0.82 cfs @ 12.08 hrs, Volume= 2,747 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.82 cfs @ 12.08 hrs, Volume= 2,747 cf

Routed to Pond 14P : P.UIS4

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

Peak Elev= 142.46' @ 12.08 hrs

Flood Elev= 143.90'

Device	Routing	Invert	Outlet Devices
#1	Primary	140.40'	<b>6.0" Round Culvert</b> L= 5.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 140.40' / 140.30' S= 0.0200 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.20 sf

**Primary OutFlow** Max=0.82 cfs @ 12.08 hrs HW=142.45' TW=141.25' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.82 cfs @ 4.17 fps)

**Summary for Pond DMH6: DMH6**

Inflow Area = 1,810 sf, 29.83% Impervious, Inflow Depth &gt; 5.97" for 100-Year event

Inflow = 0.29 cfs @ 12.09 hrs, Volume= 900 cf

Outflow = 0.29 cfs @ 12.09 hrs, Volume= 900 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.29 cfs @ 12.09 hrs, Volume= 900 cf

Routed to Pond DMH7 : DMH7

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 160.05' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.75'	<b>12.0" Round Culvert</b> L= 29.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.75' / 159.45' S= 0.0103 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.29 cfs @ 12.09 hrs HW=160.05' TW=159.70' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.29 cfs @ 1.46 fps)

**Summary for Pond DMH7: DMH7**

Inflow Area = 2,410 sf, 31.74% Impervious, Inflow Depth &gt; 6.06" for 100-Year event

Inflow = 0.38 cfs @ 12.09 hrs, Volume= 1,216 cf

Outflow = 0.38 cfs @ 12.09 hrs, Volume= 1,216 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.38 cfs @ 12.09 hrs, Volume= 1,216 cf

Routed to Pond DMH8 : DMH8

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 159.70' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	159.35'	<b>12.0" Round Culvert</b> L= 147.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 159.35' / 157.85' S= 0.0102 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.38 cfs @ 12.09 hrs HW=159.70' TW=148.63' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.38 cfs @ 1.58 fps)

**27164-2**

Type III 24-hr 100-Year Rainfall=8.37"

Prepared by Hancock Associates

Printed 10/14/2025

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Summary for Pond DMH8: DMH8**

Inflow Area = 5,005 sf, 37.26% Impervious, Inflow Depth &gt; 6.26" for 100-Year event

Inflow = 0.82 cfs @ 12.09 hrs, Volume= 2,610 cf

Outflow = 0.82 cfs @ 12.09 hrs, Volume= 2,610 cf, Atten= 0%, Lag= 0.0 min

Primary = 0.82 cfs @ 12.09 hrs, Volume= 2,610 cf

Routed to Pond DMH2 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 148.63' @ 12.09 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	148.10'	<b>12.0" Round Culvert</b> L= 72.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 148.10' / 142.35' S= 0.0799 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=0.82 cfs @ 12.09 hrs HW=148.63' TW=146.49' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 0.82 cfs @ 1.95 fps)

**Summary for Pond DMH9:**

Inflow Area = 45,275 sf, 3.48% Impervious, Inflow Depth &gt; 5.37" for 100-Year event

Inflow = 6.23 cfs @ 12.11 hrs, Volume= 20,244 cf

Outflow = 6.23 cfs @ 12.11 hrs, Volume= 20,244 cf, Atten= 0%, Lag= 0.0 min

Primary = 6.23 cfs @ 12.11 hrs, Volume= 20,244 cf

Routed to Pond DMH3 :

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs

Peak Elev= 147.23' @ 12.11 hrs

Flood Elev= 154.50'

Device	Routing	Invert	Outlet Devices
#1	Primary	142.38'	<b>12.0" Round Culvert</b> L= 55.0' CPP, projecting, no headwall, Ke= 0.900 Inlet / Outlet Invert= 142.38' / 139.90' S= 0.0451 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf

**Primary OutFlow** Max=6.22 cfs @ 12.11 hrs HW=147.23' TW=141.58' (Dynamic Tailwater)

↑1=Culvert (Inlet Controls 6.22 cfs @ 7.92 fps)

## Appendix VII Hydrocad Output for Recharge Volume

## Stage-Area-Storage for Pond 11P: P.UIS1

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
144.25	1,435	0	147.20	1,435	2,921
144.30	1,435	29	147.25	1,435	2,973
144.35	1,435	57	147.30	1,435	3,023
144.40	1,435	86	147.35	1,435	3,074
144.45	1,435	115	147.40	1,435	3,124
144.50	1,435	143	147.45	1,435	3,173
144.55	1,435	172	147.50	1,435	3,222
144.60	1,435	201	147.55	1,435	3,271
144.65	1,435	230	147.60	1,435	3,319
144.70	1,435	258	147.65	1,435	3,367
144.75	1,435	287	147.70	1,435	3,414
144.80	1,435	316	147.75	1,435	3,461
144.85	1,435	344	147.80	1,435	3,507
144.90	1,435	373	147.85	1,435	3,553
144.95	1,435	402	147.90	1,435	3,598
145.00	1,435	430	147.95	1,435	3,642
145.05	1,435	490	148.00	1,435	3,686
145.10	1,435	550	148.05	1,435	3,729
145.15	1,435	610	148.10	1,435	3,771
145.20	1,435	670	148.15	1,435	3,813
145.25	1,435	729	148.20	1,435	3,853
145.30	1,435	789	148.25	1,435	3,892
145.35	1,435	848	148.30	1,435	3,930
145.40	1,435	907	148.35	1,435	3,967
145.45	1,435	966	148.40	1,435	4,002
145.50	1,435	1,025	148.45	1,435	4,035
145.55	1,435	1,084	148.50	1,435	4,068
145.60	1,435	1,143	148.55	1,435	4,099
145.65	1,435	1,201	148.60	1,435	4,130
145.70	1,435	1,260	148.65	1,435	4,161
145.75	1,435	1,318	148.70	1,435	4,190
145.80	1,435	1,376	148.75	1,435	4,219
145.85	1,435	1,434	148.80	1,435	4,248
145.90	1,435	1,492	148.85	1,435	4,277
145.95	1,435	1,550	148.90	1,435	4,305
146.00	1,435	1,607	148.95	1,435	4,334
146.05	1,435	1,665	149.00	1,435	4,363
146.10	1,435	1,722	149.05	1,435	4,391
146.15	1,435	1,779	149.10	1,435	4,420
146.20	1,435	1,835	149.15	1,435	4,449
146.25	1,435	1,892	149.20	1,435	4,477
146.30	1,435	1,949	149.25	1,435	4,506
146.35	1,435	2,005	149.30	1,435	4,535
146.40	1,435	2,061	149.35	1,435	4,564
146.45	1,435	2,116	149.40	1,435	4,592
146.50	1,435	2,172	149.45	1,435	4,621
146.55	1,435	2,227	149.50	1,435	4,650
146.60	1,435	2,282	149.55	1,435	4,678
146.65	1,435	2,337	149.60	1,435	4,707
146.70	1,435	2,392	149.65	1,435	4,736
146.75	1,435	2,446	149.70	1,435	4,764
146.80	1,435	2,500	149.75	1,435	4,793
146.85	1,435	2,554			
146.90	1,435	2,607			
146.95	1,435	2,660			
147.00	1,435	2,713			
147.05	1,435	2,766			
147.10	1,435	2,818			
147.15	1,435	2,870			

## Stage-Area-Storage for Pond 12P: P.UIS2

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
140.50	<b>1,271</b>	0	143.45	1,271	2,580
140.55	1,271	25	143.50	1,271	2,626
140.60	1,271	51	143.55	1,271	2,670
140.65	1,271	76	143.60	1,271	2,715
140.70	1,271	102	143.65	1,271	2,759
140.75	1,271	127	143.70	1,271	2,803
140.80	1,271	153	143.75	1,271	2,846
140.85	1,271	178	143.80	1,271	2,889
140.90	1,271	203	143.85	1,271	2,932
140.95	1,271	229	143.90	1,271	2,974
141.00	1,271	254	143.95	1,271	3,016
141.05	1,271	280	144.00	1,271	3,057
141.10	1,271	305	144.05	1,271	3,098
141.15	1,271	331	144.10	1,271	3,138
141.20	1,271	356	144.15	1,271	3,178
141.25	1,271	381	144.20	1,271	3,217
141.30	1,271	434	144.25	1,271	3,256
141.35	1,271	487	144.30	1,271	3,294
141.40	1,271	540	144.35	1,271	3,331
141.45	1,271	593	144.40	1,271	3,368
141.50	1,271	645	144.45	1,271	3,403
141.55	1,271	698	144.50	1,271	3,438
141.60	1,271	750	144.55	1,271	3,472
141.65	1,271	802	144.60	1,271	3,504
141.70	1,271	854	144.65	1,271	3,535
141.75	1,271	906	144.70	1,271	3,565
141.80	1,271	958	144.75	1,271	3,593
141.85	1,271	1,010	144.80	1,271	3,621
141.90	1,271	1,062	144.85	1,271	3,649
141.95	1,271	1,113	144.90	1,271	3,676
142.00	1,271	1,165	144.95	1,271	3,702
142.05	1,271	1,216	145.00	1,271	3,728
142.10	1,271	1,267	145.05	1,271	3,753
142.15	1,271	1,318	145.10	1,271	3,779
142.20	1,271	1,369	145.15	1,271	3,804
142.25	1,271	1,420	145.20	1,271	3,829
142.30	1,271	1,471	145.25	1,271	3,855
142.35	1,271	1,521	145.30	1,271	3,880
142.40	1,271	1,571	145.35	1,271	3,906
142.45	1,271	1,622	145.40	1,271	3,931
142.50	1,271	1,672	145.45	1,271	3,957
142.55	1,271	1,721	145.50	1,271	3,982
142.60	1,271	1,771	145.55	1,271	4,007
142.65	1,271	1,820	145.60	1,271	4,033
142.70	1,271	1,870	145.65	1,271	4,058
142.75	1,271	1,919	145.70	1,271	4,084
142.80	1,271	1,967	145.75	1,271	4,109
142.85	1,271	2,016	145.80	1,271	4,135
142.90	1,271	2,064	145.85	1,271	4,160
142.95	1,271	2,113	145.90	1,271	4,185
143.00	1,271	2,161	145.95	1,271	4,211
143.05	1,271	2,208	146.00	1,271	<b>4,236</b>
143.10	1,271	2,256			
143.15	1,271	2,303			
143.20	1,271	2,350			
143.25	1,271	<b>2,397</b>			
143.30	1,271	2,443			
143.35	1,271	2,489			
143.40	1,271	2,535			

## Stage-Area-Storage for Pond 13P: P.UIS3

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
140.50	<b>1,924</b>	0	143.45	1,924	<b>3,944</b>
140.55	1,924	38	143.50	1,924	4,014
140.60	1,924	77	143.55	1,924	4,082
140.65	1,924	115	143.60	1,924	4,150
140.70	1,924	154	143.65	1,924	4,218
140.75	1,924	192	143.70	1,924	4,285
140.80	1,924	231	143.75	1,924	4,351
140.85	1,924	269	143.80	1,924	4,417
140.90	1,924	308	143.85	1,924	4,482
140.95	1,924	346	143.90	1,924	4,546
141.00	1,924	385	143.95	1,924	4,610
141.05	1,924	423	144.00	1,924	4,673
141.10	1,924	462	144.05	1,924	4,736
141.15	1,924	500	144.10	1,924	4,797
141.20	1,924	539	144.15	1,924	4,858
141.25	1,924	577	144.20	1,924	4,918
141.30	1,924	658	144.25	1,924	4,976
141.35	1,924	739	144.30	1,924	5,034
141.40	1,924	820	144.35	1,924	5,091
141.45	1,924	901	144.40	1,924	5,147
141.50	1,924	981	144.45	1,924	5,201
141.55	1,924	1,062	144.50	1,924	5,255
141.60	1,924	1,142	144.55	1,924	5,306
141.65	1,924	1,222	144.60	1,924	5,355
141.70	1,924	1,302	144.65	1,924	5,402
141.75	1,924	1,382	144.70	1,924	5,447
141.80	1,924	1,461	144.75	1,924	5,490
141.85	1,924	1,540	144.80	1,924	5,533
141.90	1,924	1,620	144.85	1,924	5,574
141.95	1,924	1,699	144.90	1,924	5,615
142.00	1,924	1,778	144.95	1,924	5,655
142.05	1,924	1,856	145.00	1,924	5,694
142.10	1,924	1,935	145.05	1,924	5,732
142.15	1,924	2,013	145.10	1,924	5,771
142.20	1,924	2,091	145.15	1,924	5,809
142.25	1,924	2,168	145.20	1,924	5,848
142.30	1,924	2,246	145.25	1,924	5,886
142.35	1,924	2,323	145.30	1,924	5,925
142.40	1,924	2,400	145.35	1,924	5,963
142.45	1,924	2,477	145.40	1,924	6,002
142.50	1,924	2,554	145.45	1,924	6,040
142.55	1,924	2,630	145.50	1,924	6,079
142.60	1,924	2,706	145.55	1,924	6,117
142.65	1,924	2,781	145.60	1,924	6,156
142.70	1,924	2,857	145.65	1,924	6,194
142.75	1,924	2,932	145.70	1,924	6,233
142.80	1,924	3,007	145.75	1,924	6,271
142.85	1,924	3,081	145.80	1,924	6,309
142.90	1,924	3,155	145.85	1,924	6,348
142.95	1,924	3,229	145.90	1,924	6,386
143.00	1,924	3,302	145.95	1,924	6,425
143.05	1,924	3,375	146.00	1,924	<b>6,463</b>
143.10	1,924	3,448			
143.15	1,924	3,520			
143.20	1,924	3,592			
143.25	1,924	3,663			
143.30	1,924	3,734			
143.35	1,924	3,805			
143.40	1,924	3,875			

**27164-1****Type III 24-hr 100-Year Rainfall=8.37"**

Printed 3/7/2025

Prepared by Hancock Associates

HydroCAD® 10.20-3h s/n 00711 © 2024 HydroCAD Software Solutions LLC

**Stage-Area-Storage for Pond 14P: P.UIS4**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
139.80	<b>364</b>	0	140.98	364	247
139.82	364	3	141.00	364	252
139.84	364	6	141.02	364	256
139.86	364	9	141.04	364	261
139.88	364	12	141.06	364	266
139.90	364	15	141.08	364	270
139.92	364	17	<b>141.10</b>	<b>364</b>	<b>275</b>
139.94	364	20	141.12	364	279
139.96	364	23	141.14	364	284
139.98	364	26	141.16	364	288
140.00	364	29	141.18	364	292
140.02	364	32	141.20	364	297
140.04	364	35	141.22	364	301
140.06	364	38	141.24	364	305
140.08	364	41	141.26	364	309
140.10	364	44	141.28	364	313
140.12	364	47	141.30	364	317
140.14	364	50	141.32	364	321
140.16	364	52	141.34	364	325
140.18	364	55	141.36	364	329
140.20	364	58	141.38	364	332
140.22	364	61	141.40	364	336
140.24	364	64	141.42	364	340
140.26	364	67	141.44	364	343
140.28	364	70	141.46	364	346
140.30	364	73	141.48	364	350
140.32	364	78	141.50	364	353
140.34	364	84	141.52	364	356
140.36	364	89	141.54	364	359
140.38	364	94	141.56	364	362
140.40	364	100	141.58	364	365
140.42	364	105	141.60	364	368
140.44	364	110	141.62	364	371
140.46	364	116	141.64	364	374
140.48	364	121	141.66	364	377
140.50	364	126	141.68	364	380
140.52	364	132	141.70	364	383
140.54	364	137	141.72	364	386
140.56	364	142	141.74	364	389
140.58	364	147	141.76	364	392
140.60	364	153	141.78	364	395
140.62	364	158	141.80	364	398
140.64	364	163	141.82	364	401
140.66	364	168	141.84	364	403
140.68	364	173	141.86	364	406
140.70	364	178	141.88	364	409
140.72	364	183	141.90	364	412
140.74	364	188	141.92	364	415
140.76	364	193	141.94	364	418
140.78	364	198	141.96	364	421
140.80	364	203	141.98	364	424
140.82	364	208	142.00	364	427
140.84	364	213	142.02	364	430
140.86	364	218	142.04	364	433
140.88	364	223	142.06	364	435
140.90	364	228	142.08	364	438
140.92	364	233	142.10	364	441
140.94	364	237	142.12	364	<b>444</b>
140.96	364	242			

## Appendix VIII Water Quality Sizing Information

**CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION  
BASED ON THE RATIONAL RAINFALL METHOD**

**2041 BRIDGE STREET  
DRACUT, MA**

Area	<b>0.52 ac</b>	Unit Site Designation	<b>P.DMH1</b>
Weighted C	<b>0.9</b>	Rainfall Station #	<b>67</b>
$t_c$	<b>6 min</b>		
CDS Model	<b>1515-3</b>	CDS Treatment Capacity	<b>1.0 cfs</b>

<u>Rainfall Intensity<sup>1</sup> (in/hr)</u>	<u>Percent Rainfall Volume<sup>1</sup></u>	<u>Cumulative Rainfall Volume</u>	<u>Total Flowrate (cfs)</u>	<u>Treated Flowrate (cfs)</u>	<u>Incremental Removal (%)</u>
0.08	41.0%	41.0%	0.04	0.04	38.8
0.16	23.9%	64.9%	0.08	0.08	22.0
0.24	11.5%	76.5%	0.11	0.11	10.3
0.32	7.4%	83.9%	0.15	0.15	6.5
0.40	4.4%	88.3%	0.19	0.19	3.8
0.48	2.9%	91.2%	0.23	0.23	2.4
0.56	1.8%	93.0%	0.26	0.26	1.4
0.64	1.2%	94.2%	0.30	0.30	0.9
0.72	1.6%	95.8%	0.34	0.34	1.2
0.80	0.8%	96.6%	0.38	0.38	0.6
1.00	0.6%	97.1%	0.47	0.47	0.4
1.40	1.4%	98.6%	0.66	0.66	0.8
1.80	0.9%	99.5%	0.85	0.85	0.4
2.20	0.5%	100.0%	1.04	1.00	0.1
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
					89.4

Removal Efficiency Adjustment<sup>2</sup> = **0.0%**

Predicted % Annual Rainfall Treated = **100.0%**

**Predicted Net Annual Load Removal Efficiency = 89.4%**

1 - Based on 7 years of data from NCDC station #3276, Groveland, Essex County, MA

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

**CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION  
BASED ON THE RATIONAL RAINFALL METHOD**

**2041 BRIDGE STREET  
DRACUT, MA**

Area	<b>0.56 ac</b>	Unit Site Designation	<b>P.DMH2</b>
Weighted C	<b>0.9</b>	Rainfall Station #	<b>67</b>
$t_c$	<b>6 min</b>		
CDS Model	<b>1515-3</b>	CDS Treatment Capacity	<b>1.0 cfs</b>

<u>Rainfall Intensity<sup>1</sup> (in/hr)</u>	<u>Percent Rainfall Volume<sup>1</sup></u>	<u>Cumulative Rainfall Volume</u>	<u>Total Flowrate (cfs)</u>	<u>Treated Flowrate (cfs)</u>	<u>Incremental Removal (%)</u>
0.08	41.0%	41.0%	0.04	0.04	38.8
0.16	23.9%	64.9%	0.08	0.08	21.9
0.24	11.5%	76.5%	0.12	0.12	10.3
0.32	7.4%	83.9%	0.16	0.16	6.4
0.40	4.4%	88.3%	0.20	0.20	3.7
0.48	2.9%	91.2%	0.24	0.24	2.3
0.56	1.8%	93.0%	0.28	0.28	1.4
0.64	1.2%	94.2%	0.32	0.32	0.9
0.72	1.6%	95.8%	0.36	0.36	1.2
0.80	0.8%	96.6%	0.41	0.41	0.5
1.00	0.6%	97.1%	0.51	0.51	0.4
1.40	1.4%	98.6%	0.71	0.71	0.7
1.80	0.9%	99.5%	0.91	0.91	0.3
2.20	0.5%	100.0%	1.11	1.00	0.1
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
					88.9

Removal Efficiency Adjustment<sup>2</sup> = **0.0%**

Predicted % Annual Rainfall Treated = **99.9%**

**Predicted Net Annual Load Removal Efficiency = 88.9%**

1 - Based on 7 years of data from NCDC station #3276, Groveland, Essex County, MA

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

**CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION  
BASED ON THE RATIONAL RAINFALL METHOD**

**2041 BRIDGE STREET  
DRACUT, MA**

Area	<b>0.53 ac</b>	Unit Site Designation	<b>P.DMH4</b>
Weighted C	<b>0.9</b>	Rainfall Station #	<b>67</b>
$t_c$	<b>6 min</b>		
CDS Model	<b>1515-3</b>	CDS Treatment Capacity	<b>1.0 cfs</b>

<u>Rainfall Intensity<sup>1</sup> (in/hr)</u>	<u>Percent Rainfall Volume<sup>1</sup></u>	<u>Cumulative Rainfall Volume</u>	<u>Total Flowrate (cfs)</u>	<u>Treated Flowrate (cfs)</u>	<u>Incremental Removal (%)</u>
0.08	41.0%	41.0%	0.04	0.04	38.8
0.16	23.9%	64.9%	0.08	0.08	22.0
0.24	11.5%	76.5%	0.11	0.11	10.3
0.32	7.4%	83.9%	0.15	0.15	6.4
0.40	4.4%	88.3%	0.19	0.19	3.7
0.48	2.9%	91.2%	0.23	0.23	2.4
0.56	1.8%	93.0%	0.27	0.27	1.4
0.64	1.2%	94.2%	0.30	0.30	0.9
0.72	1.6%	95.8%	0.34	0.34	1.2
0.80	0.8%	96.6%	0.38	0.38	0.6
1.00	0.6%	97.1%	0.47	0.47	0.4
1.40	1.4%	98.6%	0.66	0.66	0.8
1.80	0.9%	99.5%	0.85	0.85	0.4
2.20	0.5%	100.0%	1.04	1.00	0.1
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
					89.4

Removal Efficiency Adjustment<sup>2</sup> = **0.0%**

Predicted % Annual Rainfall Treated = **100.0%**

**Predicted Net Annual Load Removal Efficiency = 89.4%**

1 - Based on 7 years of data from NCDC station #3276, Groveland, Essex County, MA

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

**CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION  
BASED ON THE RATIONAL RAINFALL METHOD**

**2041 BRIDGE STREET  
DRACUT, MA**

Area	<b>0.10 ac</b>	Unit Site Designation	<b>P.DMH5</b>
Weighted C	<b>0.9</b>	Rainfall Station #	<b>67</b>
$t_c$	<b>6 min</b>		
CDS Model	<b>1515-3</b>	CDS Treatment Capacity	<b>1.0 cfs</b>

<u>Rainfall Intensity<sup>1</sup> (in/hr)</u>	<u>Percent Rainfall Volume<sup>1</sup></u>	<u>Cumulative Rainfall Volume</u>	<u>Total Flowrate (cfs)</u>	<u>Treated Flowrate (cfs)</u>	<u>Incremental Removal (%)</u>
0.08	41.0%	41.0%	0.01	0.01	39.7
0.16	23.9%	64.9%	0.01	0.01	23.0
0.24	11.5%	76.5%	0.02	0.02	11.0
0.32	7.4%	83.9%	0.03	0.03	7.1
0.40	4.4%	88.3%	0.04	0.04	4.2
0.48	2.9%	91.2%	0.04	0.04	2.7
0.56	1.8%	93.0%	0.05	0.05	1.7
0.64	1.2%	94.2%	0.06	0.06	1.1
0.72	1.6%	95.8%	0.07	0.07	1.5
0.80	0.8%	96.6%	0.07	0.07	0.7
1.00	0.6%	97.1%	0.09	0.09	0.5
1.40	1.4%	98.6%	0.13	0.13	1.3
1.80	0.9%	99.5%	0.17	0.17	0.8
2.20	0.5%	100.0%	0.20	0.20	0.4
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
0.00	0.0%	100.0%	0.00	0.00	0.0
					95.7

Removal Efficiency Adjustment<sup>2</sup> = **0.0%**

Predicted % Annual Rainfall Treated = **100.0%**


**Predicted Net Annual Load Removal Efficiency = 95.7%**

1 - Based on 7 years of data from NCDC station #3276, Groveland, Essex County, MA

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

## Appendix IX Mounding Analysis

## Groundwater Mounding Analysis (Hantush's Method using Glover's Solution)



COMPANY: Hancock Associates

PROJECT: 27164-P.UIS1

ANALYST: Morgan Seale

DATE: 9/12/2024 TIME: 11:23:01 AM

### INPUT PARAMETERS

Application rate: 1.32 c.ft/day/sq. ft

Duration of application: 1 day

Total simulation time: 4 day

Fillable porosity: 0.28

Hydraulic conductivity: 20.48 ft/day

Initial saturated thickness: 5.5 ft

Length of application area: 63.06 ft

Width of application area: 22.75 ft

No constant head boundary used

Groundwater mounding @

  X coordinate: 0 ft


  Y coordinate: 0 ft

Total volume applied: 1893.692 cft

### MODEL RESULTS

Time (day)	Mound Height (ft)
0	0
0	0.06
0	0.21
0.1	0.42
0.2	0.62
0.2	0.82
0.3	1.03
0.4	1.25
0.5	1.48
0.7	1.76
1	2.13
1	1.99
1.1	1.7
1.3	1.41
1.5	1.18
1.7	0.99
1.9	0.84
2.2	0.71
2.6	0.59
3.1	0.48
4	0.36

## Groundwater Mounding Analysis (Hantush's Method using Glover's Solution)



COMPANY: Hancock Associates

PROJECT: 27164-P.UIS2

ANALYST: Morgan Seale

DATE: 9/12/2024 TIME: 11:23:55 AM

### INPUT PARAMETERS

Application rate: 1.88 c.ft/day/sq. ft

Duration of application: 1 day

Total simulation time: 4 day

Fillable porosity: 0.28

Hydraulic conductivity: 20.48 ft/day

Initial saturated thickness: 6 ft

Length of application area: 55.89 ft

Width of application area: 22.75 ft

No constant head boundary used

Groundwater mounding @

  X coordinate: 0 ft


  Y coordinate: 0 ft

Total volume applied: 2390.415 cft

### MODEL RESULTS

Time (day)	Mound Height (ft)
0	0
0	0.09
0	0.3
0.1	0.59
0.2	0.87
0.2	1.14
0.3	1.42
0.4	1.7
0.5	2
0.7	2.34
1	2.8
1	2.59
1.1	2.18
1.3	1.76
1.5	1.45
1.7	1.21
1.9	1.01
2.2	0.85
2.6	0.7
3.1	0.56
4	0.42

## Groundwater Mounding Analysis (Hantush's Method using Glover's Solution)



COMPANY: Hancock Associates

PROJECT: 27164-P.UIS3

ANALYST: Morgan Seale

DATE: 9/12/2024 TIME: 11:25:10 AM

### INPUT PARAMETERS

Application rate: 2.05 c.ft/day/sq. ft

Duration of application: 1 day

Total simulation time: 4 day

Fillable porosity: 0.28

Hydraulic conductivity: 20.48 ft/day

Initial saturated thickness: 5.5 ft

Length of application area: 84.57 ft

Width of application area: 22.75 ft

No constant head boundary used

Groundwater mounding @

  X coordinate: 0 ft


  Y coordinate: 0 ft

Total volume applied: 3944.133 cft

### MODEL RESULTS

Time (day)	Mound Height (ft)
0	0
0	0.1
0	0.33
0.1	0.65
0.2	0.97
0.2	1.29
0.3	1.61
0.4	1.97
0.5	2.36
0.7	2.84
1	3.51
1	3.3
1.1	2.89
1.3	2.46
1.5	2.11
1.7	1.83
1.9	1.58
2.2	1.35
2.6	1.14
3.1	0.94
4	0.72

## Groundwater Mounding Analysis (Hantush's Method using Glover's Solution)



COMPANY: Hancock Associates

PROJECT: 27164-P.UIS4

ANALYST: Morgan Seale

DATE: 9/12/2024 TIME: 11:25:22 AM

### INPUT PARAMETERS

Application rate: 0.75 c.ft/day/sq. ft

Duration of application: 1 day

Total simulation time: 4 day

Fillable porosity: 0.28

Hydraulic conductivity: 20.48 ft/day

Initial saturated thickness: 6.2 ft

Length of application area: 24.56 ft

Width of application area: 14.83 ft

No constant head boundary used

Groundwater mounding @

  X coordinate: 0 ft

  Y coordinate: 0 ft

Total volume applied: 273.1686 cft

### MODEL RESULTS

Time (day)	Mound Height (ft)
0	0
0	0.04
0	0.11
0.1	0.18
0.2	0.25
0.2	0.3
0.3	0.34
0.4	0.38
0.5	0.43
0.7	0.47
1	0.53
1	0.44
1.1	0.32
1.3	0.24
1.5	0.19
1.7	0.15
1.9	0.12
2.2	0.1
2.6	0.08
3.1	0.06
4	0.05

## Appendix X Pipe Velocities

## Pipe Calculations

Project: 27164

Location: 2041 Bridge Street, Dracut, MA

Design Storm (Years):

25 yr

Duration  
24 hours

Depth  
5.83 in

Designed By:

MJS

Date:

8/8/2025

Checked BY:

BGG

Revised:

10/7/2025

Note: Pipe flows are based on HydroCAD outlet controls report of max flow through controlling outlet.

LOCATION		RUNOFF (cfs)	FLOW IN PIPE			FULL FLOW		DESIGN FLOW					
From	To	Design Flow	Diam (In.)	Length (Ft.)	Slope (Ft./Ft.)	Manning Coeff.	Capacity (Cfs)	Velocity (Fps)	Depth (Ft.)	Velocity (Fps.)	Angle	Hydraulic Radius	PIPE % FULL
PCB1 -->PDMH1		1.70	<b>12</b>	5	0.0500	0.012	8.6	11.0	0.31	<b>8.8</b>	2.36	0.18	20
PCB2-->PDMH1		0.70	<b>12</b>	5	0.0500	0.012	8.6	11.0	0.23	<b>7.4</b>	2.00	0.14	8
PDMH1 -->PUIS1		2.40	<b>12</b>	4	0.0225	0.012	5.8	7.4	0.44	<b>7.0</b>	2.90	0.23	41
POCS1-->PDMH11		0.39	<b>12</b>	13	0.0154	0.012	4.8	6.1	0.23	<b>4.1</b>	2.00	0.14	8
PDMH11-->PFES1		2.74	<b>18</b>	33	0.0100	0.012	11.4	6.4	0.50	<b>5.3</b>	2.46	0.28	24
PDCB1-->PDMH10		2.74	<b>12</b>	131	0.0550	0.012	9.1	11.5	0.37	<b>9.9</b>	2.62	0.20	30
PDMH10-->PDMH11		2.75	<b>12</b>	43	0.0140	0.012	4.6	5.8	0.56	<b>6.1</b>	2.90	0.27	60
PDMH2-->PUIS2		2.85	<b>12</b>	5	0.0180	0.012	5.2	6.6	0.53	<b>6.8</b>	3.02	0.26	55
P.OCS2-->PDMH3		1.55	<b>12</b>	7	0.0143	0.012	4.6	5.9	0.40	<b>5.2</b>	2.74	0.21	34
PDMH3-->PFES2		4.76	<b>18</b>	33	0.0152	0.012	14.1	7.9	0.59	<b>7.1</b>	2.71	0.32	34
PDCB2-->PDMH9		3.47	<b>12</b>	78	0.0450	0.012	8.2	10.4	0.45	<b>9.8</b>	2.94	0.23	42
PDMH9-->PDMH3		3.47	<b>12</b>	55	0.0450	0.012	8.2	10.4	0.45	<b>9.8</b>	2.94	0.23	42
PCB3-->PDMH4		1.66	<b>8</b>	5	0.0200	0.012	1.9	5.3	0.49	<b>6.0</b>	2.16	0.20	87
PCB4-->PDMH4		1.19	<b>8</b>	6	0.0167	0.012	1.7	4.8	0.42	<b>5.3</b>	2.62	0.19	70
PDMH4-->PUIS3		2.75	<b>12</b>	5	0.0200	0.012	5.5	6.9	0.50	<b>6.9</b>	3.14	0.25	50
POC3-->PDMH3		0.22	<b>12</b>	31	0.0355	0.012	7.3	9.2	0.20	<b>5.7</b>	1.85	0.12	3
PCB5-->PDMH5		0.51	<b>6</b>	5	0.0200	0.012	0.9	4.4	0.27	<b>4.5</b>	2.98	0.13	57
PDMH5-->PUIS4		0.51	<b>6</b>	5	0.0200	0.012	0.9	4.4	0.27	<b>4.5</b>	2.98	0.13	57
POC4-->PFES3		0.42	<b>12</b>	17	0.0150	0.012	4.7	6.0	0.24	<b>4.1</b>	2.05	0.14	9
PUIS1-->POCS1		0.39	<b>12</b>	10	0.0100	0.012	3.9	4.9	0.24	<b>3.3</b>	2.05	0.14	10
PAD1-->PDMH13		0.08	<b>12</b>	7	0.0143	0.012	4.6	5.9	0.19	<b>3.4</b>	1.80	0.11	2
PDMH13-->PDMH12		0.08	<b>12</b>	105	0.0960	0.012	12.0	15.2	0.18	<b>8.8</b>	1.75	0.11	1

PAD2-->PDMH6	0.18	<b>12</b>	12	0.0125	0.012	4.3	5.5	0.21	<b>3.5</b>	1.90	0.13	4
PAD3-->PDMH7	0.18	<b>12</b>	10	0.0100	0.012	3.9	4.9	0.21	<b>3.2</b>	1.90	0.13	5
PDMH6-->PDMH7	0.18	<b>12</b>	32	0.0090	0.012	3.7	4.7	0.21	<b>3.0</b>	1.90	0.13	5
PAD5-->PDMH12	0.21	<b>12</b>	11	0.0100	0.012	3.9	4.9	0.21	<b>3.2</b>	1.90	0.13	5
PDMH12-->PDMH2	0.29	<b>12</b>	210	0.0220	0.012	5.7	7.3	0.21	<b>4.7</b>	1.90	0.13	5
PDMH7-->PDMH8	0.24	<b>12</b>	151	0.0100	0.012	3.9	4.9	0.22	<b>3.2</b>	1.95	0.13	6
PDMH8-->PDMH2	0.52	<b>12</b>	70	0.0830	0.012	11.1	14.1	0.21	<b>9.1</b>	1.90	0.13	5
PUIS2--OCS2	1.15	<b>12</b>	5	0.0180	0.012	5.2	6.6	0.32	<b>5.3</b>	2.41	0.18	22
PUIS3-->POCS3	0.22	<b>12</b>	4	0.0250	0.012	6.1	7.8	0.20	<b>4.7</b>	1.85	0.12	4
PUIS4--OCS4	0.42	<b>12</b>	4	0.0250	0.012	6.1	7.8	0.22	<b>5.0</b>	1.95	0.13	7
PAD4-DMH8	0.28	<b>12</b>	8	0.0125	0.012	4.3	5.5	0.22	<b>3.5</b>	1.95	0.13	7
PCB6-DMH10	0.54	<b>12</b>	4	0.0250	0.012	6.1	7.8	0.24	<b>5.3</b>	2.05	0.14	9

## Appendix XI Operations and Maintenance Log

**2041 Bridge Street, Dracut, MA – Post Construction Maintenance**

Operations and Maintenance Log

Inspections for Year: \_\_\_\_\_

Structural Best Management Practice (Frequency)	Action	Date Completed	Completed By	Comments
Deep Sump Hooded Catch Basin– Inspect/clean four times per year. Clean when sump is 50% full.	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
Stormtech Chambers– Inspect four times per year. Clean per manufacturer's requirements.	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
	Inspect/ Clean			
Roof Drain Leaders – Inspect/clean twice per year.	Inspect/Clean			
	Inspect/Clean			
Vegetated Areas Maintenance – Inspect twice per year. Maintain as required.	Inspect			
	Inspect			

(1) Refer to the Massachusetts Stormwater Management, Volume Two: Stormwater Technical Handbook (March 1997) for recommendations regarding frequency for inspection and maintenance of specific BMP's.

(2) Inspections to be conducted by qualified professional such as an environmental scientist or civil engineer.

Limited or no use of sodium chloride salts, fertilizers or pesticides recommended.

Other notes: (Included deviations from: Con Comm. Order of Conditions, PB Approval, Construction Sequence and Approved Plan).

Stormwater Control Manager: \_\_\_\_\_

# Isolator® Row Plus

## O&M Manual



# The Isolator® Row Plus

## Introduction

An important component of any Stormwater Pollution Prevention Plan is inspection and maintenance. The StormTech Isolator Row Plus is a technique to inexpensively enhance Total Suspended Solids (TSS), Total Phosphorus (TP), Total Petroleum Hydrocarbons (TPH) and Total Nitrogen (TN) removal with easy access for inspection and maintenance.

## The Isolator Row Plus

The Isolator Row Plus is a row of StormTech chambers, either SC-160, SC-310, DC-780, SC-800, MC-3500, MC-4500 or MC-7200 models, are lined with filter fabric and connected to a closely located manhole for easy access. The fabric lined chambers provide for sediment settling and filtration as stormwater rises in the Isolator Row Plus and passes through the filter fabric. The open bottom chambers allow stormwater to flow vertically out of the chambers. Sediments are captured in the Isolator Row Plus protecting the adjacent stone and chambers storage areas from sediment accumulation.

ADS Isolator Row and Plus fabric are placed between the stone and the Isolator Row Plus chambers. The woven geotextile provides a media for stormwater filtration, a durable surface for maintenance, prevents scour of the underlying stone and remains intact during high pressure jetting.

The Isolator Row Plus is designed to capture the “first flush” runoff and offers the versatility to be sized on a volume basis or a flow-rate basis. An upstream manhole provides access to the Isolator Row Plus and includes a high/low concept such that stormwater flow rates or volumes that exceed the capacity of the Isolator Row Plus bypass through a manifold to the other chambers. This is achieved with an elevated bypass manifold or a high-flow weir. This creates a differential between the Isolator Row Plus row of chambers and the manifold to the rest of the system, thus allowing for settlement time in the Isolator Row Plus. After Stormwater flows through the Isolator Row Plus and into the rest of the chamber system it is either exfiltrated into the soils below or passed at a controlled rate through an outlet manifold and outlet control structure.

The Isolator Row Plus Flamp™ is a flared end ramp apparatus attached to the inlet pipe on the inside of the chamber end cap. The FLAMP provides a smooth transition from pipe invert to fabric bottom. It is configured to improve chamber function performance by enhancing outflow of solid debris that would otherwise collect at the chamber's end, or more difficult to remove and require confined space entry into the chamber area. It also serves to improve the fluid and solid flow into the access pipe during maintenance and cleaning and to guide cleaning and inspection equipment back into the inlet pipe when complete.

The Isolator Row Plus may be part of a treatment train system. The treatment train design and pretreatment device selection by the design engineer is often driven by regulatory requirements. Whether pretreatment is used or not, StormTech recommend using the Isolator Row Plus to minimize maintenance requirements and maintenance costs.


**Note:** See the StormTech Design Manual for detailed information on designing inlets for a StormTech system, including the Isolator Row Plus.



Looking down the Isolator Row Plus from the manhole opening, ADS Plus Fabric is shown between the chamber and stone base.



StormTech Isolator Row Plus with Overflow Structure (not to scale)



# Isolator Row Plus Inspection/Maintenance

## Inspection

The frequency of inspection and maintenance varies by location. A routine inspection schedule needs to be established for each individual location based upon site specific variables. The type of land use (i.e. industrial, commercial, residential), anticipated pollutant load, percent imperviousness, climate, etc. all play a critical role in determining the actual frequency of inspection and maintenance practices.

At a minimum, StormTech recommends annual inspections. Initially, the Isolator Row Plus should be inspected every 6 months for the first year of operation. For subsequent years, the inspection should be adjusted based upon previous observation of sediment deposition.

The Isolator Row Plus incorporates a combination of standard manhole(s) and strategically located inspection ports (as needed). The inspection ports allow for easy access to the system from the surface, eliminating the need to perform a confined space entry for inspection purposes.

If upon visual inspection it is found that sediment has accumulated, a stadia rod should be inserted to determine the depth of sediment. When the average depth of sediment exceeds 3" (75 mm) throughout the length of the Isolator Row Plus, clean-out should be performed.

## Maintenance


The Isolator Row Plus was designed to reduce the cost of periodic maintenance. By "isolating" sediments to just one row, costs are dramatically reduced by eliminating the need to clean out each row of the entire storage bed. If inspection indicates the potential need for maintenance, access is provided

via a manhole(s) located on the end(s) of the row for cleanout. If entry into the manhole is required, please follow local and OSHA rules for a confined space entry.

Maintenance is accomplished with the JetVac process. The JetVac process utilizes a high pressure water nozzle to propel itself down the Isolator Row Plus while scouring and suspending sediments. As the nozzle is retrieved, the captured pollutants are flushed back into the manhole for vacuuming. Most sewer and pipe maintenance companies have vacuum/JetVac combination vehicles. Selection of an appropriate JetVac nozzle will improve maintenance efficiency. Fixed nozzles designed for culverts or large diameter pipe cleaning are preferable. Rear facing jets with an effective spread of at least 45° are best. StormTech recommends a maximum nozzle pressure of 2000 psi be utilized during cleaning. JetVac reels can vary in length. For ease of maintenance, ADS recommends Isolator Row Plus lengths up to 200' (61 m). **The JetVac process shall only be performed on StormTech Isolator Row Plus that have ADS Plus Fabric (as specified by StormTech) over their angular base stone.**



StormTech Isolator Row Plus (not to scale)



# Isolator Row Plus Step By Step Maintenance Procedures

## Step 1

Inspect Isolator Row Plus for sediment.

- A) Inspection ports (if present)
  - i. Remove lid from floor box frame
  - ii. Remove cap from inspection riser
  - iii. Using a flashlight and stadia rod, measure depth of sediment and record results on maintenance log.
  - iv. If sediment is at or above 3 inch depth, proceed to Step 2. If not, proceed to Step 3.
- B) All Isolator Row Plus
  - i. Remove cover from manhole at upstream end of Isolator Row Plus
  - ii. Using a flashlight, inspect down Isolator Row Plus through outlet pipe
    - 1. Mirrors on poles or cameras may be used to avoid a confined space entry
    - 2. Follow OSHA regulations for confined space entry if entering manhole
  - iii. If sediment is at or above the lower row of sidewall holes (approximately 3 inches), proceed to Step 2.
    - 2.
  - If not, proceed to Step 3.

## Step 2

Clean out Isolator Row Plus using the JetVac process.


- A) A fixed floor cleaning nozzle with rear facing nozzle spread of 45 inches or more is preferable
- B) Apply multiple passes of JetVac until backflush water is clean
- C) Vacuum manhole sump as required

## Step 3

Replace all caps, lids and covers, record observations and actions.

## Step 4

Inspect & clean catch basins and manholes upstream of the StormTech system.



## Sample Maintenance Log

Date	Stadia Rod Readings		Sedi- ment Depth (1)-(2)	Observations/Actions	Inspector
	Fixed point to chamber bottom (1)	Fixed point to top of sediment (2)			
3/15/11	6.3 ft	none		New installation. Fixed point is CI frame at grade	DJM
9/24/11		6.2	0.1 ft	Some grit felt	SM
6/20/13		5.8	0.5 ft	Mucky feel, debris visible in manhole and in Isolator Row Plus, maintenance due	NV
7/7/13	6.3 ft		0	System jetted and vacuumed	DJM

adspipe.com

800-821-6710



## CDS Guide

### Operation, Design, Performance and Maintenance



## CDS®

Using patented continuous deflective separation technology, the CDS system screens, separates and traps debris, sediment, and oil and grease from stormwater runoff. The indirect screening capability of the system allows for 100% removal of floatables and neutrally buoyant material without blinding. Flow and screening controls physically separate captured solids, and minimize the re-suspension and release of previously trapped pollutants. Inline units can treat up to 6 cfs, and internally bypass flows in excess of 50 cfs (1416 L/s). Available precast or cast-in-place, offline units can treat flows from 1 to 300 cfs (28.3 to 8495 L/s). The pollutant removal capacity of the CDS system has been proven in lab and field testing.


## Operation Overview

Stormwater enters the diversion chamber where the diversion weir guides the flow into the unit's separation chamber and pollutants are removed from the flow. All flows up to the system's treatment design capacity enter the separation chamber and are treated.

Swirl concentration and screen deflection force floatables and solids to the center of the separation chamber where 100% of floatables and neutrally buoyant debris larger than the screen apertures are trapped.

Stormwater then moves through the separation screen, under the oil baffle and exits the system. The separation screen remains clog free due to continuous deflection.

During the flow events exceeding the treatment design capacity, the diversion weir bypasses excessive flows around the separation chamber, so captured pollutants are retained in the separation cylinder.



## Design Basics

There are three primary methods of sizing a CDS system. The Water Quality Flow Rate Method determines which model size provides the desired removal efficiency at a given flow rate for a defined particle size. The Rational Rainfall Method™ or the Probabilistic Method is used when a specific removal efficiency of the net annual sediment load is required.

Typically in the United States, CDS systems are designed to achieve an 80% annual solids load reduction based on lab generated performance curves for a gradation with an average particle size (d50) of 125 microns ( $\mu\text{m}$ ). For some regulatory environments, CDS systems can also be designed to achieve an 80% annual solids load reduction based on an average particle size (d50) of 75 microns ( $\mu\text{m}$ ) or 50 microns ( $\mu\text{m}$ ).

### Water Quality Flow Rate Method

In some cases, regulations require that a specific treatment rate, often referred to as the water quality design flow (WQQ), be treated. This WQQ represents the peak flow rate from either an event with a specific recurrence interval, e.g. the six-month storm, or a water quality depth, e.g. 1/2-inch (13 mm) of rainfall.

The CDS is designed to treat all flows up to the WQQ. At influent rates higher than the WQQ, the diversion weir will direct most flow exceeding the WQQ around the separation chamber. This allows removal efficiency to remain relatively constant in the separation chamber and eliminates the risk of washout during bypass flows regardless of influent flow rates.

Treatment flow rates are defined as the rate at which the CDS will remove a specific gradation of sediment at a specific removal efficiency. Therefore the treatment flow rate is variable, based on the gradation and removal efficiency specified by the design engineer.

### Rational Rainfall Method™

Differences in local climate, topography and scale make every site hydraulically unique. It is important to take these factors into consideration when estimating the long-term performance of any stormwater treatment system. The Rational Rainfall Method combines site-specific information with laboratory generated performance data, and local historical precipitation records to estimate removal efficiencies as accurately as possible.

Short duration rain gauge records from across the United States and Canada were analyzed to determine the percent of the total annual rainfall that fell at a range of intensities. US stations' depths were totaled every 15 minutes, or hourly, and recorded in 0.01-inch increments. Depths were recorded hourly with 1-mm resolution at Canadian stations. One trend was consistent at all sites; the vast majority of precipitation fell at low intensities and high intensity storms contributed relatively little to the total annual depth.

These intensities, along with the total drainage area and runoff coefficient for each specific site, are translated into flow rates using the Rational Rainfall Method. Since most sites are relatively small and highly impervious, the Rational Rainfall Method is appropriate. Based on the runoff flow rates calculated for each intensity, operating rates within a proposed CDS system are

determined. Performance efficiency curve determined from full scale laboratory tests on defined sediment PSDs is applied to calculate solids removal efficiency. The relative removal efficiency at each operating rate is added to produce a net annual pollutant removal efficiency estimate.

### Probabilistic Rational Method

The Probabilistic Rational Method is a sizing program Contech developed to estimate a net annual sediment load reduction for a particular CDS model based on site size, site runoff coefficient, regional rainfall intensity distribution, and anticipated pollutant characteristics.

The Probabilistic Method is an extension of the Rational Method used to estimate peak discharge rates generated by storm events of varying statistical return frequencies (e.g. 2-year storm event). Under the Rational Method, an adjustment factor is used to adjust the runoff coefficient estimated for the 10-year event, correlating a known hydrologic parameter with the target storm event. The rainfall intensities vary depending on the return frequency of the storm event under consideration. In general, these two frequency dependent parameters (rainfall intensity and runoff coefficient) increase as the return frequency increases while the drainage area remains constant.

These intensities, along with the total drainage area and runoff coefficient for each specific site, are translated into flow rates using the Rational Method. Since most sites are relatively small and highly impervious, the Rational Method is appropriate. Based on the runoff flow rates calculated for each intensity, operating rates within a proposed CDS are determined. Performance efficiency curve on defined sediment PSDs is applied to calculate solids removal efficiency. The relative removal efficiency at each operating rate is added to produce a net annual pollutant removal efficiency estimate.

### Treatment Flow Rate

The inlet throat area is sized to ensure that the WQQ passes through the separation chamber at a water surface elevation equal to the crest of the diversion weir. The diversion weir bypasses excessive flows around the separation chamber, thus preventing re-suspension or re-entrainment of previously captured particles.

### Hydraulic Capacity

The hydraulic capacity of a CDS system is determined by the length and height of the diversion weir and by the maximum allowable head in the system. Typical configurations allow hydraulic capacities of up to ten times the treatment flow rate. The crest of the diversion weir may be lowered and the inlet throat may be widened to increase the capacity of the system at a given water surface elevation. The unit is designed to meet project specific hydraulic requirements.

## Performance

### Full-Scale Laboratory Test Results

A full-scale CDS system (Model CDS2020-5B) was tested at the facility of University of Florida, Gainesville, FL. This CDS unit was evaluated under controlled laboratory conditions of influent flow rate and addition of sediment.

Two different gradations of silica sand material (UF Sediment & OK-110) were used in the CDS performance evaluation. The particle size distributions (PSDs) of the test materials were analyzed using standard method "Gradation ASTM D-422 "Standard Test Method for Particle-Size Analysis of Soils" by a certified laboratory.

UF Sediment is a mixture of three different products produced by the U.S. Silica Company: "Sil-Co-Sil 106", "#1 DRY" and "20/40 Oil Frac". Particle size distribution analysis shows that the UF Sediment has a very fine gradation ( $d_{50} = 20$  to  $30 \mu\text{m}$ ) covering a wide size range (Coefficient of Uniformity, C averaged at 10.6). In comparison with the hypothetical TSS gradation specified in the NJDEP (New Jersey Department of Environmental Protection) and NJCAT (New Jersey Corporation for Advanced Technology) protocol for lab testing, the UF Sediment covers a similar range of particle size but with a finer  $d_{50}$  ( $d_{50}$  for NJDEP is approximately  $50 \mu\text{m}$ ) (NJDEP, 2003).

The OK-110 silica sand is a commercial product of U.S. Silica Sand. The particle size distribution analysis of this material, also included in Figure 1, shows that 99.9% of the OK-110 sand is finer than 250 microns, with a mean particle size ( $d_{50}$ ) of 106 microns. The PSDs for the test material are shown in Figure 1.




Figure 1. Particle size distributions

Tests were conducted to quantify the performance of a specific CDS unit (1.1 cfs (31.3-L/s) design capacity) at various flow rates, ranging from 1% up to 125% of the treatment design capacity of the unit, using the 2400 micron screen. All tests were conducted with controlled influent concentrations of approximately 200 mg/L. Effluent samples were taken at equal time intervals across the entire duration of each test run. These samples were then processed with a Dekaport Cone sample splitter to obtain representative sub-samples for Suspended Sediment Concentration (SSC) testing using ASTM D3977-97 "Standard Test Methods for Determining Sediment Concentration in Water Samples", and particle size distribution analysis.

## Results and Modeling

Based on the data from the University of Florida, a performance model was developed for the CDS system. A regression analysis was used to develop a fitting curve representative of the scattered data points at various design flow rates. This model, which demonstrated good agreement with the laboratory data, can then be used to predict CDS system performance with respect

to SSC removal for any particle size gradation, assuming the particles are inorganic sandy-silt. Figure 2 shows CDS predictive performance for two typical particle size gradations (NJCAT gradation and OK-110 sand) as a function of operating rate.




Figure 2. CDS stormwater treatment predictive performance for various particle gradations as a function of operating rate.

Many regulatory jurisdictions set a performance standard for hydrodynamic devices by stating that the devices shall be capable of achieving an 80% removal efficiency for particles having a mean particle size ( $d_{50}$ ) of 125 microns (e.g. Washington State Department of Ecology — WASDOE - 2008). The model can be used to calculate the expected performance of such a PSD (shown in Figure 3). The model indicates (Figure 4) that the CDS system with 2400 micron screen achieves approximately 80% removal at the design (100%) flow rate, for this particle size distribution ( $d_{50} = 125 \mu\text{m}$ ).




Figure 3. WASDOE PSD




Figure 4. Modeled performance for WASDOE PSD.

## Maintenance

The CDS system should be inspected at regular intervals and maintained when necessary to ensure optimum performance. The rate at which the system collects pollutants will depend more heavily on site activities than the size of the unit. For example, unstable soils or heavy winter sanding will cause the grit chamber to fill more quickly but regular sweeping of paved surfaces will slow accumulation.

## Inspection

Inspection is the key to effective maintenance and is easily performed. Pollutant transport and deposition may vary from year to year and regular inspections will help ensure that the system is cleaned out at the appropriate time. At a minimum, inspections should be performed twice per year (e.g. spring and fall) however more frequent inspections may be necessary in climates where winter sanding operations may lead to rapid accumulations, or in equipment washdown areas. Installations should also be inspected more frequently where excessive amounts of trash are expected.

The visual inspection should ascertain that the system components are in working order and that there are no blockages or obstructions in the inlet and separation screen. The inspection should also quantify the accumulation of hydrocarbons, trash, and sediment in the system. Measuring pollutant accumulation can be done with a calibrated dipstick, tape measure or other measuring instrument. If absorbent material is used for enhanced removal of hydrocarbons, the level of discoloration of the sorbent material should also be identified



during inspection. It is useful and often required as part of an operating permit to keep a record of each inspection. A simple form for doing so is provided.

Access to the CDS unit is typically achieved through two manhole access covers. One opening allows for inspection and cleanout of the separation chamber (cylinder and screen) and isolated sump. The other allows for inspection and cleanout of sediment captured and retained outside the screen. For deep units, a single manhole access point would allow both sump cleanout and access outside the screen.

The CDS system should be cleaned when the level of sediment has reached 75% of capacity in the isolated sump or when an appreciable level of hydrocarbons and trash has accumulated. If absorbent material is used, it should be replaced when significant discoloration has occurred. Performance will not be impacted until 100% of the sump capacity is exceeded however it is recommended that the system be cleaned prior to that for easier removal of sediment. The level of sediment is easily determined by measuring from finished grade down to the top of the sediment pile. To avoid underestimating the level of sediment in the chamber, the measuring device must be lowered to the top of the sediment pile carefully. Particles at the top of the pile typically offer less resistance to the end of the rod than consolidated particles toward the bottom of the pile. Once this measurement is recorded, it should be compared to the as-built drawing for the unit to determine whether the height of the sediment pile off the bottom of the sump floor exceeds 75% of the total height of isolated sump.

## Cleaning

Cleaning of a CDS systems should be done during dry weather conditions when no flow is entering the system. The use of a vacuum truck is generally the most effective and convenient method of removing pollutants from the system. Simply remove the manhole covers and insert the vacuum hose into the sump. The system should be completely drained down and the sump fully evacuated of sediment. The area outside the screen should also be cleaned out if pollutant build-up exists in this area.

In installations where the risk of petroleum spills is small, liquid contaminants may not accumulate as quickly as sediment. However, the system should be cleaned out immediately in the event of an oil or gasoline spill. Motor oil and other hydrocarbons that accumulate on a more routine basis should be removed when an appreciable layer has been captured. To remove these pollutants, it may be preferable to use absorbent pads since they are usually less expensive to dispose than the oil/water emulsion that may be created by vacuuming the oily layer. Trash and debris can be netted out to separate it from the other pollutants. The screen should be cleaned to ensure it is free of trash and debris.


Manhole covers should be securely seated following cleaning activities to prevent leakage of runoff into the system from above and also to ensure that proper safety precautions have been followed. Confined space entry procedures need to be followed if physical access is required. Disposal of all material removed from the CDS system should be done in accordance with local regulations. In many jurisdictions, disposal of the sediments may be handled in the same manner as the disposal of sediments removed from catch basins or deep sump manholes. Check your local regulations for specific requirements on disposal.



CDS Model	Diameter		Distance from Water Surface to Top of Sediment Pile		Sediment Storage Capacity	
	ft	m	ft	m	y <sup>3</sup>	m <sup>3</sup>
CDS1515	3	0.9	3.0	0.9	0.5	0.4
CDS2015	4	1.2	3.0	0.9	0.9	0.7
CDS2015	5	1.5	3.0	0.9	1.3	1.0
CDS2020	5	1.5	3.5	1.1	1.3	1.0
CDS2025	5	1.5	4.0	1.2	1.3	1.0
CDS3020	6	1.8	4.0	1.2	2.1	1.6
CDS3025	6	1.8	4.0	1.2	2.1	1.6
CDS3030	6	1.8	4.6	1.4	2.1	1.6
CDS3035	6	1.8	5.0	1.5	2.1	1.6
CDS4030	8	2.4	4.6	1.4	5.6	4.3
CDS4040	8	2.4	5.7	1.7	5.6	4.3
CDS4045	8	2.4	6.2	1.9	5.6	4.3
CDS5640	10	3.0	6.3	1.9	8.7	6.7
CDS5653	10	3.0	7.7	2.3	8.7	6.7
CDS5668	10	3.0	9.3	2.8	8.7	6.7
CDS5678	10	3.0	10.3	3.1	8.7	6.7

Table 1: CDS Maintenance Indicators and Sediment Storage Capacities

Note: To avoid underestimating the volume of sediment in the chamber, carefully lower the measuring device to the top of the sediment pile. Finer silty particles at the top of the pile may be more difficult to feel with a measuring stick. These finer particles typically offer less resistance to the end of the rod than larger particles toward the bottom of the pile.



## CDS Inspection & Maintenance Log

CDS Model: \_\_\_\_\_ Location: \_\_\_\_\_

1. The water depth to sediment is determined by taking two measurements with a stadia rod: one measurement from the manhole opening to the top of the sediment pile and the other from the manhole opening to the water surface. If the difference between these measurements is less than the values listed in table 1 the system should be cleaned out. **Note: to avoid underestimating the volume of sediment in the chamber, the measuring device must be carefully lowered to the top of the sediment pile.**
2. For optimum performance, the system should be cleaned out when the floating hydrocarbon layer accumulates to an appreciable thickness. In the event of an oil spill, the system should be cleaned immediately.

## SUPPORT

- Drawings and specifications are available at [www.ContechES.com](http://www.ContechES.com).
- Site-specific design support is available from our engineers.

**CONTECH®**  
ENGINEERED SOLUTIONS  
800-338-1122  
[www.ContechES.com](http://www.ContechES.com)

©2017 Contech Engineered Solutions LLC, a QUIKRETE Company

Contech Engineered Solutions provides site solutions for the civil engineering industry. Contech's portfolio includes bridges, drainage, sanitary sewer, earth stabilization and stormwater treatment products. For information on other Contech division offerings, visit [www.ContechES.com](http://www.ContechES.com) or call 800.338.1122

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS A WARRANTY. APPLICATIONS SUGGESTED HEREIN ARE DESCRIBED ONLY TO HELP READERS MAKE THEIR OWN EVALUATIONS AND DECISIONS, AND ARE NEITHER GUARANTEES NOR WARRANTIES OF SUITABILITY FOR ANY APPLICATION. CONTECH MAKES NO WARRANTY WHATSOEVER, EXPRESS OR IMPLIED, RELATED TO THE APPLICATIONS, MATERIALS, COATINGS, OR PRODUCTS DISCUSSED HEREIN. ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND ALL IMPLIED WARRANTIES OF FITNESS FOR ANY PARTICULAR PURPOSE ARE DISCLAIMED BY CONTECH. SEE CONTECH'S CONDITIONS OF SALE (AVAILABLE AT [WWW.CONTECHES.COM/COS](http://WWW.CONTECHES.COM/COS)) FOR MORE INFORMATION.

The product(s) described may be protected by one or more of the following US patents: 5,322,629; 5,624,576; 5,707,527; 5,759,415; 5,788,848; 5,985,157; 6,027,639; 6,350,374; 6,406,218; 6,641,720; 6,511,595; 6,649,048; 6,991,114; 6,998,038; 7,186,058; 7,296,692; 7,297,266; related foreign patents or other patents pending.

# HANCOCK ASSOCIATES

Surveyors | Engineers | Scientists